

LHC operation and objectives for 2010/2011

Mike Lamont





Rough outline

- Introduction
- Outline operational sequence
- Mechanics
 - sequencer, procedure
 - software
 - settings
- Key systems
 - collimation, beam dump, RF..
- Machine protection
- Brief overview of beam through the sequence
 - losses, emittance, lifetimes, optics



Commissioning recap

- Magnetically and optically well understood
 - Excellent agreement with model and machine
- Magnetically reproducible
 - Important because it means optics and thus set-up remains valid from fill to fill
- Aperture clear and as expected
- Excellent performance from instrumentation and controls
- Key systems performing well
 - Injection
 - Beam dump
 - Collimation
 - Machine protection



Commissioning recap

- Ramp and squeeze
 - In general under control
- Inject, ramp and squeeze multiple bunches and bring them into stable beams.
- Keep them there
 - Maximum fill length – a remarkable 30 hours
- And do it again
- Routinely over-inject nominal bunch intensities and ramp them to 3.5 TeV, squeeze them, bring them into collisions and deliver stable beams.

A remarkably successful initial commissioning period

which is still ongoing... [NB]



Operational modes

- Physics production
- Machine development
 - End of fill MD [potentially with unsafe beam]
 - Dedicated commissioning periods
 - Ad hoc inter-fill system commissioning
 - Validation runs – loss maps, dumps with beam in abort gap
- Access/interventions as required
- Technical stops
 - 4 days every 6 weeks
 - 2 months over Christmas

Might question the rigour with which we pass between these modes



Comments

- Haven't fully come out of commissioning mode yet.
- In proton physics Operations crew drive the machine through the full cycle...
- ... punctuate regular operations with periods of dedicated beam commissioning system commissioning
- **“Collegiate atmosphere”**. Still considerable presence in control room of sub-system experts tracking up, improving, tweaking. Some of this is passive, some can impact beam.
 - Beam instrumentation, Beam transfer, Feedbacks etc...
 - “I’m just going to make a transparent change to the voltage ramp” YESTERDAY
- Other teams also present intermittently
- Controls/software improvements/bug fixes still common
- **Relaxed attitude to testing**



Organization

- Operations
 - 6 highly skilled machine coordinators who pair up and take 1 out 3 weeks
 - 8 engineers-in-charge who run the show in the CCC while on shift
 - 7 operators – experienced (LEP) individuals
- Restricted Machine Protection Panel
 - ~10 cross system experts
 - Weigh the odds, **set intensity envelope**
- Physics coordinator
 - Italian with eyes firmly fixed on 1 fb^{-1}
- LHC commissioning working group
 - Discussions of a technical nature
- LMC
 - Decisions



The sequence


PROTON PHYSICS

- Bread and butter mode of operation
- In which is concentrated high intensity
- Task by task breakdown of everything that needs to be done to drive LHC through the nominal operational cycle



Nominal cycle


Globally the machine state is fairly well described by machine mode/beam mode combination





Sequencer

Info Panel



REFRESH SEQUENCES

LHC MODE

Accelerator Mode **Beam Mode**

SHUTDOWN NO BEAM

AVAILABLE SEQUENCES

- CHANGE LHC MODES
- CHECK ALL CRITICAL SETTING
- CHECK COLLIMATOR INJECTIO
- CHECK COLLIMATOR PHYSICS
- DRIVE OUT-OF-BEAM SETTING
- DRIVE TOTEM ROMAN POTS
- END ADJUST HANDSHAKE
- END BEAM_DUMP HANDSHAK
- END INJECTION HANDSHAKE
- LHC NOMINAL SEQUENCE (B1
- ONDULATOR L4 U_RES RESET
- ONDULATOR R4 U_RES RESET
- PRE-CYCLE LHC EIS_BEAM
- PRE-CYCLE LHC MAGNETS FO
- PRECYCLE S12
- PRECYCLE S23

Filter sequences by category:

All Development

Physics Dry Run

Equipment te... MD

LHC NOMINAL SEQUENCE (B1 & B2)

SEQUENCE CONTROL PANEL

Sequence Information

Name	Description	Category	Created_by
LHC NOMINAL SEQUENC...	LHC Nominal sequenc...	PHYSICS	LASSE, RA...

Play Sequence

Run Pause Resume Abort Clear Status

SUB_SEQUENCE CONTROL PANEL

Sub_sequence Information

Sta...	displayName	Description	Category
...	END OF INJECTION	End of injection	PHYSICS
...	PREPARE RAMP	Prepares LHC for the ramp	PHYSICS
...	RAMP-V01	RAMP-V01	PHYSICS
...	SQUEEZE TO 3.5 M	SQUEEZE TO 3.5 m of all IPS	PHYSICS
...	PREPARE COLLISIONS	PREPARE COLLISIONS FROM 3.5 M SQUEEZE...	DEVELOP...
...	RAMP DOWN - PRECYCLE COMB...	RAMP DOWN - PRECYCLE COMBO V01	PHYSICS

Play Sub_sequence

Run Pause Resume Interrupt Clear Status

PREPARE RAMP ON ERROR

COMPONENTS CONTROL PANEL

Component Information

De...	Ty...	Name	Status	Devic...	Hw...	Context	Command	OnError	OnR...	Id
		INFORM DETABLE WITH SPECIAL EVENTS FOR K...	...					STOP	STOP	6...
	T	CHECK RF FREQUENCY PROGRAMS LINKED ON					STOP	STOP	6...
	T	TRIM ALL CAVITY Q TO 30000 (for 10A/s ramp)	SKIP...			LHC.USER...		STOP	STOP	6...
	T	TRIM ALL CAVITY Q TO 60000 (for 2A/s ramp)	...			LHC.USER...		STOP	STOP	6...
	T	INCORPORATE INJECTION TRIMS INTO RAMP	...					STOP	STOP	6...
	T	INCORPORATE RF FREQ INJECTION TRIMS INTO					STOP	STOP	6...
	T	MAKE LHC.USER.RAMP RESIDENT	...			LHC.USER...		STOP	STOP	6...
	T	LOAD RAMP SETTINGS IN PC&RF FGC	...					STOP	CON...	1...

Play Component

Step Run Stop Interrupt Jump Clear Status



& 6 pages of procedure

Over-injection

- **ADT phase shift to injection** (if not already done before)
- **Ask injectors to switch to LHC INDIV and to copy over transfer line settings**
- Check that the SPS has longitudinal emittance blow up on and at the nominal settings: (0.6eV.s which corresponds to a bunch length of ~1.6ns)
- **Mask BLMs** in 2 and 8 (masking is still required)
- Change **BPM sensitivity** through YASP (LOW for nominal bunches, HIGH for probe and bunch intensities below $3\text{-}4 \times 10^{10}$)
- Change **BQM attenuation**: three buttons available: pilot, intermediate (indiv up to some 10^{10}), nominal (10^{11})
- Change beam mode to INJECTION PHYSICS BEAM
- **ADT:**
 - **CHECK with the ADT application in the CCM that the ADT system is switched on, i.e. "RF ON". If it is off, in level 1 or level 2, switch it to "RF ON".**
 - *The gain of the feedback is controlled by 8 FGC functions. These have to be correctly started at the ramp and set back to the injection value. Pending further studies the injection values are -20 dB except for the vertical beam 2 plane where -24 dB is programmed. During the ramp the gain is linearly increased to -3 dB except vertical beam 2 which ramps to -7 dB. Beta functions at vertical beam 2 are higher so a lower gain is used.*
 - **VERIFY in the working sets (RF-LHC:ADT) that the damper off and on are enabled for the four timing cards in question, i.e. eight knobs to verify, Damper H/V B1/B2 On/Off, all enabled;** if they are disabled then this has the effect that the action of the corresponding HX.ADTSTART-CT and HX.ADTSTOP-CT on the damper on/off switch located inside the damper lowlevel system is masked.
 - *The timing delay is not really important, this is an expert setting to be used if RF teams make local observations synchronised with the On or OFF command.*
 - *The damper system is currently configured to close the loop automatically on turn 3 after injection. In fact the beam in signal opens the feedback loop, then an internal turns counter starts and will close the feedback loop at turn 3. This delay allows for filter transients that will not be put onto the beam.*
 - *The damper feedback loop can be opened ("switched off") by sending a timing event, HX.ADTSTOP-CT; it can be switched on again if wanted, using the HX.ADTSTART-CT event. The Beam_in signal will briefly open the loop (if it was closed) and activate the turns counter to issue the ON on turn 3 (see point 4 above).*
 - **OBSERVE with the fixed display "Injection oscillations what happens.** Currently the damper is configured to not act on the pilot, you should see flat lines. For the nominal bunch a damped oscillation should be seen.
- **Clear "circ bunch config" in Injection sequencer, and then request injection**
- For these injections, make sure that "Circ bunch config autoClear" in unticked in the Injection Sequencer, or else the circulating bunch configuration will only contain the latest injection per beam.
- Bunch positions can be verified through LHC BQM display (LHC Control -> Beam Measurements -> Beam Quality Monitor)
- **Measure emittance H&V** of both beams with the wire scanner
 - Parameters to be used for the wire scan, both beams both plane: **Gain:1300V, filter T_1_PER_CENT for B1 H/V and B2 H, filter T_10_PER_CENT for B2 V**



Pre-cycle

Aim: reproducible magnetic machine

- Coming back from recovery
 - Full pre-cycle of all magnetic circuits
 - Main dipoles, quadrupoles to 6 kA
 - “de-Gauss” corrector circuits
 - IPQs, IPDs, ITs to around 3.5 TeV level
- After stable beams
 - Rampdown/precycle combination
 - All main circuits from 3.5 TeV/3.5 m to below injection current
 - “de-Gauss” corrector circuits

Largely successful



Pre-flight checks etc

- Beam dump XPOC
- Check critical settings
 - beam dump - various, injection kicker, BETS, IPOC, abort gap, SMP energy limits, collimators
 - BLM
- BLM sanity checks
- BIS pre-operational checks
- BI checks
- Injection kickers conditioning
- Load collimator and protection devices energy thresholds
- Set thresholds for roman pots



Pre-injection

- Set power converters, RF, ADT to injection level
- Condition injection kickers
- Injection handshake with experiments
- Collimators to parking
- RF-LBDS frequency link check
- RF beam control resynch
- Resynchronize to SPS if needed
- Ask the SPS to check beam parameters
- load BI defaults and tune viewer injection settings
- check frequency lock



Injection – general

Complex dance of hardware, timing, RF, interlocks etc.

- Transfer lines in good shape after big effort.
- Re-phasing, synchronization & transfer & capture
- Inject pilot, measure and correct
- Over-inject witness pilot with nominal bunches
- Injection process controls semi-automatically by injection sequencer
- Beam quality check in SPS
 - vetos extraction
- Injection quality check in LHC
 - inhibits further injection, latches, easily unlatched

Full program of beam based checks performed: injection protection (TDI etc), transfer line collimators, TDI positioning, aperture, kicker waveform etc. have been performed.



Injection 1/2

- Collimators are set to injection positions
- Arm LBDS
- Change accelerator mode to PROTON PHYSICS.
- Change beam mode to INJECTION PROBE
- Set BQM attenuation to probe
- Increment fill number
- Inject 1 bunch for beam 1 and beam 2
- Measure and correct RF injection phase
- Verify Injection synchro error :
- Correct orbit with respect to reference**
 - "450 GeV collimator setup, separation is ON, low int." (for 2-3x10¹⁰) ,
 - "450 GeV collimator setup, separation is ON, high int." (for 8-10x10¹⁰)



Injection 2/2

- Verify Injection oscillations
- Measure and set fractional tunes to 0.28/0.31
- Measure and set chromaticity to $\sim 4, 4$
- Dump and re-inject if you have done corrections of the synchro error, injection phase or injection oscillations to check your trims



Over injection

- Change beam mode to: INJECTION PHYSICS BEAM
- Ask injectors to switch to LHC INDIV for single bunch injection or LHC2 for multi bunch injection and to copy over transfer line settings if trims have been done.
- Check that the SPS has longitudinal emittance blow up on and at the nominal settings: (0.6eV.s which corresponds to a bunch length of ~ 1.6 ns)
- Mask BLMs in 2 and 8 (masking is still required)
- Change BPM sensitivity through YASP (LOW for nominal bunches, HIGH for probe and bunch intensities below $3-4 \times 10^{10}$)
- Change BQM attenuation: three buttons available: pilot, intermediate (indiv up to some 10^{10}), nominal (10^{11})



Injection sequencer

RB: lhcop

Injection schemes

GRP : ALL

AbortGapTest

Alternating 43 bunches sche...

B1_bunch_scan_LBDS

B2_AbortGapStudies

B2_bunch_scan_LBDS

EARLY-IONS

Multi_12b_8_8_8

Multi_13b_8_8_8

Multi_24b_16_16_16

Multi_25b_16_16_16

Multi_25b_16_16_16_hyb

Multi_2b_1_1_1

Multi_48b_36_16_36

Multi_6b_4_4_4

Multi_9b_6_6_6

Multi_inj_MD

Multi_inj_MD12

Multi_inj_MD2

Nominal25ns

Nominal75ns

Pilot R1

Pilot R2

Single_10b_4_2_4

Single_10b_4_2_4_b

Single_10b_4_2_4_rot

Refresh list

load >>

Circ bch config autoClear

Loop

Ignore IQC

Set Scheme Active

Start

Step

STOP

Display circ Bunch config

Clear active scheme

Clear circ bunch config B1

Clear circ bunch config B2

name	order	ring	RFBucket	NbrBnches	BnchSpac(ns)	BnchInt[E9]	PartType	PS btchs
B1_Multi4Btch_bu1	1	RING_1	1	4	2500	100	0	4
B2_Multi4Btch_bu1	2	RING_2	1	4	2500	100	0	4
B1_Multi4Btch_bu4001	3	RING_1	4001	4	2500	100	0	4
B2_Multi4Btch_bu4001	4	RING_2	4001	4	2500	100	0	4
B1_Multi1Btch_bu8001	5	RING_1	8001	1	2500	100	0	1
B2_Multi1Btch_bu8501	6	RING_2	8501	1	2500	100	0	1
B1_Multi4Btch_bu8941	7	RING_1	8941	4	2500	100	0	4
B2_Multi4Btch_bu8911	8	RING_2	8911	4	2500	100	0	4
B1_Multi4Btch_bu12941	9	RING_1	12941	4	2500	100	0	4
B2_Multi4Btch_bu12911	10	RING_2	12911	4	2500	100	0	4
B1_Multi4Btch_bu17851	11	RING_1	17851	4	2500	100	0	4
B2_Multi4Btch_bu17851	12	RING_2	17851	4	2500	100	0	4
B1_Multi4Btch_bu21851	13	RING_1	21851	4	2500	100	0	4
B2_Multi4Btch_bu21851	14	RING_2	21851	4	2500	100	0	4

Change bunch int for all requ...

check reservation: cwo-ccc-d4lc.cern.ch

Take the reservation

Request LSA mastership: LSA is not master

Remove LSA mastership


refresh Mastership state

<p>IQC_RESULT BEAM1</p> <p>NO DATA</p>	<p>UNLATCH B1</p>	<p>LATCH STATUS B1</p>
<p>IQC_RESULT BEAM2</p> <p>NO DATA</p>	<p>UNLATCH B2</p>	<p>LATCH STATUS B2</p>



Injection - nominal

- Change beam mode to INJECTION PHYSICS BEAM
- Clear "circ bunch config" in Injection sequencer, and then request injection
- For these injections, make sure that "Circ bunch config autoClear" is unticked in the Injection Sequencer, or else the circulating bunch configuration will only contain the latest injection per beam.
- Bunch positions can be verified through LHC BQM display
- Measure emittance H&V of both beams with the wire scanner



Ramp


- 450 GeV – 3500 GeV
 - 17 minutes
 - Parabolic – exponential – linear – parabolic to minimize effects of snapback and duration
 - Snapback correction pre-programmed for b2,b3,b4,b5,a2,a3 based on FIDEL predictions for full decay
- Preloaded functions to power converters, collimators, RF
 - ramp initiated with timing event
- **Tune and orbit feedback** considered mandatory
- Transverse feedback on
- Fill-to-fill feed-forward performed intermittently



Ramp


Remarkably smooth so far

Feedbacks – mission critical and in general working very well - have had some issues – damping to robustness





Ramp - collimators





Flat top – prepare for squeeze

- Go to FLAT TOP mode
- Turn off the Transverse feedback
- Switch Tune FB OFF
- Stop the orbit feedback
- Turn off continuous chromaticity measurement (if switched on for the ramp)
- Measure and correct chromaticity (dp/p 0.2 per mille) and tune.
- Check that the coupling is <0.005 otherwise correct it with COUPLING KNOB -> LHCBEAMn/CMINUS_IM.IP1 and LHCBEAMn/CMINUS_RE.IP1

decay observed but not handled rigorously



Flat top – prepare for squeeze

- Re-measure and correct orbit
 - wrt "Reference for collimation at 3.5 TeV separated", (SEPARATED-3.5TeV-HIGH_INT in REF catalog).
- Correct radial position
- Start orbit acquisition/saving with a YASP
- Start the beta * monitoring tool
- Open windows of tune viewers (H: 0.295 - 0.315 ; V: 0.315 - 0.325)
- trim the TUNE-FB reference for tune feedback to collision tunes with the continuous tune viewer application
- go in FB/Trim tab, enter the right values (64.31 and 59.32) and press H&V button



Squeeze

- From 11-10-11-10 to 3.5 m **all points**
 - (over squeezed in Alice)
- **Collisions tunes (.31/.32)**
- Tune feedback on
- Orbit feedback on [interaction regions disabled]
- Tune, Q', **coupling**, orbit, optics corrections
- Squeeze in two stages
 - Stop in middle to set tertiary collimators to 3.5 m values

Relatively smooth – occasional soft lifetime dips



Collide

- Beams brought into collisions at same time via functions which collapse the separation bumps (~ 100 s)
 - fine IP positioning included – Alice to ~ 3.8 sigma separation
 - orbit, tune feedback off
 - transverse feedback on, octupoles on
 - nominal tunes
- Tertiary collimators to stable beam positions after bump collapse from sequencer
- Move to stable beams if lifetime, losses, luminosities look reasonable
- Luminosity optimization
 - Powerful application – allows movement of beams at IP, and as a result the tertiary collimators
- Stable beams – very stable




Operations above 1 MJ

- Case 1: Loss of beam due to procedural error or sub-system failure
 - in principle caught by BIS – very extensively tested - positive experience so far
- Case 2: Putting the machine in a dangerous state so that if something does go wrong it is not properly protected
 - Collimation, protection devices in wrong positions, orbit at collimators,
 - Local orbit bumps, optics errors
- These can be:
 - genuine mistakes
 - incomplete sequence execution
 - complacency and/or a gung ho attitude
 - experts messing around when they shouldn't
 - equipment failures or glitches
 - ...



Case 2, sub clause a

- The collimators and protection devices must be in position at all times
- The hierarchy must be respected
- The collimators and protection devices are positioned with respect to the closed orbit
- Therefore the closed orbit must be in tolerance at all times. **This includes the ramp and squeeze.**
 - **Orbit feedback becomes mandatory**
 - **Interlocks on beam positions**
- If these rules are not respected something will get broken eventually




CONTROLS



LSA (LHC Software Architecture)

- Standard architecture for high level software
- Middle tier designed to provide services to allow effective accelerator control. Technology now well established.
- Data model & business layer are common for all accelerators
- Database design and implementation well established

- 21st century version control and release mechanism
- Some unit testing, limited device based test environment
- No rigorous testing on machine of new releases



LSA Core 1

- Optics & Magnet model
 - Machine layout, device configuration
 - Optics, Twiss
 - Transfer functions, harmonic errors etc.
 - On-line model
- Settings generation
 - Settings span full parameter space
- Settings management & trim
 - Management of settings for all parameters through fullcycle
 - Coherent modifications
 - History of changes and rollback.



[LSA] Core 2

- Hardware exploitation
 - Equipment control/settings
 - Power Converters, RF, Collimators, Kickers, Beam Dump etc.
 - Equipment monitoring
- Run control
 - Hypercycle: pre-cycle, injection, ramp and squeeze
 - Sequencer, Mode etc.
- Timing
 - Timing events, event tables, telegrams, Safe Beam Parameters, injection requests...
 - RF: Bucket selection, pre-pulses
 - BST
 - Triggered measurement acquisition...




Standard services

- Security
 - Role Based Access Control (RBAC)
 - Restrict access to accelerator devices
 - Developed in the framework of the LAFS collaboration
 - Management of Machine Critical Settings (MCS)
- Post mortem
- Logging
- Fixed displays
- Communication with experiments
- Software Interlocks
- Daemons
- Measurement facilities



Services - Hardware

	Application	XPOC	Analog Acquisition	Alarms	SIS	MCS	PM	Timing	RBAC
INJECTION KICKERS	X	X	X	X		X	X	X	X
BEAM DUMP	X	X	X	X		X	X	X	X
POWER CONVERTERS	XX			X	X		X	X	X
COLLIMATORS	X			X	X	X	X	X	X
RF	XX		X	X	X		X	X	X
TRANVERSE FB	X		X	X			X	X	X
MAGNETS	XX			X			X		
MKQA etc	X			X	X		X	X	X
WARM MAGNETS	X			X	X		X	X	X
RADIATION MONITORS				X			X		
SPECTROMETERS				X	X		X	X	



Services - Instrumentation

	Priority	Conc	Settings	State	Logging	PM	SIS	MCS	Application	FDisplay	Daemon
BPM [D,I]	1	X			X	X			XX	X	
BLM	1	X	X		X	X		X	XX	X	
BCT [DC, FD, FR]	1				X	X				X	
BTV	1		X	X	X		X		X	X	
Rest Gas [BGI]	3		X	X	X		X		X		
Sync. Rad [BSRA]	1		X	X	X		X		X		X
Wire Scanners [BWS]	2		X		X		X		X		X
Luminosity [BRA,S,G]	1				X				X	X	X
Tune [BQBBQ]	1		X	X	X	X			XX		
Tune [BQHT]	2				X				X		
AGM [BSRA]	2				X				X	X	
Schottky [BQS]	2				X				X		X
BST [BOB]	1										



BEAM THROUGH THE CYCLE



Nominal cycle – hot spots – 2008 guess

Injection	Losses at injection: injection oscillations, RF capture
Injection plateau	Big beams, lower dynamic aperture, full buckets, un-captured beam, long range beam-beam, crossing angles, persistent current decay Won't be pretty. 10 hours lifetime will be good
Start ramp	Un-captured beam lost immediately we start the ramp (~5% total) Snapback: chromaticity, tunes all over the place
Ramp	Things should calm down, assume 10 hour lifetime
Squeeze	Tunes, chromaticity, collimator, TCDQ adjustments – expect some lifetime dips
Collide	Beam finding, background optimization (?)
Physics	Collisions, beam-gas, halo production etc.
Adjust	Squeezing IR2, roman pot adjustment
Dump	Should be squeaky clean, very occasion pre-fire...



Beam current during fill 25/08/2010


Timeseries Chart between 2010-08-26 01:00:00.000 and 2010-08-26 06:00:00.000 (LOCAL_TIME)

LHC.BCTFR.A6R4.B1:BEAM_INTENSITY

LHC.BCTFR.A6R4.B2:BEAM_INTENSITY

RPTE.UA23.RB.A12:1_MEAS





Beam current FBCT / DBCT

Timeseries Chart between 2010-08-26 01:00:00.000 and 2010-08-26 06:00:00.000 (LOCAL_TIME)





Beam current during start ramp 25/08/2010

Timeseries Chart between 2010-08-26 01:00:00.000 and 2010-08-26 06:00:00.000 (LOCAL_TIME)


LHC.BCTDC.A6R4.B1:BEAM_INTENSITY

LHC.BCTDC.A6R4.B2:BEAM_INTENSITY

LHC.BCTFR.A6R4.B1:BEAM_INTENSITY

LHC.BCTFR.A6R4.B2:BEAM_INTENSITY

RPTE.UA23.RB.A12:I_MEAS






Beam current during round off 25/08/2010

Timeseries Chart between 2010-08-26 01:00:00.000 and 2010-08-26 06:00:00.000 (LOCAL_TIME)

LHC.BCTFR.A6R4.B1:BEAM_INTENSITY

LHC.BCTFR.A6R4.B2:BEAM_INTENSITY

RPTE.UA23.RB.A12:1_MEAS







New Record Lumi

26-Aug-2010 04:24:46 Fill #: 1303 Energy: 3500 GeV I(B1): 5.51e+12 I(B2): 5.23e+12


	ATLAS	ALICE	CMS	LHCb
Experiment Status	PHYSICS	NOT READY	STANDBY	PHYSICS
Instantaneous Lumi (ub.s) ⁻¹	10.456	0.138	10.719	8.882
BRAN Luminosity (ub.s) ⁻¹	9.573	0.137	7.914	7.327
Fill Lumiosity (nb) ⁻¹	2.0	0.0	2.0	1.7
BKGD 1	0.018	0.019	20.644	0.197
BKGD 2	16.000	0.290	0.002	4.773
BKGD 3	5.000	0.008	0.003	0.106

LHCb VELO Position **OUT** Gap: 58.0 mm STABLE BEAMS TOTEM: **STANDBY**






Last two weeks



25b



48b



50b



W34

Peak luminosity – stable beams	$1.03 \times 10^{31} \text{ cm}^{-2}\text{s}^{-1}$
Average luminosity – stable beams	$7.08 \times 10^{30} \text{ cm}^{-2}\text{s}^{-1}$
Total stable beam time	67.6 hours (40.2%)
Delivered luminosity	1724 nb^{-1}
Luminosity lifetime	~25 hours

Hübner factor ≈ 0.29

Including some dedicated bunch train commissioning


	Availability	Physics
W33	47.3%	22%
W34	~85%	40.2%

- **Remarkable machine availability:** impressive performance of cryogenics, QPS, converters, RF, instrumentation, collimators, injectors...
- **Very effective** use of available time



Measured Cleaning at 3.5 TeV


(beam1, vertical beam loss, intermediate settings)






Optics

- Stunningly stable





2010




2010 – main aims

- Clear priority to lay the foundations for 2011 and delivery of 1 fb^{-1}
- Have performed a safe, phased increase in intensity with validation and a running period at each step
- Gained solid operational experience of [not faultlessly] injecting, ramping, squeezing and establishing stable beams
- Need to finish commissioning of some critical sub-systems
 - E.g. Abort gap monitoring, abort gap cleaning, transverse damper
- Aimed for steady running at or around 1 MJ over the summer...



Bunch trains

■ Next up



through the cycle




Ramp, squeeze and collide – high intensity

- 1 nominal bunch
- Reference orbit nailed
- Adjust collimators and dump protection at flat-top
 - setup for momentum cleaning of beam 2
- Qualify collimation and protection with **loss maps** at 3.5 TeV before squeeze. Asynchronous dump test
- Re-establish **reference orbit** at 3.5 TeV after squeeze.
- Perform required re-setup of **ring collimators** (depends on orbit changes).
- Qualify collimation and protection with **loss maps** at 3.5 TeV after squeeze. **Asynchronous dump test.**



High intensity bunch trains

- Push through 4, 12, 24 bunches per beam
- Monitor & adjust
 - ADT
 - Longitudinal blow-up
 - RF
 - Feedbacks
- First stable beams: 3x4



Brennan Goddard, Malika Meddahi


STEPS	# bunches/beam	# SPS bunch trains	# SPS bunches/train	# bunches/injection	# injections	E/inj [MJ]	I/inj (e12)	E/total (MJ @ 3.5 TeV)
A	48	1	4	4	12	0.03	0.4	2.69
	48	1	8	8	6	0.06	0.8	2.69
	96	1	8	8	12	0.06	0.8	5.38
	96	1	12	12	8	0.09	1.2	5.38
	144	1	12	12	12	0.09	1.2	8.06
B	144	2	12	24	6	0.17	2.4	8.06
	192	2	12	24	8	0.17	2.4	10.75
	240	2	12	24	10	0.17	2.4	13.44
	288	2	12	24	12	0.17	2.4	16.13
	336	2	12	24	14	0.17	2.4	18.82
C	396	3	12	36	11	0.26	3.6	22.18



An older estimate

Table 2: Projected intensity increases and associated performance in 2010 with around nominal bunch intensity (1.1×10^{11}). All numbers approximate.

N_b	N_c	I_{tot}	Energy per beam [MJ]	Peak Luminosity [$\text{cm}^{-2}\text{s}^{-1}$]	Days	Int. Lumi [pb^{-1}]	Approx. date
3	1	3×10^{11}	0.2	2.5×10^{29}	5	0.03	W4 June
4	2	4×10^{11}	0.2	5.1×10^{29}	5	0.07	W1 July
8	4	8×10^{11}	0.4	1.0×10^{30}	5	0.13	W2 July
20	10	2×10^{12}	1.1	2.5×10^{30}	10	0.6	W3/4 July
24	16	2.4×10^{12}	1.5	4.9×10^{30}	20	1.7	August
48	32	4.8×10^{12}	3.0	9.8×10^{30}	10	1.7	September
96	96	9.6×10^{12}	5.9	2.9×10^{31}	10	5.1	September
144	144	1.4×10^{13}	8.9	4.4×10^{31}	10	7.6	October
192	192	1.9×10^{13}	11.8	5.9×10^{31}	10	10.1	October
240	240	2.4×10^{13}	14.8	7.3×10^{31}	10	12.7	November





Target of some aggressive programming




Schedule

Very AGGRESSIVE schedule!

Assuming excellent machine availability



TS postponed from w42 to w43



Early Heavy Ion Run Parameters

John Jowett

		Early (2010/11)	Nominal
\sqrt{s} per nucleon	TeV	2.76	5.5
Initial Luminosity (L_0)	$\text{cm}^{-2}\text{s}^{-1}$	1.25×10^{25}	10^{27}
Number of bunches		62	592
Bunch spacing	ns	1350	99.8
β^*	m	2	0.5
Pb ions/bunch		7×10^7	7×10^7
Transverse norm. emittance	μm	1.5	1.5
Luminosity half life (1,2,3 expts.)	h	$\tau_{\text{IBS}}=7-30$	8, 4.5, 3

Initial interaction rate: 100 Hz (10 Hz central collisions $b = 0 - 5$ fm)

$\sim 10^8$ interaction/ 10^6 s (~ 1 month)

In two years: 2×10^7 central collisions, integrated luminosity 25 fb^{-1}



2011



2011 Q1&2

	Jan				Feb			Mar					
Wk	52	1	2	3	4	5	6	7	8	9	10	11	12
Mo		3	10	17	24	31	7	14	21	28	7	14	21
Tu													
We													
Th		Technical stop											
Fr													
Sa	1												
Su													



LHC closed (Jan 4-5, Feb 1-6)
 Re-commissioning with beam (Mar 7-8)
 Technical stop (Mar 11-12)

	Apr			May					June					
Wk	13	14	15	16	17	18	19	20	21	22	23	24	25	
Mo	28	4	11	18	Easter	2	9	16	23	30	6	Whit	13	20
Tu														
We														
Th										Ascension				
Fr				G. Friday										
Sa														
Su					May day									

Start non-LHC physics program (Apr 15)



2011 Q3&4





2011 – 3.5 TeV

- Restart 4th February
- 9 months protons, 4 weeks ions
- Integrated luminosity target driven – 1 fb⁻¹
- Need to run flat out above 1e32 cm⁻²s⁻¹

Table 4: Possible 2011 ball-park scenarios with 1.1×10^{11} protons per bunch.

N_b	β^* [m]	Energy per beam [MJ]	Peak Luminosity [cm ⁻² s ⁻¹]	Int. Lumi per month [pb ⁻¹]
432	3.5	27	1.3×10^{32}	61
432	2.5	27	1.8×10^{32}	85
796	3.5	49	2.4×10^{32}	113
796	2.5	49	3.4×10^{32}	157



Conclusions

- Very successful period of initial commissioning
 - 5 months since first collisions at 3.5 TeV
 - Commissioning is still ongoing...
- All key systems performing remarkably well – some hugely complex systems out there.
 - Some commissioning still required, issues still to address
- Performance with beam (losses, lifetimes, luminosity, emittance growth etc.) is very encouraging.
- Have bedded in the nominal cycle but it remains a complex procedure with a number of critical manual actions required – mistakes still very much possible
- We don't yet have a MJ culture.
- Aggressive planning for the rest of 2010
- Smooth running with 10s MJ in 2011 foreseen