

# Status & Prospects of the ALFA stations

LHC Lumi Days, January 13-14, 2010  
K.Hiller, DESY on behalf of ATLAS


## Outline:

- 1) Principle of the luminosity measurement with ALFA
- 2) Detector performance from test beam measurements
- 3) Status of the installation in the LHC tunnel
- 4) Prospects for data taking 2011 and beyond

# The 2 ways of luminosity measurement

## Direct from machine parameters

$$L = \frac{f \cdot N_1 \cdot N_2}{A}$$



### Input:

- beam currents
- crossing area (e.g. from transverse beam scans)

### Precision:

- ~ 10% at LHC startup,
- ~ 5% with best systematics

## Indirect from rates via $L = N / \sigma$

$$L = \frac{(N_{sig} - N_{bg})}{(\epsilon \cdot acc \cdot \sigma)}$$

### Input:


- cross sections e.g. W/Z from PDFs, or  $\sigma_{tot}$  via optical theorem
- efficiency, acceptance and backgrounds

## ALFA concept to determine the luminosity from small angle proton scattering:

- 1) total + elastic rates + optical theorem limited due to ATLAS  $\eta$  range
- 2) elastic rate +  $\sigma_{tot}$ , e.g. TOTEM
- 3) elastic rate in the Coulomb-Nuclear Interference region

# Concept of the ALFA measurement

Elastic scattering in the Coulomb-Nuclear interference region:



## Measurement program:

- 1) start from a well-known theoretical rate dependence
- 2) measure unbiased elastic rate
- 3) fit luminosity and 3 other free parameters to  $dN / dt$

Main conditions to reach the Coulomb region  $|t| < 10^{-3} \text{ GeV}^2$




- Detector positions far from IP
- Special beam settings
- Detectors close to beam

$$\frac{dN}{dt} \approx L \pi \left| -\frac{2\alpha}{|t|} + \frac{\sigma_{tot}}{4\pi} (i + \rho) \exp(-b|t|/2) \right|^2$$

$L$  = luminosity ,  $\sigma_{tot}$  = total cross section


$\rho = \text{Re } f_{el} / \text{Im } f_{el} (t = 0)$ ,  $b$  = nuclear slope

# ALFA stations in the LHC tunnel



Multi-layer fiber detectors readout by Multi-Anode PMTs in Roman Pots

2 stations on both sides far from the IP approaching the beam in the vertical coordinate.



# High- $\beta^*$ optics for ALFA runs

- Use of standard collision optics impossible due to beam divergence at IP:

$$\sigma(y') = \sqrt{\varepsilon / \beta^*}, \text{ with emittance } \varepsilon \text{ and } \beta^* \text{ at IP}$$

- Distance of scattered proton from nominal beam line depends on  $y^*$  and  $\Theta^*$ :

$$y = \sqrt{\beta / \beta^*} (\cos \Psi + \alpha^* \sin \Psi) y^* + \sqrt{\beta \beta^*} \sin \Psi \theta_y^*$$

In the left-right difference of  $y$ -coordinates the unknown vertex offset cancels

$$(y_L - y_R) = 2 \Theta^* \sqrt{\beta \beta^*} \sin(\Psi)$$

- For phase advance  $\psi = 90^\circ$  parallel-to-point focusing possible:  
protons with same angles at IP focus to same position  $y$  in ALFA


## Special runs for ALFA with:

- Small beam divergence at IP by  $\beta^* = 2625\text{m}$ ,  $\varepsilon = 1\mu\text{m rad}$ ,
- Vertical phase advance  $\psi = 90^\circ$
- 0-crossing that scattered protons hit the detectors
- Moderate number of bunches

All this implies running at low luminosity  $L \sim 10^{-27-28} \text{ cm}^{-2}\text{s}^{-1}$

# Estimate of luminosity precision

Simulation of elastic protons including beam optics and detector effects and detectors in a distance of  $12\sigma = 1.5$  mm to the beam.




Variable	Input	Uncertainty %
Statistics	6.6 million, 1.5mm	1.77
Beam divergence	+/-10%	0.31
Crossing angle	+/- 0.2 $\mu$ rad	0.18
Optical functions	$\beta^*$ 1%, $\beta$ 2%	0.59
Phase advance	+/- 0.5 degree	1.0
Detector alignment	+/- 10 $\mu$ m	1.3
Acceptance	+/- 10 $\mu$ m	0.52
Resolution	30 $\mu$ m	0.35
Backgrounds		1.1
Total uncertainty		2.82

**→  $\Delta L / L \sim 3\%$  seems to be possible**



# ALFA fiber trackers

## Concept

- $2 \times 10$  U planes
- $2 \times 10$  V planes




Diamond shaped detectors approaching the beam in the vertical coordinate.




## Note:

fibers good for luminosity  $\sim 10^{-27-28} \text{ cm}^{-2}\text{s}^{-1}$ , but not radiation hard for collision runs.

# ALFA overlap detectors



- ❑ To ensure precise pot positioning
- ❑ 3 layers of 60 fibers staggered by 166  $\mu\text{m}$
- ❑ Precision given by large number of halo proton tracks



First test beam result:  $\sigma_{\text{OD}} < 10 \mu\text{m}$ ,  
final values coming from test beam 2010



# Test beam campaign 2010


All final combinations of detectors, readout electronics and trigger systems have been extensively investigated in the test beam H6B.

EUDET Si-Pixel telescope









120 GeV pions

ALFA station





80 million triggers for 4 sets of stations & detectors



# Overview measurement program





# Preliminary TB10 results



# First tracks from the tunnel

- ❑ Station B7L1 with the upper detector ALFA2 in parking position installed 2009/10
- ❑ Not triggered by ALFA - parasitic running in spy mode with ATLAS L1A triggers
- ❑ 2<sup>nd</sup> attempt with proper TDAC configuration: HI run 170406 December 4

→ tracks, showers and many empty triggers



# Main installation activities in the LHC tunnel

## **December 2010:**

- removal of detector ALFA2 in station B7L1 (installed 2009/10)
- breaking of Roman Pot and LHC vacuum
- removal of ALFA2 Roman Pot
- installation of 2<sup>nd</sup> station A7L1 in sector 8-1
- installation of both stations in sector 1-2
- reinstallation of ALFA2 Roman Pot with new ferrites
- station alignment in LHC coordinate system
- restoring of Roman Pot and LHC vacua
- bake out of stations and close by beam pipes


**All stations including Roman Pots were installed.  
Stations aligned to LHC system, bake out done.**

## **January 2011:**


- replacement and adjustment of new springs for auto-retraction
- insertion of the fiber detectors
- installation of the electronics and cabling
- commissioning of the station movement systems
- survey and final LVDT calibration for detector positioning
- commissioning of the data readout by LED signals

**End of January all 4 stations on both sides should  
be ready for movement and data taking.**

# Installation in the tunnel



**Vacuum breaking**



**Inserting stations**



**Alignment**



**Bake out**

# Road map 2011 and beyond

## 1) Parasitic runs with collision optics and detectors in garage positions:

Commissioning of individual detectors and readout with shower fragments.

## 2) Parasitic runs with collision optics and detectors outside garage positions:

Commissioning of the twin stations in both sectors 1-2 and 8-1 with halo particles.

Detectors are outside of garage positions but still very far from the beam, e.g. 20mm.

## 3) Special run with $\beta^*=90\text{m}$ and detectors close to the beam:

Extrapolating the elastic rate to  $t = 0 \text{ GeV}^2$  can be used to determine the total cross section with a precision in the range from 5-7%. Luminosity cannot be measured – needed as input from VdM scan or elsewhere.

**Note:** The feasibility of the un-squeeze to 90m with external tune compensation and parallel running of TOTEM and ALFA has to be demonstrated by machine studies.

## 4) Intermediate high- $\beta^*$ optics 1500m

TOTEM baseline optics, with some additional hardware interventions (more details explained LHC note 431, May 2010)

Not sufficient to reach Coulomb-Nuclear Interference region. But smaller  $t$  by higher  $\beta^*$  improves the extrapolation to 0  $\text{GeV}^2$ . With additional input for missing factors luminosity and/or total cross section can be determined.

## 5) ATLAS high- $\beta^*$ optics 2600m

The ultimate optics to reach the Coulomb Nuclear Interference region with most stringent requirements (aperture of injection line, small emittance, phase advance).

# Time line


- 1) Commissioning in garage position can happen very soon.
- 2) Move out of garage position for commissioning with halo particles seems very likely as the next step.
- 3)  $\beta^*=90\text{m}$  needs machine studies, also for parallel running of TOTEM and ALFA  
It is a necessary step to very high- $\beta^*$  and would be very good if it happens 2011.
- 4) Intermediate  $\beta^*=1500\text{m}$ :  
Due to hardware intervention realistic only after next long shut-down.
- 5) Very high  $\beta^*=2600\text{m}$ :  
As for 4) dedicated machine studies needed. Time scale depend certainly on decision about  $\beta^* = 1500\text{m}$ .

Schedule for items 4), 5) depend on experience and results achieved at 1) – 3).  
Dedicated machine studies are needed to prepare  $\beta^* = 1500, 2600\text{m}$  runs.



Thanks for Attention

# Front-End Electronics



## Main components:

- PMFs with MAROC chips on MAPMTs
- Kapton cables
- motherboards
- trigger mezzanines
- firmware

## All well-tested by:

- LED signals
- S-curves
- cosmic runs
- timing by source
- test beam

# Detector Slow Control

Back Home Refresh NO USER 25/06/2010 15:37:55

FORWARD\_RPO Sector 1-2

RPS (BOTTOM) READY OK

High Voltage	READY	OK	✓
Front-End	OK	OK	✓
PMF configuration	CONFIGURED	OK	✓
Movement control	READY	OK	✓



Zoom: 100 All connected

RPO LAB Absolute Luminosity For Atlas Detector Control System


ALFA NOT\_READY

RP1	UNKNOWN	OK
RP2	UNKNOWN	OK
RP3	UNKNOWN	OK
RP4	UNKNOWN	OK
RP5	NOT_READY	OK
RP6	READY	OK
RP7	UNKNOWN	E
RP8	UNKNOWN	E
Infrastructure	READY	OK

Atlas ALFA - RP6

MOTHERBOARD / DETECTOR PARAMETERS Front-End OK

Detector 1	-11.26 °C	3V3 PMF	3.12 V	1600.4 mA	Row1 ALFA-R	2.49 V	616.6 mA	MAROC	3.43 V	538.4 mA	
Detector 2	-11.26 °C	1V2 CDR	1.23 V	102.7 mA	Row2 ALFA-R	2.46 V	639.6 mA	MAROC	3.43 V	635.8 mA	
PMF 1	51.89 °C	GOL	5.6 mA	TTC-RX	34.2 mA	Row3 ALFA-R	2.47 V	650.0 mA	MAROC	3.44 V	536.6 mA
PMF 19	61.59 °C	I VCC-IO 2V5	435.0 mA	Row4 ALFA-R	2.47 V	742.1 mA	MAROC	3.43 V	635.1 mA		
PMF 23	65.31 °C	I VCC-IO 3V3	648.9 mA	Row5 ALFA-R	2.46 V	740.6 mA	MAROC	3.42 V	632.9 mA		
Air cooling inlet	35.77 °C										
Air cooling outlet	37.36 °C										
EXT 1	132.24 °C										
EXT 2	132.22 °C										
EXT 3	132.25 °C										



**Main tasks:**

- configuration of R/O
- low voltages
- high voltages
- monitoring of positions, temperature, pressure,...


HIGH VOLTAGE HV READY OK

MAPMT settings Vset 900 V I Trip 500 mA CONFIGURE







Trigger PMT settings OL - Vset 950 V Itrip 500 mA MD - Vset 1100 V Itrip 500 mA CONFIGURE

POT MOVEMENT MM Control READY OK

Top 3.00 mm Bottom -3.00 mm P04 ALIVE




# Measurement Program



## Standard Settings:

- HV(MAPMT) = 900V, HV(Trigger) = 950V / 1100V (Bialkali/SBA)
- THERMO = 7, GAIN = Equalized
- Trigger = EUDET ⊗ ALFA ⊗ Veto

# TB10 Tomography with EUDET Clusters



Many useful cross checks:

- distance of MDs
- position of ODs to MDs
- detector position to 0-beam

