




*Possibility of a higher PSB to PS  
transfer energy*

*K. Hanke  
for the PSB Upgrade WG  
Chamonix 2011*



## PS Booster

- construction 1972
- present energy range 50 MeV to 1.4 GeV
- **energy upgrades from 800 MeV to 1 GeV (1988), and from 1 GeV to 1.4 GeV (1999)**
- 7 flavors of LHC beams, 10 types of fixed target beams, intensity and emittances cover several orders of magnitude
- ppm operation (1.2 s cycle length)



- upgrade of the Booster ring and the transfer line to the PS for 2 GeV  
→ this Task Force
- upgrade of the BI line and injection region for 160 MeV H- & intensity increase  
→ so far L4 project – now part of LIU\_PSB

## PS Booster Energy Upgrade



Follow-up of the 2010 LHC performance workshop at Chamonix

<http://indico.cern.ch/conferenceOtherViews.py?view=standard&confId=67839>

- remove bottlenecks in the LHC injector chain
- consolidation of the injectors is necessary anyway
- put in place **Task Force** for a feasibility study and first resource & time estimate

Working group web page:

<https://twiki.cern.ch/twiki/bin/view/PSBUpgrade/WebHome>



The aim of the study is to evaluate the technical feasibility of an increase in beam energy of the CERN PS Booster from presently 1.4 GeV to about 2 GeV as proposed at the Chamonix 2010 workshop.

### The study comprises:

- Confirm the potential gain in terms of intensity and brilliance for LHC-type beams as presented at the Chamonix 2010 workshop.
- Confirm the technical feasibility. Identify accelerator components and equipment that need to be upgraded or exchanged. Identify potential showstoppers and point out solutions. Assign the responsible groups/units. Provide first rough time estimates for the various interventions needed.
- Provide a first estimate of material and personnel resources needed to complete the upgrade. Draft a project break-down into work packages, in preparation for a project to be launched by the director of accelerators.

# Working Group Organisation



coordinator K. Hanke / sc. secretary T. Hermanns

|                              |                                 |        |
|------------------------------|---------------------------------|--------|
| 1. Beam Dynamics             | G. Rumolo (now C. Carli)        | BE/ABP |
| 2. Magnets                   | D. Tommasini, A. Newborough     | TE/MCS |
| 3. Magnetic Measurements     | M. Buzio                        | TE/MCS |
| 4. RF System                 | A. Findlay, M. Paoluzzi         | BE/RF  |
| 5. Beam Intercepting Devices | O. Aberle                       | EN/STI |
| 6. Power Converters          | S. Pittet                       | TE/EPC |
| 7. Vacuum System             | E. Mahner                       | TE/VSC |
| 8. Instrumentation           | J. Tan                          | BE/BI  |
| 9. Commissioning & OP Issues | B. Mikulec (deputy coordinator) | BE/OP  |
| 10. Extraction and Transfer  | J. Borburgh                     | TE/ABT |
| 11. Controls                 | L. Fernandez                    | BE/CO  |
| 12. Electrical Systems       | D. Bozzini, S. Olek             | EN/EL  |
| 13. Cooling and Ventilation  | M. Nonis                        | EN/CV  |
| 14. RP and Safety            | M. Widorski                     | DGS/RP |
| 15. Transport and Handling   | I. Ruehl                        | EN/HE  |
| 16. Survey                   | T. Dobers                       | BE/ABP |
| Linkperson Consolidation     | N. Gilbert                      | EN/MEF |
| Linkperson Design Office     | R. Folch                        | EN/MME |
| Linkperson PS                | R. Steerenberg, S. Gilardoni    | BE/OP  |
| US LARP                      | E. Prebys                       | FNAL   |

Recently a work unit “Booster injection” has been added



|     |                                    |        | feasible | impact |
|-----|------------------------------------|--------|----------|--------|
| 1.  | Beam Dynamics                      | BE/ABP | YES      |        |
| 2.  | Magnets                            | TE/MCS | YES      | +++    |
| 3.  | Magnetic Measurements              | TE/MCS | YES      |        |
| 4.  | RF System                          | BE/RF  | YES      | (+++)  |
| 5.  | Beam Intercepting Devices          | EN/STI | YES      | (+)    |
| 6.  | Power Converters                   | TE/EPC | YES      | +++    |
| 7.  | Vacuum System                      | TE/VSC | YES      | +      |
| 8.  | Instrumentation                    | BE/BI  | YES      |        |
| 9.  | Commissioning                      | BE/OP  | YES      |        |
| 10. | Extraction, Transfer, PS Injection | TE/ABT | YES      | +++    |
| 11. | Controls                           | BE/CO  | YES      |        |
| 12. | Electrical Systems                 | EN/EL  | YES      | ++     |
| 13. | Cooling and Ventilation            | EN/CV  | YES      | ++     |
| 14. | RP and Safety                      | DGS/RP | YES      |        |
| 15. | Transport and Handling             | EN/HE  | YES      |        |
| 16. | Survey                             | BE/ABP | YES      |        |

## Summary (before going into the details)



- we have double checked the arguments presented at the 2010 Chamonix workshop and we confirm that an increase in beam energy will facilitate injection of high-brilliance and high intensity beams into the PS
- we have done a complete survey of all PSB equipment and systems with regard to an energy increase and did not find any showstopper
- we have identified PSB equipment and systems that need to be modified or exchanged in order to operate at 2 GeV beam energy
- we propose technical solutions for these items, along with a cost estimate and schedule
- we have identified items, which were already accounted for in the consolidation program; we have disentangled these items from the budget estimate for the energy upgrade
- we propose a project schedule, which is in line with the long-term LHC planning

**CERN**  
CH-1211 Geneva 23  
Switzerland



The  
**PSB Upgrade**  
Working Group

|                                                                     |
|---------------------------------------------------------------------|
| PSB Upgrade Working Group Document No.<br><b>1082646-0003</b>       |
| CERN Div./Group or Supplier/Contractor Document No.<br><b>BE-OP</b> |
| EDMS Document No.<br><b>1082646 v.3</b>                             |



DATE: 2010-09-23

## Feasibility Study

# PS BOOSTER ENERGY UPGRADE FEASIBILITY STUDY FIRST REPORT

### *Abstract*

This document summarises a survey of the CERN PS Booster systems with regard to a possible energy upgrade to 2 GeV. Technical solutions are proposed along with a preliminary estimate of the required resources and the time lines.

#### **Prepared by:**

**Klaus Hanke**  
BE-OP

[Klaus.Hanke@cern.ch](mailto:Klaus.Hanke@cern.ch)

Oliver Aberle  
Alfred Blas  
Jan Borburgh  
Davide Bozzini  
Marco Buzio  
Christian Carli  
Tobias Dobers  
Alan Findlay  
Leandro Fernandez  
Simone Gilardoni  
Thomas Hermanns  
Edgar Mahner  
Bettina Mikulec  
Antony Newborough  
Mauro Nonis  
Slawomir Olek  
Thomas Otto  
Mauro Paoluzzi  
Serge Pittet  
Rende Steerenberg  
Ingo Ruhl  
Giovanni Rumolo  
Jocelyn Tan  
Davide Tommasini

#### **Checked by:**

Simon Baird  
Oliver Bruning  
Jean-Paul Burnet  
Edmond Ciapala  
Francois Duval  
Doris Forkel-Wirth  
Eugenia Hatziangeli  
Erk Jensen  
Jose Miguel Jimenez  
Rhodri Jones  
Mike Lamont  
Roberto Losito  
Volker Mertens  
Mauro Nonis  
Thomas Otto  
John Pedersen  
Lucio Rossi  
Ingo Ruhl  
Marc Tavlet

#### **Approved by:**

Steve Myers  
Roland Garoby  
Frederick Bordry  
Paul Collier  
Roberto Saban

document released

Distribution List: R. Heuer

Chamonix 2011



## Main Findings and Recommendations



- the study aims at LHC beams only; however we found that the cost drivers do not disappear when restricting ourselves to LHC beams; we have studied variants of the “LHC-only” scenario, where we suppress fixed-target physics cycles whenever we have LHC cycles in the injectors (LHC filling and setting up); some savings (but not the cost drivers), while the loss of non-LHC physics appeared unacceptable to us (<https://edms.cern.ch/document/1079117/1>)
  - **consider all beams to the PS at 2 GeV (ISOLDE remains at the present 1.0/1.4 GeV)**
  - **enable the full machine including PS transfer for ppm operation**
  - **confirmed as baseline scenario by the LIU project**
- we were asked to put in place the upgrade rapidly, even before Linac4; this turned out to be technically challenging and schedule wise unrealistic
  - **energy upgrade and commissioning with L4 will coincide (in 2015/16)**
  - **compatibility with L4 intensities**
- we have addressed the question of intermediate energies between 1.4 and 2.0 GeV
  - **we found that the present MPS is not able to run at any energy higher than 1.4 GeV and needs to be replaced in any scenario (cost driver)**

## WU 2 Magnets [A. Newborough, D. Tommasini]



achievable field levels for 2 GeV

concern over life span due to mechanical stress

saturation of outer rings will increase even more

present main unit cooling system insufficient

auxiliary magnets: majority not affected, but study to be completed

15-18/59 transfer line magnets presumably require exchange; need optics studies for final confirmation

PS injection bumpers, correctors and quads

new field levels are achievable

stress test completed in SM18; no degradation found


change solid retaining plates by laminated ones to reduce/eliminate saturation

cycle designed with rms current within 10% of the present one, only minor modifications to the cooling circuits necessary (in situ)

auxiliary ring magnets mainly used at low energy, no worry

modification/replacement of ~30% of the transfer line magnets

replacement of many PS low-energy magnets; study ongoing ; now part of LIU\_PS



Booster main magnet undergoing tests for operation at 2 GeV

## WU 4 RF System [A. Findlay, M. Paoluzzi]



high-level rf: consolidation of C02, C04  
and C16

everything covered by consolidation,  
no issues left for the upgrade project

consolidation of low-level rf,  
transverse damper, rf cables

### notice:

it is a necessary condition for the energy upgrade that the RF consolidation is completed; in case this is not (or not completely) covered, or if consolidation is not completed within the time frame of the upgrade, then the upgrade will not work

the consolidation of the C04 is required to achieve 2 GeV - C02 and C16 are not mandatory for the energy increase but required for a reliable operation over the next 25 years.

**budget:** 14320 kCHF – 14320 kCHF (cons.) = 0 kCHF

## WU 5 Beam Intercepting Devices [O. Aberle]



present dump obsolete, no spare,  
neither appropriate for L4 intensities  
nor for 2 GeV

beam stopper BTP.STP10 has to be  
checked with regard to 2 GeV  
operation; new design might be  
needed, still to be confirmed.

new design in progress, production of a new  
dump plus spare to be launched

if insufficient, launch new design and  
construction (2 units)

notice:

study of the PSB dump has been triggered by the question whether it can accept  
L4 intensities – the energy upgrade comes now as additional constraint into this ongoing  
study

**budget:** 700 kCHF – 700 kCHF (cons.) = 0 kCHF



present MPS cannot deliver 2 GeV cycle

- it can neither deliver the required rms nor peak current
- increasing peak power using traditional thyristor technology would have unacceptable effect on the whole Meyrin network
- the present 1.4 GeV is a hard limit for the existing MPS

number of smaller power converters needs to be changed

notice:

ppm operation between 1.0/1.4 GeV (ISOLDE) and 2 GeV (PS) for some power supplies assume fast cycle to reduce rms power

new POPS-type MPS using capacitor bank

- divide machine in 2 circuits (inner and outer rings); will make R 1+4 trim power supply obsolete
- some civil engineering needed

replacement of a number of smaller power supplies

**budget:** 20850 kCHF (cost driver) – 6630 kCHF (cons.) = 14220 kCHF in case all beams at 2 GeV  
21100 kCHF – 6630 kCHF = 14470 CHF if LHC beams only



number of extraction elements OK

number of septa/kickers cannot operate at 2 GeV\*, notably extraction kickers (BE.KFA) and recombination septa (BT.SMV)

PS injection kicker and injection septum do not work at 2 GeV

---

\* there is a proposal to run with the existing recombination elements for LHC beams only

extraction kicker and recombination septa to be re-designed and re-built; some other elements (BE.SMH) to be modified (re-inforce cooling)

Longer PS injection septum and complete injection region to be re-designed and re-built (now LIU\_PS).

PS injection kicker OK if operated in short-circuit mode, otherwise additional kickers

The re-design of the PS injection region is under way; it is hoped that the injection point can stay where it is now (SS42); otherwise displace to SS41. A solution has been found for LHC-type beams, but a solution that works for all beams is being worked on. Conclusion expected for early 2011.

→ critical issue

**budget:** 5763 kCHF – 550 kCHF (cons.) = 5213 kCHF



present power consumption around 10 MVA; future electrical distribution will depend on the requests

no more power available from transformer for general services; 18 kV cubicles cannot be extended; system needs consolidation

**budget:** 1700 kCHF

After topical meetings with EN/CV and TE/EPC the needs have been clarified:

- TE/EPC estimates a 10% increase in their request for the MPS, and 40% for the transfer line.
- CV estimate a 15-20% increase of the power demand

re-design of the system has started; to be seen within the context of a global re-design of the electrical network on the Meyrin site





cooling: future design of cooling and ventilation will depend on the cooling needs, mainly magnets, power and rf; survey of the cooling needs of the different work units has shown so far no increase in the cooling needs

ventilation: no specific needs communicated to CV

recently RP have asked for a complete review of the system

notice:

need ~6 months in a row for commissioning of cooling plant and new equipment, length of the shutdowns is therefore a concern

**budget:** 5500 kCHF – 4500 kCHF (cons.) = 1000 kCHF

refurbishment of cooling station and some distribution piping

complete refurbishment of existing plant keeping the same functionalities

being followed up


## Summary Resources in kCHF




|                                       |              | Consolidation |              |
|---------------------------------------|--------------|---------------|--------------|
| Total Beam Dynamics                   | 50           | 0             | 50           |
| Total Magnets                         | 3445         | -210          | 3235         |
| Total Magnetic Measurements           | 111          | 0             | 111          |
| Total RF                              | 14320        | -14320        | 0            |
| Total Beam Intercepting Devices       | 700          | -700          | 0            |
| Total Power Converters                | 21100        | -6630         | 14470        |
| Total Vacuum System                   | 100          | 0             | 100          |
| Total Beam Instrumentation            | 67           | -10           | 57           |
| Total Commissioning                   | 50           | 0             | 50           |
| Total Extraction, Transfer, Injection | 5763         | -550          | 5213         |
| Total Controls                        | 116          | 0             | 116          |
| Total Electrical Systems              | 1700         | 0             | 1700         |
| Total Cooling & Ventilation           | 5500         | -4500         | 1000         |
| Total RP                              | 0            | 0             | 0            |
| Total Transport and Handling          | 680          | -400          | 280          |
| Total Survey                          | 50           | 0             | 50           |
| <b>Total Project</b>                  | <b>53752</b> | <b>-27320</b> | <b>26432</b> |

Behind this overview there is a detailed budget & manpower break-down for each WP

# Draft Project Schedule



**assumes resources (money and manpower) are made available in due time**



## Summary & Next Steps



- one year of intense work
- different options studied
- an upgrade of the PSB from 1.4 GeV to 2.0 GeV is technically feasible
- a realistic estimate of budget and time lines has been made; the upgrade can be completed by 2016
- consolidation items have been disentangled from the budget
- the budget has been entered in the MTP according to our estimate

next steps:

- conclusions from retreat and Chamonix
- make decision and freeze design choices
- prepare TDR