

Jason Tarrant - STFC

- Contents
 - » Integration Engineering
 - Inputs & information required
 - Outputs (documents)
 - Checks
 - Forthcoming work
 - Immediate integration issues



- Integration Engineering
 - » Main inputs / information required
 - 3D models of MICE components & assemblies = enable quick generation of 'perfect' geometry
 - 2D drawings of MICE components & assemblies = show tolerances i.e. non-perfect sizing
 - (and/or) Inspection & survey results
 - Installation information (when, what, who, how) incl:
 - Installation instructions (incl. tooling, hardware etc required)
 - Position / placement & mass information
 - Services requirements (installation, testing and operation)
 - Testing plan Mechanical requirements (e.g. apparatus / hardware)





Information required...cont'd


Expected delivery? Current model(s)? Engineering drawings / tolerances / specifications? Pending / future expected changes? Position & orientation confirmation? Mass & C of G? Known interfaces and any prior checks? Infrastructure required (hardware, services, tooling, survey, inspection & test equipment etc) @ all stages e.g. deliver, installation, testing, operation? Safety (incl. unwanted outputs / interaction)? Post manufacture test, inspection and other quality control or survey related data? **Delivery state? Storage requirements?** Installation (when, what, who, how)?





» Outputs

- Essential Geometry model & drawing
 - General specification of MICE channel component position
 - Interact with device suppliers & physicists
 - Sign-off Technical Board (?)
 - To include RFCC change (old version shown below)





Integration Engineering



» Outputs

- Component / system models (mainly) and drawings
 - For checking overall interfaces, envelopes etc, for services and infrastructure hardware development (e.g. flooring platforms)
 - Interact with device suppliers, services & peripheral developers
 - Sign off with inclusion of
 - » RAL Infrastructure Team
 - » Component / system suppliers
 - » Hardware developers / suppliers
- Survey development models & drawings
 - For development of compatible survey hardware & procedures (e.g. magnetic survey deployment system)
 - Interact with survey groups







» Outputs

- Installation models, drawings, documents & schedules
 - For specific installation information & placement requirements for MICE devices, including e.g.
 - » Datum features
 - » Placement tolerances
 - » Testing requirements
 - » General mechanical (e.g. kit lists, torques, tooling)
 - Interact with both magnetic and physical survey groups as well as device developers, infrastructure and installation team
 - Sign off with inclusion of
 - » RAL Infrastructure Team
 - » Component / system / hardware suppliers



Integration Engineering



- » Outputs
 - Actual placement version of Essential Geometry drawing (i.e. post installation & survey)
 - A record of actual placement e.g. for simulations (possibly 3D models as well for G4MICE simulation)
 - Interact with survey group & simulation group
 - Sign off (as built) with Technical Board (?)



- Integration Engineering
 - » Checks on components & systems

Envelopes

- Ensure fit with MICE environment & surrounding hardware
- Ensure it can be manoeuvred into location & any subsequent locations (e.g. future steps or testing)

- Placement

 Ensure physics & mechanical compatibility requirements (e.g. floor to centre height)

-Interfaces


- Ensure interface details match, including allowance for manufacturing tolerances, surveying accuracy etc
- Determine flexibility at interfaces for adjustment if required
- Services routing and connection interfaces





- Forthcoming Work
 - » Understand who 'stakeholders' are
 - » Get information on the components & systems, and their integration into the MICE hall
 - Obtain the information listed earlier...
 - » Continue work on models & drawings (bulk of work)

Immediate Issues: Floor to Centre Height




Bases of models currently @ different distances from centre


- » Required 1515mm or less
 - -~OK from SV (SS), A DeM (RFCC), TESLA (AFC)





Immediate Issues: RFCC Clash





- » Mezzanine will be modified to suit
- » Other local hardware might also be a problem (TBD)

