

# *MICE RF System*



*Andrew Moss*

*ASTeC*

*Collaboration meeting CM29*

*15<sup>th</sup> - 18<sup>th</sup> February 2011*




## *contents*

- High power amplifier testing
  - Results so far
  - Next steps
  - Plan
- Hall layout
  - First attempts of CAD modelling
  - Optimisation
  - plan


## *Amplifier status*

- First medium power (300kW) amplifier and power supply system tested 2008
- Refurbishment and rebuild of first high power (2MW) amplifier complete October 2009
- Power supplies for first 2MW amp operational
- Two further 300kW amplifiers awaiting repair
- Two refurbished 2MW CERN amplifiers partly tested, awaiting assembly and high power test
- Still need to build 3 more sets of power supplies
- One more 300kW amplifier to buy/acquire

## *RF system components*



## *Test system at Daresbury*



Daresbury test setup for proving amplifiers/power supplies



## *High power amplifier status*




- Final electrical checks September 2010 – crowbar/cathode modulator systems
- Amplifier connected to test load via coax
- Filament test to 500A on tube



## *4616 medium power amplifier*


- 4616 pre amplifier set up on matched test load
- system has old LBNL tube installed, new ones in stock
- System operated at 70kW into load, gives us a known starting point to run into the 2MW amplifier system





## Initial testing

- 4616 connected into input of main 116 amplifier
- High reflected power issues immediately, looked to be reflecting 50 % of power
- However match of input changes <sup>116</sup> forward with heating, RF drive level, HT applied and cathode modulator switching on, after playing with the system tuning match got much better (10<sup>th</sup> reflected power)
- RF diode traces a great diagnostic to see immediate changes in response (1Hz) operation as power meters slow to update at low rep rate






## 116 amplifier testing

- So far testing has been relatively un dramatic and system very quickly up to 100kW
- Old ISIS tube installed while we learn how to operate the system
- Sudden oscillation possible, can see diode traces change dramatically when this happens
- lots of RF noise on all earth systems causing interlocks to fire at 160kW, gradually going around the power supply fixing these issues
- Discussions with ISIS linac team have indicated that the amplifier looks to be working correctly, suggested a method for tuning up the system. HV bypass capacitors have been fitted on main cap bank to aid in noise reduction

Forward



Andrew Moss

## *RF and power supply testing this week*

- System pushed to 200kW RF output by driving input very hard
- Tests on crowbar circuit have revealed that at HV level of 23kV system starts to have breakdown issues inside power supply
- Testing with a current limited (1mA) power supply to find cause of breakdown will commence

Forward power into load





## *Further 116 testing*

- HV issues are the are the major obstacle to reaching high power in this system at the moment, could also be some self oscillation in the circuit, lots more to understand
- Old ISIS tube showing gain of 10 which is to be expected, should be useful up to 1MW
- Will then swap to a new 4616 and new 116 to push system harder
- So far the amplifier system seams very well behaved at up to 22kV and 200kW, however a long way to go yet !



# Predicted hall layout for RF components

Typical layout of system  
using amplifier with DL/LBNL  
type output




DC = directional coupler = power measurement




## *Coax design*


- Coax system will use large phase shifter to make amplifier immune to reflected power issues
- Hybrid power splitters to divide power before each cavity with a rejection load, this should provide a robust reliable system
- Local phase shifters in each cavity coupler, small range available only, so need to plan coax system carefully to get phase lengths within range at the cavity input couplers
- Power monitoring in each section of coax will be linked in to RF control system so that issues can be flagged before faults occur
- Nitrogen gas pressure system with the coax for voltage stand off and interlock
- Plan to have the ability to connect test loads in place of cavity to test amplifier/coax system in its complete configuration

Tim Hayler, Alan Grant and Alan Muir  
have been doing CAD layouts



















## *Layout optimisation*


- Try to get as much of the complex RF devices out from under the floor so that floor does not need to be lifted if there is a problem
- Still need space around amplifiers to work on them
- trombone phase shifters behind shield wall freed up a lot of space
- move feeds to cavity couplers as close as possible to under the required port
- ‘flexible’s’ up from floor to cavity couplers will be able to be removed so RFCC can be moved














## *Layout further work*

- Need to match lengths of coax from hybrid splitters to cavity inputs for phase addition
- These can be in 4 inch coax to save space
- Smaller RF loads found, can be designed to our specification
- Will add small phase shifters into these lines to take out small errors
- N2 pressurisation to be discussed, cavity inputs may need this anyway for voltage standoff, interlock if something goes wrong in the couplers/coax
- Write specification for coax system to purchase



## *Plan*

- Complete tests on current amplifier and then ship to MICE
- Build up first CERN amplifier to working system and begin tests early 2011
- Test digital LLRF on amplifier system
- Build up next set of power supplies and transfer into test system, send current power supplies to be installed in MICE hall
- Complete design of RF components from amplifier to cavities and procure

## *Thanks to*

- Tim Hayler, Alan Grant, Alan Muir for their work on the layout
- Mark Keelan and Alan Letchford for help with the amplifier systems