

Status of the AFC at RAL

Tom Bradshaw

John Cobb

Win Lau

Matt Hills

Elwyn Baynham

Mike Courthold


Victoria Bayliss

7th February 2011



Talk will cover

- Recent progress at TESLA
- Staffing Changes
- Test Plan for AFC at RAL




Recent Issues – we have been slow getting the winding started


- Reported last meeting that there was some concern over the loss of bobbin temper after application of insulation. This was completed but there was a delay with remake of G10 insulation (not enough cover in the corners).
- Some high voltage tests have been done on current insulation system. Tests on the 0.3mm G10 showed that it can withstand 3kV for 2 minutes. Tests were done with actual samples and one of the bobbins.
- Tests completed on splice – results obtained in the nano-ohm region. These are being repeated but first indications are excellent.
- Improved thermal contact at top of HTS leads to improve the temperature margin.
- Personnel changes at Tesla mean that we are reviewing items prior to winding to check that issues have not been forgotten.

- Conductor tails - These now exit the coil in a copper half tube which provides good thermal sinking and mechanical support.
- Analysis suggests that this is a good solution and is required.


These are slightly old drawings – the copper channels extend directly into the coil




Cover removed for clarity




- Assembly sequence “story board” is still being refined – getting the cold mass centre line accurately in the module is proving a challenge.
- Still need Mississippi to scrap a safety window to act as a test piece.
- Quench protection heater sizing is ongoing ...






- We have a test cryostat for checking that the crycoolers meet specification before installation.
- This is at Tesla – we are waiting for a window of opportunity to start tests.




The recent leaving of Tom Frame – the lead engineer and a frank discussion with TESLA senior management on the lack of progress has precipitated a change of personnel and a reorganisation at TESLA.



Patrick Clayton will be Technical Manager supported by Mike Nakatsu – he has two technical support staff.



- Test plan for the AFC when at RAL
- Special conditions of testing without the lattice means that a support structure will be required for operation of the magnet in the MICE Hall (Item is top heavy and same/similar support will be required for transport).
- Assume that the tests will first be done with hydrogen and the absorber. It may be that the absorber will have to be taken out at the end of the tests to fit a solid one.



- Tesla on-site commissioning and acceptance test at RAL – probably in the MICE Hall
 - Installation
 - Connection of services
 - Cool down
 - Ramp up current

These are the tests which are contractual and represent the final milestone for the delivery of the AFC. It is also an opportunity for us to learn how the system will operate.



- Field Mapping at full field
 - Set-up
 - Mapping
- Absorber integration
 - Fit absorber - check for interferences
 - Integrate with Transfer line
 - Leak check and pump
 - Instrumentation check
- Safety windows
 - Installation
 - Leak check
- Cover plate installation
 - Install
 - Pump down and leak check

This will be done by CERN with OU involvement

We have some tight fitting pipework


Different pump port as normally this would be the MICE vacuum

- Preliminary cool-down
 - Base temperature test
 - Helium condensation
 - Cooling power at 20K
 - Warm-up H₂ system
- Hydrogen System test
 - Cool down
 - Part fill with hydrogen
 - Warm-up H₂ system
 - Purge
 - Cool & Fill with hydrogen
 - Hold for two days
 - Ramp up field and hold
 - Warm-up H₂ system
 - purge

This is a test without hydrogen to test operation and instrumentation. Also the test will thermally cycle the system to check joints.

This first part of the test checks the hydrogen fill with a minimum amount of hydrogen to reduce risk.

Second part includes full operational check together with magnetic field in the AFC





Science & Technology Facilities Council

Technology

END