Kicker options for MTE

Prepared by L.Ducimetière, L.Sermeus

<u>Outline:</u> Reminder : Present MTE dedicated kickers Hybrid extraction using CT elements Faster KFA 13 – 21 (shorter rise time) Stronger KFA 13 – 21

Present MTE dedicated kickers

«Phase 1» construction completed in 2008:

- KFA 13/21 for the extraction of the « islands »
- +KFA 4 for the core beam (complemented by KFA 71-79)





Hybrid extraction using CT elements

For a full compatibility CT + MTE :

- 5-stair kick for the DFA 242 using the refurbished NSG switches
- Refurbishement of RSG switches
for the DFA 254 – 10 kCHF, 0.2 MY
- Consolidation of BFA 9 tank
feedthrough (new oil-free interface), ring oil system – 10 kCHF, 0.1 MY





- Update B 359 infrastructure (oil retention, fire hazards; full detail in IEFC days, March 2011) 240 kCHF, 2 MY by end LS1

- Full refurbishement of electrical distribution and Electronics&Controls by end LS1 (see Etienne's talk for details and M+P)

Faster KFA 13 – 21 (shorter rise time)

For both KFA 13 and KFA 21, 1 PFN supplies 3 seriesconnected magnet modules.

Shorter rise time can be achieved by energising the 3 kicker modules by independent PFN's rather than in series.





Faster KFA 13 – 21 (shorter rise time)

Additional equipment required:

- ► 4+1 spare PFNs + 2 vacuum tanks
- hydraulic systems + cooling
- electronics and controls
- new building in PS ring centre

Resource estimate (based on equipment built in 2008):

KFA 21

KFA 13

- Equipment
- New building
- Manpower (staff)
- Time to completion
- 6.0 MCHF (2008 prices) 1.0 MCHF (250 m² @ 4 kCHF/m²) 12 MY (not presently available) t_0 + 2.5 Y

in building 367 (same as POPS !!)

KFA 4

Stronger KFA 13 – 21

Increasing the strength of the KFA13 – 21 have been suggested to give more clearance at septum 16.

However :

- Magnets already operating in shortcircuited mode
- No room for additional magnets
 Nominal operating voltage provides no margin: system working with only 6% margin from the design/test voltage (10% recommended)
- Many component already at the limit (cables connectors, HV capacitors, cables)





Scenario and option	Resources kCHF MY		Feasibility
CT only	240	2.0	Update of B 359 infrastructure during LS1
MTE only	110	1.1	90% for updating B 359 infrastructure during LS1
CT-MTE Hybrid	260	2.3	90% for updating B 359 infrastructure during LS1
Thinner septum	-	-	
Dummy Septum	-	-	
Faster kicker	7000	12	Incl. EC; Manpower not available, long lead time, new building, not realistic
Stronger kicker	-	-	Not technically feasible



Keeping CT for combined use is an option Requires a large safety overhaul program (in LS1) Cost M = 260 kCHF, P = 2.3 MY

Keeping CT for combined use is an option Requires a large safety overhaul program (in LS1) Cost M = 260 kCHF, P = 2.3 MY

Faster KFA 13 – 21 kicker : not cost efficient Reduce losses on SMH16 by factor ~ 2, but Cost M = 7 MCHF, P = 12 MY, T = 2.5 Y, S = 250 m²

Keeping CT for combined use is an option Requires a large safety overhaul program (in LS1) Cost M = 260 kCHF, P = 2.3 MY

Faster KFA 13 – 21 kicker : not cost efficient Reduce losses on SMH16 by factor ~ 2, but Cost M = 7 MCHF, P = 12 MY, T = 2.5 Y, S = 250 m²

Increased strength of KFA 13 – 21 : not really an option

- Keeping CT for combined use is an option Requires a large safety overhaul program (in LS1) Cost M = 260 kCHF, P = 2.3 MY
- Faster KFA 13 21 kicker : not cost efficient Reduce losses on SMH16 by factor ~ 2, but Cost M = 7 MCHF, P = 12 MY, T = 2.5 Y, S = 250 m²
- Increased strength of KFA 13 21 : not really an option

Expecting clear roadmap from this workshop

LS1 program needs advance scheduling