

# CLIC07 Workshop


Summary from  
« Two-beam hardware and  
integration » WG

Session on Wed 17.10.2007

G. Riddone, R. Ruber

18.10.2007

- Thanks to all speakers for very professional and valuable presentations
- 22 talks → covering a wide range of topics
  - Tunnel
  - Cooling
  - Transport
  - Module and transfer lines
  - Quadrupole
  - Alignment/stabilisation/supporting system
  - Vacuum requirements/system
  - Beam instrumentation
- A more detailed summary will be prepared within two weeks with clear recommendations/actions





CLIC workshop – Working group: Two beam hardware and Integration


# CLIC Civil Engineering Layouts & Tunnel Cross Section

John Osborne TS-CE


Acknowledgements : C.Wyss, J-L Baldy, N.Baddams



- Further in-depth studies needed to better define tunnel cross section, in particular for :
  - Demineralised Water ( $\Delta T$  to be better understood) and maximum flow to avoid vibration problems.
  - Ventilation System to comply with current Safety requirements for emergency situations.
  - (see talk by J. Inigo-Golfin)
  - Next iteration deadline with updated parameters ?



Return loop: to be optimised




Distance of PITS - Safety!

# First Considerations on CLIC Cooling System

Ch. Martel, J. Inigo-Golfin  
TS/CV

## New proposed tunnel section Transversal ventilation

- No  $\Delta T$  along the tunnel
- Better air cooling
- Real smoke extraction
- Smoke compartmentalization
- Safe evacuation
- Evolutive capacity




Compatible with new tunnel safety requirements throughout the world

© 2014, CLIC-CERN/EP

CLIC-EP/2014-017

## Integration of required pipes



© 2014, CLIC-CERN/EP

CLIC-EP/2014-017

## Clic - Conclusions

- Refining of requirements necessary, first version of URD should be issued in the coming months with the main sizing parameters,
- Compromises in the design, in view of the very large numbers involved, not to be dismissed without careful consideration.

## Transport of the CLIC Modules and Elements

CLIC Workshop October 2007  
Two Beam Hardware and Integration  
Working Group  
Keith Kershaw (CERN)

### Information needed for transport

- Dimensions
- Weight
- Support points
- Lift points
- Maximum accelerations (and frequencies)
- Number to be transported and installed
- Support interfaces
- Interconnection details
- Position in tunnel cross section and space around
- Time available for transport and installation

## Introduction - Transport system integration into design


- Main concern for today's meeting is transport in the tunnel
- Key items to transport
  - 1) Modules, module supports
  - 2) Transfer line /roof elements
  - 3) Injection rings, loops
  - 4) Turnaround elements
  - 5) Drive beam dump

approx 50,000 items with declared weights of max 2 tonnes to be installed within two year period (logistics!)

Don't forget racks, cables, cooling and ventilation, supports...

### Integration issues

- Space for transport , unloading and transfer
  - With guidance error margin
  - Allow co-activity (passage next to transport zone)
- Space for power rail
- Space for loading lowered items
- Consider logistics (parking and passing places)
- Integration should include space for removal



CLIC workshop at CERN  
16-18 October, 2007




## How to apply scheduling work done for ILC to the CLIC project

Prepared by M Gastal

### Goal:

- Present the work done for the construction schedule of ILC project and explore the possibility to apply it to CLIC



17/10/2007

martin.gastal@cern.ch

1



## Conclusions




### → Key milestones:

- Surface Detector Assembly Building ready for detector:  $t = t_0 + 2Y$
- First tunnel sections ready for services installation:  $t = t_0 + 2.5Y$
- Detector Hall (cavern) ready for detector:  $t = t_0 + 4Y$
- First beam tunnel section ready for machine installation:  $t = t_0 + 3Y$
- More efforts needed to load resources into the schedule and assess coactivity more thorough fully
- The installation sequence for the machine and detectors have to be designed and inserted in the general schedule
- A post completion analysis of the CMS project will be presented in early 2008. It should provide useful insight in the installation schedule for the ILC experimental areas

17/10/2007

martin.gastal@cern.ch

1



## Conclusions



- A draft construction schedule for CLIC could be produced using the same methods used for ILC

→ Starting this exercise soon is crucial for the lessons learnt from the LHC project are still fresh in people's mind

→ Sources of information to feed into the schedule are available at CERN and come from all departments.

→ Keeping a link between the two projects can be mutually beneficial

17/10/2007

martin.gastal@cern.ch

41




# CLIC workshop "Two beam hardware and integration" working group Module layout and main requirement


G. Riddone, A. Samoshkin

17.10.2007

> 20000 modules



# CLIC module




G. Riddone, CLIC07 workshop, 17.10.2007

44



# Several activity domains



G. Riddone, CLIC07 workshop, 17.10.2007



# Conclusions

- Dedicated development programs of systems including, micron precision pre-alignment, nanometer stabilization, cooling, vacuum, beam instrumentation, active alignment and beam dynamics, etc. are needed
- An important issue is the integration of these various systems into the CLIC module which will be repeated over twenty thousand times along the length of CLIC → optimization, reliability, scheduling (see talk of M. Gastal) and cost
- The module study raises feasibility issues, identifies areas needing study and design, addresses important aspects of cost and provides basic parameters for other areas of the study
- Test module in CLEX from 2008 (see talks of K. Alam and F. Toral [TBL]):
  - System integration
  - Alignment system
  - Stabilization system

Key-issue

G. Riddone, CLIC07 workshop, 17.10.2007


CLIC workshop, 16-18 October 2007

Working group "Two beam hardware and integration"

## Test module in the two beam test stand

Khurshid Alam, AB-RF


17.10.2007



K. Alam, CLIC workshop,  
October 16-18, 2007

1

Key issue:  
**PETS  
assembly**




1 m long

## Conclusions

- Progress on the test module in agreement with the schedule
  - PETS assembly strategy will be tested at the end of 2007
  - tank and components needed for phase 1 will be delivered to CERN in march 2007
- Main beam:
  - tank is under study
  - closer CLIC module configuration to be studied (alignment and stabilization features to be integrated)

CLIC module



Experience  
exchange  
with CIEMAT  
PETS  
for TBL

K. Alam, CLIC workshop,  
October 16-18, 2007




## Main features of PETS tank

(I will review the present status of the PETS tank design for CTF3. Hopefully, PETS tank will be similar in CLIC)




J. Calero, D. Camillo, J.L. Gutiérrez, E. Rodríguez, E. Toral  
CERN, 17/10/2007

## General layout



2

## Copper rods (II)



- End rings: two pins on each rod for alignment and one screw for clamping.
- Enhanced thermal contact: all the rods have the same length and contact pressure is made by bolts.
- Intermediate stainless steel ring: the assembly is stiffer and sag is negligible. Two pins and two screws on each rod.

Height (mm)	Sag (micron)
35	29.3
40	23.4
45	19.2

5

## Conclusions

- Conceptual design of PETS tank is on-going.
- There are a lot of difficult issues to solve:
  - high precision copper machining,
  - complex assembly,
  - cooling system under high-vacuum conditions,
  - brazing...
- Test program is being defined.
- Time schedule is very tight, but more manpower is now available. Tasks will run in parallel.
- Hopefully, all this experience will be directly transferred to PETS tank in CLIC.

16


# PETS components and waveguide connections

CLIC Workshop 2007


David Carrillo

## Testing single PETS bar

- A device has been designed to do RF tests of the single PETS bar
- It consists of two side blocks that will be put together with a single PETS bar in order to create inside a mode ( $TE_{10}$ ) with same phase advance,  $v_g$ , etc as the decelerating mode ( $TM_{01}$ )



## Choke flange. Shifts & twist



## Conclusions

- A **Choke flange** design has been done, which will allow a flexible connection between PETS and accelerating structures and also will provide a vacuum port
- **Single bar test device** will allow us to measure RF quality of single bars before putting all together
- **Mode launcher** designed will be used to introduce and extract power in order to test phase-shift and S parameters for PETS

David Carrillo

CIBMAT





### Copper quadrant structures:



### Structure fabrication: dimensional tolerances

M. Taborelli

Contributions of :  
G. Arnaiz-Izquierdo, A. Cherif, D. Glaude, R. Leuxe,  
CLIC study team



Longest accelerating structure built so far in quadrants

The target is:


$\pm 1 \mu\text{m}$  on the shape on parts of 500 mm length

Note: This cannot be achieved by any present available technology on the full size of the part  
► regions of necessary accuracy should be re-defined and restricted as much as possible

$\pm 3 \mu\text{m}$  alignment accuracy on 2m length



### Achieved shape accuracy, milled parts





# CLIC workshop "Two beam hardware and integration" working group

## Main requirement for module cooling

Risto Nousiainen


17.10.2007

7.7 kW /mod.

Risto Nousiainen,  
17.10.2007



1



## Discussion

- Main issues:

- 1. Tolerances


- Static
- Dynamic

- 2. Vibrations

- Water induced
- Balance between sufficient cooling and acceptable flow parameters

- 3. Temperature stabilization

- 4. Volumetric flow




1 Kelvin causes  
an misalignment of 7  
microns with the current  
support

Risto Nousiainen,  
17.10.2007




9



## Layouts for module cooling

Configuration	-	+	$V_{\text{flow module}}$	$V_{\text{flow water}}$
AS Parallel	Additional volumetric flow	Thermal stability Temperature gradient	3 m <sup>3</sup> /hr	7500 m <sup>3</sup> /hr
AS Series	8 different structures Thermal stability	Small volumetric flow High $\Delta T$ of water	0.5 m <sup>3</sup> /hr	1200 m <sup>3</sup> /hr

- Two extreme cases
- Other options:
  - Two AS in series




$\Delta T$  over one AS 1.5 K

Risto Nousiainen,  
17.10.2007



NB: For a standard module.



## Future work

- Previous study:
  - Water induced Quadrupole vibrations
- Future work
  - How to compensate dynamic effects?
  - How to predict water induced vibrations?
  - System design for cooling

Risto Nousiainen,  
17.10.2007



10



# CLIC workshop "Two beam hardware and integration" working group

## Supporting System


Risto Nousiainen

17.10.2007

Risto Nousiainen,  
17.10.2007




1



## Discussion

### • The main challenges


- Tolerances
- Initial error compensation during pre-alignment
  - Thermal
  - Mechanical
- Operational errors
  - Mechanical stability
  - Thermal expansion
  - Vibrations → Stabilization
- System integration
  - Alignment
  - Interconnections
  - Vacuum
  - Cooling



Risto Nousiainen,  
17.10.2007




10




## Supporting Strategy

### • Improved precision

- Separate supports
  - AS girder
  - PETS girder + Quad.
  - MB Quadrupole
- Vacuum tanks



### • Flexible interconnections



Risto Nousiainen,  
17.10.2007



7



## Conclusions and future work

### • Previous Study

- Magnet stabilization
- CTF2, alignment study
- Cooling induced vibrations

### • Current work

- Specifications for supporting system
- Conceptual design

### • Future work

- Continuation of vibration measurement
- System design
- System integration

Risto Nousiainen,  
17.10.2007



11

Presented by A. Latina

### Conclusion

- The fast beam ion instability is more important for the main than for the drive beam
- Expect to need good vacuum for drive beam (1ntorr)
  - need to explore lattice detuning

- We need very good vacuum in the main beam transfer lines
  - maybe optimised lattice

0.1 nTorr

- In the main linac we avoid the problem by not trapping the ions
  - But it is worth checking that the simple estimates are good enough
  - Parameters may change
  - The ions could affect the feedback systems
- ⇒ Should be able to simulate ions
  - simple programs exist
- ⇒ We need to integrate this

# THIN FILMS FOR CLIC ELEMENTS

## DB and MB transfer line

Total length: 2x 21km

2% filled with 1m long magnets: 2x 420 magnets

Diameter of the beam pipe  $\phi=40mm$

Limit pressure to avoid ion stimulated desorption:  $10^{-10}$  Torr ("large" molecules)

# THIN FILMS FOR CLIC ELEMENTS

## Outline

- Motivation
- The role of MME-CCS
- DB and MB transfer lines
- Main beam
- Main beam quadrupoles
- Other issues
- conclusions

CLIC workshop 17/10/2007

Pedro Costa Pinto TS/MME/CCS

Static vacuum

	q ( $10^{-12}$ Torr)	S ( $1/s$ )	L (m)	L (m)	
<del>No bakeout: main gas H<sub>2</sub>O</del>	<del><math>1.4 \cdot 10^{-12}</math></del>	<del>40</del>	<del>1.7</del>	<del>2.3</del>	
With bakeout: main gas H <sub>2</sub>	$5 \cdot 10^{-13}$	46	5.0	6.8	Possible solution...
With bakeout: CO	$5 \cdot 10^{-14}$	36	9.6	14	
With NEG: not pumped CH <sub>4</sub>	$10^{-17}$	28	814	1220	Better solution
With NEG: not pumped Kr	$2 \cdot 10^{-18}$	6	1202	1802	

# THIN FILMS FOR CLIC ELEMENTS

## Main Beam

Bakeout excluded: tight mechanical tolerances.

Pumping speed in the accelerating structures is limited

*If  $10^{-10}$  torr are necessary... this is a feasibility issue for CLIC!*

Dynamics of the H<sub>2</sub>O pumping in limited conductance systems must be better understood

An experimental set-up is being implemented to study H<sub>2</sub>O pumping dynamics

Best possible dynamic vacuum must be simulated

- Pumping speed and geometry
- Thermal desorption/adsorption rates
- Surface coverage vs time
- Ion desorption yields
- Ionization efficiency per train
- Ion bombardment of the walls
- Breakdown rate
- Gas released per breakdown
- .....

We propose monte carlo and electrical network analogy approach

# THIN FILMS FOR CLIC ELEMENTS

## Conclusions

•MB and DB transfer lines:  $10^{-10}$  torr feasible with bakout or NEG. (NEG better for dynamic vacuum). **Not a feasibility issue.**

•Main beam:  $10^{-10}$  torr not possible without heating the structures. Best possible dynamic vacuum must be simulated. H<sub>2</sub>O behavior must be studied. **feasibility issue.**

•Main beam quadrupoles: distributed pumping required. **Probably not a feasibility issue.**

•Combining rings: classical NEG solution. Input is necessary to correctly evaluate the situation. **Not a feasibility issue.**

•injection lines: maybe a SEY of 0.9 is required. **feasibility issue.**

## acknowledgments

Bernard Jeanneret and Daniel Schulte.