



- Results
- New installations
- RadMONs (2nd and 3rd Slots)
- Equipments to be tested in 2012

Results

• RF MosFETs

○ Motivation

- Having a deeper understanding of their behavior and limits

- ✓ **Used in the PS Booster over the last 20 years** → $10^5 - 10^6$ Gy without major failures

○ In the PSB → De-rated conditions:

- ✓ $V_{DS\ max} = 125\ V$ → Vdrain swings between 0-80V (40 V_{DC})

○ For the test:

- Test setup is placed inside the target area

- ✓ Dose expected from Slot3 to the end of the year ≈ **11 kGy** (*will depend on the new schedule*)


- Control/acquisition is located below station 2 with remote reset units

○ Test are performed in the worst case condition (80 V_{DC})

○ Evaluation:

- Failure rate to single events

- I_D vs V_G characteristic measurements vs dose



Results

• RF MosFETs

○ Motivation

- Having a deeper understanding of their behavior and limits

✓ **Used in the PS Booster over the last 20 years** → $10^5 - 10^6$ Gy without major failures

○ In the PSB → De-rated conditions:

✓ $V_{DS\ max} = 125\ V$ → Vdrain swings between 0-80V (40 V_{DC})

○ For the test:

- Test setup is placed inside the target area

use expected from Slot 2

(rule)

acquired

performed in the


kGy (will depend on new

reset units

○ Evaluation:


- Failure rate to single events
- I_D vs V_G characteristic measurement vs dose

Aborted due to a loss of communication with the PXI located below Station 2



Kept the MosFETs (without any control and DAQ system connected) inside the target area for the last Slot
→ Possibility to measure I_{ds} vs V_{gs} curve after irradiation

Actual levels:
Dose ≈ 6 kGy
HEH $\approx 3.8e13\ cm^{-2}$



Results

• Cryo test

○ Motivation

- Validate the design of a new power supply for the LHC beam screen heaters

○ Required dose: **Up to 1 kGy** → To validate up to the DS level

○ Decided test location : TSG45 – 451

- From Slot 3 to the end of the year \approx **1 kGy** (*will depend on the new schedule*)

○ For the application:


- Power supply will be “off” during beam
- Will be “on” only when the beam is off to supply the beam screen heaters

○ For the test:

- Off-line measurements at the end of each slot → 3 boards with MosFETs, 1 board will be removed at the end of each slot to measure I_{ds} vs V_{gs} curves.

- On-line measurements

→ Operate constantly or in switching mode to check if they failed during irradiation. Specific application.



Results

• Cryo test

○ Motivation

- Validate the design of a new power supply for the LHC beam screen heaters

○ Required dose: **Up to 1 kGy** → To validate up to the DS level

○ Decided test location : TSG45 – 451

- From Slot 3 to the end of the year \approx **1 kGy** (*will depend on the new schedule*)

○ For the application:

- Power supply will be “off” during beam
- Will be “on” only when the beam is off to supply the beam screen heaters

○ For the test:

Removal of 1 over 3 boards

Visual inspection of the 2 active MosFET boards

Installation of a new active board 4-channel analog Switches

Installation of a new passive board containing 6 analog switches

On the active board, 3/12 analog switches were not functioning at the end of Slot3



Results

• TE/EPC – Puls AC/DC Power Supply

○ Motivation

- Improvement of the Puls AC/DC power Supply used in the tunnel

○ It has been found that 2 different versions of the PSU exist


- One installed in the LHC (not rad. Tolerant).
- The second one not installed (seems to be more rad. tolerant)

○ Those PSU are built by the same manufacturer

- → Slight difference on the design for the same model → **COTS can show different behavior under radiation**

○ During slot 3, PSU failed at around **100 times higher HEH fluence** compare to the model installed in LHC.

○ During the last Slot, TE/EPC is testing **2 additional PSUs**.




New installations and results

- **LED Warning System**


- **Motivation**

- New prototype to be tested based on lessons learned from last year:
 - Safety lighting system powered by voltage transformer + Graetz bridge
 - Power LED technology
- The system is tested on 2 different locations:
 - **With monitoring** : Position 453
 - **Without monitoring** to test if the prototype can survive up to higher doses : Position 451
- Radiation levels since the beginning of the year:
 - **Position 453: Dose: 337 Gy - ϕ_{eq} : 3.4×10^{12} neq/cm² – HEH : 2.4×10^{12} cm⁻²**
 - **Position 451: Dose: 760 Gy - ϕ_{eq} : 7.5×10^{12} neq/cm² – HEH : 5.3×10^{12} cm⁻²**
- Up to now we are covering locations up to DS levels (close the quadrupole magnets (nom. operation):
 - ϕ_{eq} : 20 years
 - ϕ_{HEH} : 50 years
 - Dose: 4 years



New installations and results

- **LED Warning System**
 - **New installation**
 - Other lights
 - Type **400 W metal iodide**
 - Installed in **TCC2** → Several died
 - Radiation level is measured in TCC2 (end TS #4)
 - Which radiation levels can they stand in **CNRAD** ?
 - Correlation with measurement in **TCC2**



New installations and results

- **BPM components**


- **Motivation:**

- 4 SFP bidirectional transceivers:
 - 2 × manufacturers (Huihong – Ligent)
- 1 SFP Transceiver (2 fibers)
 - FFX Technology
- **Additional 12 SFP bidirectional transceivers have been installed**

- **QPS**

- **Motivation**

- Up to June, **only 1 μ FIP failure with auto-reset** has been detected and **no failure on the PhotoMos relay** has been observed so far.
- Radiation levels: Dose = 282 Gy, **$2 \times 10^{12} = \text{HEH}/\text{cm}^2$** and $\phi_{\text{eq}} = 2.7 \times 10^{12} \text{ cm}^{-2}$
- *In terms of HEH fluence, **we reached 20 years of LHC operation in the DS** (close to quadrupole magnets)*
- During slot 3 **one failure** occurred:
- **Check and re-start of one DUT during TS** → Installation of a remote reset box.



New installations

- **RadMON Version 6**


- **Motivation:**

- Test of 2 prototypes of the **next version of the RadMON**.
- Same used during the **H4 test** → They already get around **50 Gy** (**No failure observed**)
- Tests have been performed at **PSI** up to ≈ 300 Gy → **No failure observed**
- **Target dose: 200/300 Gy** → Installed in TSG45, position 451.

- **Acquisition crate for load sensors (BE/ABP)**

- **Motivation**

- They are installed in shielded area in P5 (2) and P2 (2). **After LS1, more will be installed**
 - **IP1** (US15) , **IP2** (UA23 & UA27), **IP5** (>LS1: IL55), and **IP8** (UA83 & UA87) → **Each IP : 2 crates**
- Target dose: **100 Gy** → Position 453
- Acquisition system composed by several semiconductor devices:
 - CMOS, MOSFET driver, FPGA (Xilinx CPDL), 12 bit DAC ...)




New installations

- **IT beacon**


- **Motivation**

- Will be installed everywhere in the **LHC tunnel**.
- 15 beacons installed in **TSG46** (data transmission monitored on-line)
 - Expected radiation levels:
 - Dose: : $\approx 30 \text{ Gy}$ (Nom. Operation \rightarrow **15 years** in the Arcs (dose))
 - HEH fluence: $\approx 1.5e11 \text{ cm}^{-2}$ (Nom. Operation \rightarrow **1,5 years** in the DS* (HEH fluence))
- 5 beacons installed in **TSG45** – position 453 (off-line). **Check if still working** at the end of the slot
 - Expected radiation levels:
 - Dose: $\approx 120 \text{ Gy}$ (Nom. Operation \rightarrow **7 months** in the DS* (dose))
 - HEH fluence: $\approx 8e11 \text{ cm}^{-2}$ (Nom. Operation \rightarrow **8 years** in the DS* (dose))

*In the DS, close to quadrupole magnets



RadMONs – 4th Slot



RM7 box (5V)
RM7 deported
RadFETs:
 400 nm
 1000 nm

RM10 box (3V)




RM10 deported
 (Target Area)
RadFETs:
 400 nm W5
 400 nm W8

RM8 deported
RadFETs:
 100 nm
 400 nm

RM8 box (3V)

During last slot, comparison between
W5 and W8 wafers → **Target Area**

Interesting results:



Equipments tested in 2012

- **BPM components**
- **LED warning system**
- **QPS**
- ~~**Ethernet Switches**~~
- ~~**Wifi access points**~~
- **Cryo power supply**
- **TE/EPC components**
- **Acquisition Crate load sensors (BE/ABP)**
- **IT beacons**
- **RadMON version V6**

