




# Measurements planned with the photo injector in CTFII



## Status



- Waiting
- Installation of the diagnostic beam line is being finished up
- Study of the integration into CTF3 done (EPAC 2006-paper)



S. Döbert, CTF3 collaboration meeting, Jan. 2008



# RF GUN Test in CTF II



## Beam parameters

$E = 5.6 \text{ MeV}$

$\Delta E = 1 \% ?$

$Q = 2.3 \text{ nC}$

$T_p = 1.5 \mu\text{s} (1.5 \text{ GHz})$



$\epsilon_N = 20 \text{ mm mrad}$

$\sigma_z = 10 \text{ ps}$

$N \sim 2000 \text{ bunches !}$





## RF GUN Test in CTF II





Philosophy: use existing parts and operate with CTF3 controls and data acq.



# Diagnostic section in CTF II



# RF GUN CTF2 , Simulations 25 deg







$E = 5.45 \text{ MeV}$


$\Delta E/E = 0.3 \%$

$bl = 5.7 \text{ ps (FWHM)}$

$\varepsilon_n = 15.4 \mu\text{m}$



# Fentes en tungstène



## Tungsten slit mask:

2 mm thick

0.1 mm slit width






0.8 mm distance

Matière: tungstène (fourni)

Epaisseur: 2 mm


2 pièces à réaliser

# RF GUN CTF2 , Emittance Measurement





# Desirable Measurements




- Beam current and position  
(fast WCM, BPR and Faraday Cup)
- Energy and energy spread, if possible time resolved  
(Spectrometer with OTR screen and a low power segmented dump)
- Emittance, if possible along the train  
(multi slit with OTR and ceramic screen,  
use of gated camera in principle possible)
- relative bunch length with wake field signal (BPR)
- use of a streak camera for longitudinal profile






# Studies



- Study and verify single bunch beam parameters as a function of rf-parameters, laser parameters and focusing  
Establish best working point !
- Add bunches and investigate stability of beam parameters along the train
- Study rf pulse compression, velocity bunching and emittance compensation for future CTF3 installation, CLIC and general interest
- 3 GHz and 1.5 GHz beams
- Verification of the phase switch for CTF3




## Comments




- Diagnostic session well advanced and should be ready for commissioning once the gun is available
- Emittance measurements will need some care and study
- Hired a doctoral student Öznür Mete to study the photo injector beam dynamics in detail
- Scheduling conflicts with drive beam commissioning have to be sorted out

# Integration of the PHIN - Photo injector into CTF3





Possible integration of the photo injector



# Photo injector integration

Option 1: rf-gun + 2 m drift to the first structure







$E = 5.4 \text{ MeV}$

$\Delta E/E = 0.2 \%$





$bl = 5.7 \text{ ps (FWHM)}$

$\epsilon_n = 11.9 \mu\text{m}$



# RF GUN in CTF3 , nothing for 2 meters


CTF2 RFGUN Test




# RF GUN with phase sag due to pulse compressor

## Output phase space variation (horizontal)

Gun only







After one structure



Emittance:  $1.8 * \text{Max} = 30$

# RF GUN in CTF3 with velocity bunching



Phase: -25 / -90 deg

Energy: 7.1 MeV

$\Delta E/E$ : 2.8 %

Bunch length: 2.0 ps

Emi: 14.6  $\mu\text{m}$

