


## Status report of RF guns construction at LAL

21-23 January 2008

G. Bienvenu, M. Desmons, M. Joré, B. Mercier, J. Prevost, C. Prevost, R. Roux  
LAL, IN2P3-CNRS, Université Paris-Sud, France


- 1- Construction of the photo-injector for the drive beam linac (PHIN)
- 2- Construction of the photo-injector for the probe beam linac

## 1- Construction of the PHIN gun




PHIN

The drawing:




## 1- Construction of the PHIN gun



Where are we since the last collaboration meeting?

All pieces of the gun sent to CERN to be brazed

=> gun brazed in December, 19<sup>th</sup>



**BUT:**  
Big leaks in the cooling tubes

CERN brazing workshop  
hopes to fix the problem

Delivery date: ??

## 1- Construction of the PHIN gun

There is a twin photo-injector, to be installed at LAL (**JRA objectives**)


Brazing was delayed because one cell was used for the CERN gun:  
and we decided to do it at LAL





Completion of brazing: mid-March

Accelerator ready by the end of Spring

Tapered waveguides are brazed




## 2- Construction of the probe beam gun



- Last year, all components were already there
- End of February: pieces of the gun were available to be brazed


!! Again, big delay  
due to brazing problems  
Change of staff

## 2- Construction of the probe beam gun



PHIN

Finally, gun was brazed just before Christmas and no leak at all



BUT

$$F_r = 2996.025 \text{ MHz !!}$$

Before brazing,  $f = 2997.9 \text{ MHz}$

Fortunately, we have two holes/cell  
 Thickness of cavity wall  $\approx 4 \text{ mm}$   
 $\Rightarrow$  deformation with a screw  
 to increase the frequency  
 in every cell to keep well balanced  
 electrical field.

Finally:  $f_r = 2998.057 \text{ MHz}$  for  $T = 20^\circ\text{C}$ ,  $H = 60 \%$ ,  $P = 1015 \text{ mbar}$   
 Width at  $-3 \text{ dB} = 452 \text{ kHz} \Rightarrow QL = 6633 \Rightarrow \beta = 0.96 \Rightarrow S11 = 0.02$   
 Field (perturbation method):

Half cell:  $\Delta f = 780 \text{ KHz}$

Middle cell:  $\Delta f = 780 \text{ KHz}$

Coupling cell:  $\Delta f = 790 \text{ KHz}$

## 2- Construction of the probe beam gun

Now, installation of components on the girder while I am speaking!



Date of delivery at CERN: January, 4 -14