

# Status of LHCb


Roger Forty (CERN)

*On behalf of the LHCb Collaboration*


1. Experimental infrastructure
2. Detector installation
3. Preparation for physics
4. Collaboration matters

# The LHCb Experiment

- Dedicated experiment for precision measurement of CP violation and rare decays of b-hadrons (and charm) at the LHC
- Collider-mode operation at same time as the general-purpose detectors, with less-focussed beams → most events have a single pp interaction



# 1. Experimental infrastructure



# Shielding wall




- Upper part completed  
Labour intensive “Egyptian work”  
as inaccessible by crane...



- Assembly of lower part  
is progressing well  
Paused while a problem with leaking  
cooling-water pipes is investigated



# View of the cavern



**It's full!**  
Installation of major structures is essentially complete

# Spectrometer magnet

- Warm dipole magnet completed and mapped two years ago
- Switched on again last month
- Operated from CERN Control Centre, together with the three compensating magnets
- Monitored by ECS:



LHCb dipole →


Compensators

Successful test




# Beam pipe

- Conical, three beryllium sections
- Installation now complete
- Aluminium spares being made (in case of accident)



# Bake-out


- Leaks developed in the third Be section during acceptance tests  
Sealed by LHC vacuum group (AT/VAC) using silicon varnish
- Bake-out completed successfully in June: ready for operation






# 2. Detector installation



RICH system + Track Calorimeter + Muon detector



# VELO





- 21 stations of Si wafer pairs with  $r$  and  $\phi$  strip readout
- Split in two halves to allow retraction from beam line
- Both detector halves now completed, installed in the pit



# RF-boxes

- Modules sit in secondary vacuum, separated from machine vacuum by 300  $\mu\text{m}$  AlMg3 foil RF-boxes
  - Intricately formed to allow for overlap of the two halves
- Leaks developed ( $\sim 10^{-5}$  mbar l/s) but only between primary and secondary vacua: no immediate concern for operation
  - R&D has started for replacement RF-boxes




# Installation of detector halves



C-side installation, 30 October (video extracts...)

# Installation of detector halves





- After completion: testing I/V characteristics of modules → all OK





# VELO readout

- Analogue readout → plenty of copper cables, all now installed
- First read-out of data (noise) using the full electronics chain




# Trigger Tracker

- VELO is in  $\sim$  field-free region  
→ straight tracks
- TT is a silicon microstrip detector placed in fringe field of magnet to give first  $p_T$  measurement for the trigger
- Sensor ladders all completed  
Excellent quality < 0.1% bad strips  
Detector boxes + infrastructure installed in pit
- Installation of sensors into detector boxes underway, will be complete end-2007




# Tracking Stations

- VELO + TT define tracks upstream of magnet  
IT + OT measure them after deflection:





# Inner Tracker



- IT ladder production complete  
Support system + infrastructure ready
- Mounting of silicon detectors in their boxes in progress
- First two boxes installed in pit  
Remaining 10 installation ~ one/week


# Outer Tracker

Modules with 5° stereo angle






- Drift chambers: straw tubes 5 mm diameter, 5 m length
- Detector installation complete  
Electronics installation underway
- Cosmic trigger counters set up for commissioning

Raw hit map of cosmons over 7 modules




# OT gain-loss issue (recap)

- Extensive ageing studies made during R&D phase
  - Expect 1 C/cm integrated charge at hottest region after 10 years
  - High rate, high dose tests → no ageing detected
- However, irradiation with weak lab source for a short period (left over a weekend)
  - Significant gain loss observed
  - Similar results with  $^{90}\text{Sr}$  ( $\beta$ -emitter)
  - Largest effect for 2–5 nA/cm




Ratio of signals after/before irradiation


# Culprit identified



- Test chamber built without glue




20 mCu  
480 hours



Araldite (AY103)  
added at entrance


- 1 m-long chambers constructed with different glue:




- Trabond (2115) gives no apparent gain loss
- Problem is from out-gassing of Araldite

# Minimising the effect

- The gain-loss effect is clearly reduced by flushing chambers
  - All modules are continuously flushed, including next ~ year to first data
- Warming modules to 40°C during flushing also helps
  - Heating jackets prepared for use in situ





After 10 days heating




# Effect on experiment


- Strongly varying occupancy over OT  
→ variation of current expected
  - Region likely to be affected is close to beam pipe
- If flushing + heating does not remove gain-loss effect, would start to see lower efficiency in those modules
- Effect can be repaired (temporarily) by HV training
  - 20 hours at 1.9 kV
- Module production capability will be maintained, and we will investigate resources required for production of replacement modules in case of need



# RICH system




- Two RICH detectors to cover momentum range 2–100 GeV
- RICH-2 already completed last year, was only waiting for its photon detectors
- RICH-1 now nearly complete  
Aerogel radiator delivered



# RICH-1 mirrors



- Material budget critical for spherical mirrors as inside tracking volume
- Carbon fibre construction: 1.5%  $X_0$  produced by CMA (US) and coated by SESO (France)






# Photon detectors



- After the long history of HPD development, production of all 550 required tubes is now complete! (Principal industrial partner: DEP, Holland)
- Excellent performance measured




# RICH-2 commissioning


- RICH-2 is now fully equipped with 288 HPDs
  - 10 cannot take 20 kV (~3%), to be replaced

- Commissioning is in progress

Pattern of light spots projected onto the HPD plane  
(will be used for calibration of magnetic distortions)





Note: this layout is a feature of the display—  
tubes are hexagonally close-packed in reality





Number of photoelectrons

# Calorimeter system

- Composed of Scintillating Pad Detector/PreShower + ECAL + HCAL
- First priority: Level-0 trigger




ECAL: Pb/sci.fi. Shashlik (25 X<sub>0</sub>)






# Calorimeter system

- Complete calorimeter system has been installed and cabled; Commissioning now in progress
- Cosmics not very well adapted for use in LHCb (few are horizontal 100 m underground)  
Nevertheless, cosmic triggers being set up for calorimeter commissioning
- In the mean time, system exercised using LED pulses: signal display in HCAL after reconstruction via full chain




# Muon detector

- All MWPCs for Muon detector stations M2–5 installed except for 20 (out of 1084, ~2%) that need to be replaced
- All MWPCs and 3-GEMs for M1 produced



# M1 installation

- Completion of the M1 infrastructure expected early 2008
  - Delayed: priority given to completing M2–5
  - Has to fit in the crowded region between RICH-2 and Calorimeters:




- Installation of chambers will follow, but may not be complete for the 2008 run
  - Use of M1 is to improve  $p_T$  determination in the Level-0 trigger
  - Not crucial for the low-rate conditions expected in 2008

# Trigger

- Trigger has two levels:
  1. Level-0 (hardware, 1 MHz output)  
Full detector then read out into farm of commercial CPUs
  2. HLT (software, 2 kHz output → storage)
- Level-0 uses information from:
  - *Pile-up system*  
Dedicated silicon sensors in VELO tank  
fast detection of multiple pp vertices
  - *Calorimeter trigger*  
high- $p_T$  clusters from e,  $\gamma$ , h
  - *Muon trigger*  
high- $p_T$  ( $> \sim 1$  GeV)  $\mu$  candidates
- Production of all Level-0 electronics boards now complete
  - Commissioning in progress



*L0 Decision Unit*  
→ overall decision



L0DU card

# High Level Trigger


- First release of complete HLT framework last month  
Suitable for benchmarking CPUs to be purchased for the farm
- Implements strategy of “trigger confirmation”  
HLT focuses on confirming objects that triggered Level-0  
by matching them to tracks in VELO or T-stations
  - *eg* confirm L0 muons in T stations, extrapolate to origin, calculate mass  
→ online  $J/\psi$  (takes  $\sim 1$  ms)





# Online system

- Three major subsystems:
  - TFC: Timing and Fast Control
  - DAQ: Data Acquisition
  - ECS: Experiment Control System



- In LHCb the ECS is used to control the DAQ, as well as for monitoring and control of the detectors
  - “One click” starting of a run recently achieved (reading RICH-2)

# Data Acquisition


- Common read-out board used by most detectors (TELL1) all now installed
- Read-out network is based on Force10 switch (E1200, as used by CERN/IT)
- Control room is now equipped — and is being used!



# CPU farm

- CPU farm for HLT (and monitoring) will eventually be 1000–2000 boxes
  - Depends on price/performance of CPU selected (and processing time required for HLT)
  - Market survey completed, tendering underway for first slice
- Due to lower rates expected at start-up, plan to install ~20% of CPU farm and switch capacity by May 2008, remainder early 2009


Recent test of CPU performance





# 3. Preparation for physics

- Alignment of detectors under study using simulation
  - Matrix inversion (Millepede) and iterative residual minimisation
- Exercising alignment techniques using test-beam data

RICH ( $C_4F_{10}$  radiator gas)




VELO






# Computing

- Successful use of Grid made for large scale simulation + reco.
  - >  $10^8$  fully-simulated events recently generated (“DC06” data) including  $b\bar{b}$  background at  $2$  and  $5 \times 10^{32} \text{ cm}^{-2}\text{s}^{-1}$  luminosity
- However, difficulties encountered with “stripping” the data
  - After reconstruction, first step for physics analyses is to centrally run pre-selections (with loose cuts) for the channels of interest
  - Jobs need to read in rDST’s and write DST’s (+ETC) at Tier-1 sites (CERN, CNAF, GridKa, IN2P3, NIKHEF, PIC, RAL)  
Problems encountered with storage management at the sites  
→ stripping of DC06 data now restarted + reprocess at same time
- Use of the Grid for analysis jobs is increasing steadily




# Reconstruction

- Continuous effort made to maintain excellent performance of tracking and particle ID software
  - Keep up with added realism in simulation (tilted detectors, updated material budget)
  - Prepare for adaptation to real data
- Tracking developed for open VELO (will be important at start of run)



# Physics studies

- References to recent analyses collected together on a web page [http://lhcb-phys.web.cern.ch/lhcb-phys/DC04\\_physics\\_performance](http://lhcb-phys.web.cern.ch/lhcb-phys/DC04_physics_performance)
- Keeping an eye on the impressive progress of the B factories:
- **Observation of  $D^0-\bar{D}^0$  mixing:**
  - Time dependence of  $\sim 4000$  wrong-sign  $D^0 \rightarrow K^+\pi^-$  decays
  - LHCb has  $\sim 300$  Hz of trigger output rate dedicated to charm...  
→ 47,000 tagged wrong-sign decays/year ( $2\text{fb}^{-1}$ )
  - Will probe CP violation in the  $D^0$  system at the  $10^{-3}$  level
- **First constraints on CKM angle  $\gamma$  using  $B^\pm \rightarrow D(K_S\pi^+\pi^-) K^\pm$**





## Summary of DC04 physics performance

[Home](#)
[Physics](#)
[E-mail](#)
[Notes](#)
[Meetings](#)
[Search](#)

Quick access to sections of this page: [Expected yields and sensitivities](#) | [Flavour tagging and proper time](#) | [Reconstruction](#) | [DC04 MC samples](#) |

This page summarizes the LHCb physics performance obtained at the end of 2007 using Monte Carlo studies based on the so-called [DC04 samples](#). These results, documented in [public LHCb notes](#), update and supersede the ones reported in the physics chapter of the [LHCb re-optimization TDR](#).

### Expected yields and sensitivities

Decay mode	Total eff. (%)	2 fb <sup>-1</sup> signal yield	B <sub>bb</sub> /S	B <sub>specific</sub> /S	Physics observable	2 fb <sup>-1</sup> statistical precision	10 fb <sup>-1</sup> statistical precision	Assumptions, comments	More info
<i>B<sub>u</sub> control channels</i>									
B <sub>u</sub> → D <sup>0</sup> •+ν	0.125	2.4M	0.75±0.03						<a href="#">CERN-LHCb-2006-058</a>
B <sub>u</sub> → D <sup>0</sup> (Kπ)π <sup>+</sup>	0.64	1.0M	0.13±0.03						<a href="#">CERN-LHCb-2006-058</a>
<i>B<sub>s</sub> mixing effects (including CPV) in tree decays</i>									
B <sub>s</sub> → D <sub>s</sub> <sup>-</sup> •+ν	0.123	1.06M	0.36±0.13						<a href="#">CERN-LHCb-2007-029</a>
B <sub>s</sub> → D <sub>s</sub> <sup>-</sup> π <sup>+</sup>	0.39	140k	[0.014,0.05] 90% CL	[0.08,0.4] (all) 0.044±0.014 (Dπ)	Δm <sub>s</sub>	0.007 ps <sup>-1</sup>		B/S=0.2	<a href="#">CERN-LHCb-2007-017</a> <a href="#">CERN-LHCb-2007-041</a>
B <sub>s</sub> → D <sub>s</sub> K <sup>±</sup>	0.32	6.2k	< 0.18 90% CL	[0.08,3] (all) 0.15±0.05 (D <sub>s</sub> π)	γ <sup>+</sup> φ <sub>s</sub> (tagged) γ <sup>+</sup> φ <sub>s</sub> Δ(T1/T2)  λ	12.7 deg 10.3 deg 10.3 deg 0.061	5.7 deg 4.6 deg 4.6 deg 0.027	B/S=0.7	<a href="#">CERN-LHCb-2007-017</a> <a href="#">CERN-LHCb-2007-041</a>
B <sub>s</sub> → J/ψ(••)φ	2.05	131k	0.12±0.03		R <sub>T</sub> ΔΓ <sub>s</sub> /Γ <sub>s</sub> φ <sub>s</sub>	0.0004 0.0092 0.023			<a href="#">CERN-LHCb-2006-047</a> <a href="#">CERN-THESIS-2006-042</a>
B <sub>s</sub> → J/ψ(••)η(γγ)	—	~8.5k	2.0 (tot)		φ <sub>s</sub>	0.109			



# $B^\pm \rightarrow D(K_S \pi^+ \pi^-) K^\pm$

- Mode used by B factories to give best existing constraint on CKM angle  $\gamma$ :


$53^\circ \begin{smallmatrix} +15^\circ \\ -18^\circ \end{smallmatrix} \pm 3^\circ \pm 9^\circ$  [Belle]

$92^\circ \pm 41^\circ \pm 11^\circ \pm 12^\circ$  [BaBar]


(stat, syst, model)

$\sim 400$  events each

- LHCb yield  $\sim 5000$  events/2 fb $^{-1}$
- Spot the difference between the Dalitz plots for B $^+$  and B $^-$   $\rightarrow$  effect of CP violation
- Binning can reduce model dependence  
Precision on  $\gamma \sim 12^\circ$  (in one year)




hep/ph 0703267





# Physics Studies (continued)

- Preparing to open up the  $\sim$  unexplored  $B_s$  sector
- Current competition is from the Tevatron experiments  
*eg* measurement of the  $B_s - \bar{B}_s$  mixing phase  $\phi_s$ 
  - Counterpart for  $B_s$  system of the  $B^0 - \bar{B}^0$  mixing phase  $\phi_d = 2\beta$   
Very small in the Standard Model:  $-2\lambda^2\eta \approx -0.04$  rad
  - First experimental constraint from D0:  $\phi_s = -0.79 \pm 0.56$  rad  
using  $\sim 1000 B_s \rightarrow J/\psi \phi$  events [PRL 98/121801]
  - LHCb expects  $\sim 130,000$  events/year ( $2 \text{ fb}^{-1}$ )  
 $\rightarrow \sigma(\phi_s) = 0.02$  rad
- Preparing analyses where we can make an early impact
  - *eg*  $B_s \rightarrow \mu^+\mu^-$



$$B_s \rightarrow \mu^+ \mu^-$$

- BR =  $(3.4 \pm 0.5) \times 10^{-9}$  in Standard Model  
Can be significantly enhanced in SUSY
- Current limit  $< 47 \times 10^{-9}$  at 90% CL [CDF]
- Using loose selection, LHCb expects
  - ~ 40 signal events/2 fb<sup>-1</sup> (SM BR)
  - ~ 1500 bkg evs (mostly  $b \rightarrow \mu, \bar{b} \rightarrow \mu$ )
  - Statistical method then applied to separate signal from background using particle ID, vertexing and mass variables
  - $\sigma(m_{\mu\mu}) = 18 \text{ MeV}$
- Limit set at 90% CL (if no signal):  
Already interesting for 0.1 fb<sup>-1</sup>



# 4. Collaboration matters

- LHCb is a collaboration of ~ 650 members from 48 institutes
  - in Brazil, China, France, Germany, Ireland, Italy, Poland, Romania, Russia, Spain, Switzerland, Ukraine, UK, and the US
- At our last collaboration week (11-14 September):
  - University College Dublin was admitted as a full member (previously Technical Associate)
  - Olav Ullaland (CERN) took over from Alasdair Smith as Resource Coordinator
  - Andrey Golutvin (ITEP) was elected as new Spokesperson  
He will take over from our first spokesperson, Tatsuya Nakada on 1 May 2008 for 3 years




# Cost and Funding

- The cost of the experiment is **75.3 MCHF**, unchanged from MoU and last LHCC status report (15 November 2006)
- At that time 1.3 MCHF was missing from the funding  
Since then extra contributions have been pledged:  
kCHF 55 (Brazil), 300 (France), 20 (Spain), 400 (UK), 500 (US)  
→ **Experiment is now fully funded**
- Further expenditure is however foreseen:
  1. *Replacement of the third beryllium beam pipe section*  
Installed section UX85/3 had minor leaks, closed with varnish  
OK for initial operation, but concern for long-term reliability
  2. *Replacement set of VELO modules*  
The installed silicon sensors will receive a substantial radiation dose  
Expected to survive for  $\int L \sim 6 \text{ fb}^{-1}$  (i.e. 3 “nominal” years)  
Profit from existing production setup to produce a replacement set

# Organization (simplified)

New bodies introduced  
to adapt to next phase:  
Construction → Exploitation

Preparation for  
the future



# Upgrade Working Group

- LHCb is designed to run at an average luminosity of  $2 \times 10^{32}$  and be able to handle  $5 \times 10^{32} \text{ cm}^{-2}\text{s}^{-1}$  for short periods
  - For a “nominal” year of  $10^7$  seconds this corresponds to  $2 \text{ fb}^{-1}$   
Most physics goals are expressed in terms of the reach for  $10 \text{ fb}^{-1}$   
(i.e. 5 nominal years)
- Sensitivities would then only slowly increase → investigating upgrade of detector to handle higher luminosity:  $\text{few} \times 10^{33} \text{ cm}^{-2}\text{s}^{-1}$ 
  - Not directly coupled to SLHC machine upgrade, since already available, but may well overlap in time with upgrades of ATLAS+CMS
- Working Group set up to identify the R&D required to make an upgrade of LHCb feasible, and to make the physics case
  - Issues of triggering, fast vertex detection, electronics, radiation dose, handling the pile-up and higher occupancy, etc...
  - Expression of Interest for R&D towards an upgrade is in preparation

# Conclusion

- Installation of LHCb is almost complete
  - All major structures are in place (except for M1, in progress)
  - Sensitive elements are now produced and mostly in place: RICH-1, the Silicon Trackers, and M1 remain to be instrumented, schedule continues to be tight for those detectors
  - Progress made to understand and minimise the OT gain-loss
- Commissioning is now underway
  - Using cosmics where possible, otherwise test pulses, light spots, etc.
  - The first beam-gas events will be very instructive
- Preparation for physics continues
  - The experiment, including software, will be ready for first beam
  - Important measurements can be made even with  $0.1 \text{ fb}^{-1}$  of data

We are eager to see the first collisions!