QXF magnet design and plans

G. Ambrosio and P. Ferracin

HiLumi-LHC/LARP Conductor and Cable Internal Review 16-17 October 2013 CERN



Outline

- Overview of magnet design
- Strand parameters
- Cable dimensions (first iteration)
- Insulation thickness
- Coil design and cable unit lengths
- Short sample current and magnet parameters
- Planning for short and long models
- Risk analysis



QXF magnet design

- Target: 140 T/m in 150 mm coil aperture
- OD: 630 m
- SS shell, 8 mm for LHe containment
- Al shell, 29 mm thick
- Iron yoke
 - Cooling holes
 - Slots of assembly/alignment
- Master plates
 - 58 mm wide bladder
- Iron pad
- Aluminum bolted collars
 - Coil alignment with G10 pole key
- Ti alloy poles





From HQ to QXF

- Similar coil lay-out
 - 4-blocks, 2-layer with same angle
 - Wider cable (from 15 to 18 mm), same stress with +30% forces
- Same structure concept with additional accelerator features
 - Pre-load capabilities of HQ design qualified and successfully tested
 - Larger pole key for cooling holes, cooling channels, alignment assembly
 - handling slots, LHe vessel





Engineering design (work in progress)





Paolo Ferracin

5

Strand

(from CERN technical specification document)

- 0.85 mm strand
 - OST RRP
 - 108/127, 132/169 and 144/169
 - Bruker PIT
 - 192 filaments
- Cu/Sc: **1.2** → 55% Cu
 - For 108/127 and 144/169: 1.13
- Maximum critical current at 4.2 K
 - 361 A at 15 T
 - 632 A at 12 T



RRP strand









7

Cable insulation



- AGY S2-glass fibers 66 tex with 933 silane sizing
- 32 (CGP) or 48 (NEW) coils (bobbins)
- Variables: # of yarn per coil and of picks/inch
- Target: \leq 150 μ m per side

Samples	Insulated cable thickness (mm)	Bare cable thickness (mm)	Insulation thickness (µm)
S1	1.822	1.530	146
S2	1.823	1.531	146
S3	1.821	1.530	146





2D magnetic design

(By F. Borgnolutti)

Paolo Ferracin

- Two-layer four-block design
- Analytical model with sector coil
 - 6 angles to optimize for field quality
- Criteria for the selection
 - Maximize gradient and # of turns (protection)
 - Distribute e.m. forces and minimize stress
- Result: 22+28 = 50 turns

ligh

uminosity

U.S. LARP

All harmonics below 1 units at $R_{ref} = 50 \text{ mm}$







200

9

250

Lengths



	Short model	Q1/Q3 (half unit)	Q2
Magnetic length [m]	1.2	4.0	6.8
"Good" field quality [m]	0.5	3.3	6.1
Coil physical length [m]	1.5	4.3	7.1
Cable unit length per coil [m]	150	430	710
Strand per coil [km]	6.5	18	30



Superconductor properties and I_{ss} computation

- Non-Cu J_c of virgin strand without self field (s.f.) correction
 - 2450 A/mm² (12 T, 4.2 K) - 632 A
 - 1400 A/mm² (15 T, 4.2 K) - 361 A
- Self field corr. (ITER barrel)
 - 0.429 T/kA
- 5% cabling degradation
- Godeke's parameterization





Magnet parameters

- Operational conditions: 140 T/m
 - *I_{op}*: 17.5 kA
 - B_{peak_op} : 12.1 T
 - 82% of I_{ss} at 1.9 K
 - *G_{ss}*: 168 T/m
 - *I_{ss}*: 21.2 kA
 - *B_{peak_ss}*: 14.5 T



- Stored energy: 1.3 MJ/m
- Inductance: 8.2 mH/m





SQXF status and plan

- First generation cable in 06/2013
- Coil design with 1st generation cable in 07/2013
- Coil parts fabrication/optimization in progress
 - Decision on end parts for first generation coils: 01/2014
- Coil tooling
 - Winding and curing tooling by 11/2013
 - Reaction and impregnation tooling by 02/2014
- Fabrication of full practice coil starts, both at CERN and in the US, in 02/2014 (with 1st gen. cable)
- 2nd gen. cable by 06/2014
- 2nd gen. coil fabr. starts in 03/15 (LARP) and 05/15 (CERN)



SQXF plan and schedule Coil fabrication

• CERN

- 1st gen. cable
 - 2 practice coils
 - 1 mirror coil
 - 5 RRP coils
- 2nd gen. cable
 - 6 PIT coils
 - 5 RRP coils

• LARP

- 1st gen. cable
 - 2 practice coils
 - 1 mirror coil
 - 5 RRP coils
- 2nd gen. cable
 - 5 RRP coils



SQXF plan and schedule Coil fabrication

	Task	Task Name	Duration	Start	Finish Pre					2014						2015						2016						2017
	Mode		•	•	•	May	/ Jul	Sep	Nov	Jan	Mar	May	Jul	Sep	Nov	Jan	Mar	May	Jul	Sep	Nov	Jan	Mar	May	Jul	Sep	Nov	Jan
24	3	First generation cable geometry	0 days	Sat 01/06/13	Sat 01/06/13	•	01/06																					
25	-	Second generation cable geometry	0 days	Mon 02/06/14	Mon 02/06/14							•	02/06															
26	3	Coil fabrication CERN	806 days	Wed 08/01/14	Wed 08/02/17						-	1	-	:			:		:		-	1		-				
27	3	End parts decision	0 days	Wed 08/01/14	Wed 08/01/14					Ø8/	/01																	
28	3	First generation coils	445 days	Mon 03/02/14	Fri 16/10/15						-	-	-				-			÷ •	4							
29	3	E Coil C1 (practice)	120 days	Mon 03/02/14	Fri 18/07/14						-	-	-	-										-				
34	3	Coil C2 (practice)	120 days	Mon 28/04/14	Fri 10/10/14							<u> </u>	-							1								1
39	3	Coil C3 (RRP) for mirror	100 days	Mon 21/07/14	Fri 05/12/14															1								
44	3	Coil C4 (RRP)	100 days	Mon 22/09/14	Fri 06/02/15																							
49	3	E Coil C5 (RRP)	100 days	Mon 24/11/14	Fri 10/04/15																							
54	3	Coil C6 (RRP)	100 days	Mon 26/01/15	Fri 12/06/15												:											
59	3	Coil C7 (RRP)	100 days	Mon 30/03/15	Fri 14/08/15													:										
64	3	Coil C8 (RRP)	100 days	Mon 01/06/15	Fri 16/10/15																1							
69	3	Second generation coils	398 days	Mon 03/08/15	Wed 08/02/17														-	-	-	1	-	:	:		:	
70	3	Coil C9 (PIT)	100 days	Mon 03/08/15	Fri 18/12/15														-	-	÷							
75	3	E Coil C10 (PIT)	100 days	Thu 17/09/15	Wed 03/02/16															-	-							
80	3	Coil C11 (PIT)	100 days	Tue 03/11/15	Mon 21/03/16																÷—	+						
85	3	Coil C12 (PIT)	100 days	Fri 18/12/15	Thu 05/05/16						-											<u> </u>		÷				
90	3	E Coil C13 (PIT)	100 days	Wed 03/02/16	Tue 21/06/16																			÷				
95	3	Coil C14 (PIT)	100 days	Mon 21/03/16	Fri 05/08/16									-										-				
100	3	Coil C15 (RRP)	100 days	Thu 05/05/16	Wed 21/09/16																							
105	3	Coil C16 (RRP)	100 days	Thu 09/06/16	Wed 26/10/16									-						1						_	į	
110	3	Coil C17 (RRP)	100 days	Thu 14/07/16	Wed 30/11/16															1								
115	3	Coil C18 (RRP)	100 days	Thu 18/08/16	Wed 04/01/17																							b
120	3	Coil C19 (RRP)	100 days	Thu 22/09/16	Wed 08/02/17									-						1				1			:	
125	3	Coil fabrication LARP	488 days	Wed 05/02/14	Fri 18/12/15						-	-	-	-	:		-		-	-	-							
126	3	First generation coils	301 days	Wed 05/02/14	Wed 01/04/15									:	:		-			-								
127	3	Practice Coil #L1	108 days	Wed 05/02/14	Fri 04/07/14							-	÷							1								
132	3	Practice Coil #L2	120 days	Thu 13/03/14	Wed 27/08/14							-	÷	Ż														
138	3	Coil #L3 (for mirror test)	88 days	Mon 14/04/14	Wed 13/08/14						÷	-	÷															
143	3	Coil #L4	107 days	Mon 07/07/14	Tue 02/12/14								<u> </u>	:														
150	3	Coil #L5	102 days	Mon 28/07/14	Tue 16/12/14									:														1
156	3	Coil #L6	120 days	Mon 18/08/14	Fri 30/01/15									:	:													1
163	3	Coil #L7	98 days	Wed 01/10/14	Fri 13/02/15										:									1				1
169	3	Coil #L8	116 days	Wed 22/10/14	Wed 01/04/15										-	I				-				-				1
176	3	Second generation coils	207 days	Thu 05/03/15	Fri 18/12/15								1					:	:	:	-	, I						1
177	3	Coil L9	107 days	Thu 05/03/15	Fri 31/07/15								1	-				:		1								1
184	3	🕀 Coil L10	107 days	Thu 09/04/15	Fri 04/09/15															φ								1
191	3	Coil L11	107 days	Thu 14/05/15	Fri 09/10/15													-	:	÷				1				
198	3	Coil L12	107 days	Thu 18/06/15	Fri 13/11/15								1	-					-	-	÷							1
205	3	🛨 Coil L13 (spare)	107 days	Thu 23/07/15	Fri 18/12/15															-	-	7		1				1



SQXF plan and schedule Tests

- 1st generation coils
 - First LARP coil mirror test in 12/2014
 - First **CERN coil mirror test** (mirror) in 04/2015
 - First magnet test (SQXF1) in 05/2015
 - Assembled and tested by LARP with 3 LARP coils and 1 CERN coil
 - Then SQXF1b (LARP), SQXF2 (CERN), SQXF2b in series (2015-2016)
 - All the coil fabricated to date will be available for 1 magnet (not shared)
 - Test of LHe containment in SQXF2b
- 2nd generation coils
 - LARP RRP: SQXF3 and SQXF3b (2016)
 - CERN PIT: SQXF4 (2016-2017)
 - CERN RRP: **SQXF5** (2017)
- Test of 2-magnets in 1-cold-mass: SQXF6 (2017)





CERN long models Schedule

- Coil winding starts in 09/2015
 3 practice, 6 RRP, 6 PIT
- Mirror test in end 2016 / early 2017
- First long model by mid-2017
- 2 long models, 4 tests in 2017-2018

Tas	k	Task Name	Duration	Start	Finish	Predecessors	1	2014				2015			2016			2017				2018		2019
Mo	je 🔻		-	-	-	-	r	1st Qu	Jarter	3rd Quart	er	1st Quarter	3rd C	Juarter	1st Quarter	3rd	Quarter	1st Quar	rter	3rd Quarte	r	1st Quarter	3rd Quarter	1st Quarter
							Nov	Jan I	Mar May	Jul Sep	Nov	Jan Mar May	Jul	Sep Nov	Jan Mar M	lay Jul	Sep No	v Jan Ma	ar May	Jul Sep	Nov	Jan Mar Ma	y Jul Sep N	ov Jan Mar
5 🗟		Long prototype program	1403 days?	Wed 01/01/14	Fri 17/05/19			Ý			-								1 1					
6 🗟		E Long prototype tooling design and fabrication	435 days?	Wed 01/01/14	Tue 01/09/15			Ý Ť			-		-											
10 🔁		Long prototype coils fabrication	616 days	Wed 02/09/15	Wed 10/01/18	1										-						7		
11 🔁		Practice coil 1	132 days	Wed 02/09/15	Thu 03/03/16									<u> </u>										
15 🗟		Practice coil 2	132 days	Tue 03/11/15	Wed 04/05/16	i								, <u> </u>										
19 🗟		* Practice coil 3	110 days	Wed 03/02/16	Tue 05/07/16											-								
23 🔁		🗄 Coil 4 (RRP mirror coil)	110 days	Tue 05/04/16	Mon 05/09/16											_								
27 🔁		🗄 Coil 5 (RRP)	110 days	Mon 06/06/16	Fri 04/11/16						-					v i	÷ • •							
31 🗟		🗄 Coil 6 (RRP)	110 days	Fri 05/08/16	Thu 05/01/17						1							-						
35 🔁		🗄 Coil 7 (RRP)	110 days	Thu 06/10/16	Wed 08/03/17	,	1																	
39 🗟			110 days	Wed 07/12/16	Tue 09/05/17						-							+++	-					
43 🗟		Coil 9 (RRP)	110 days	Tue 07/02/17	Mon 10/07/17														-					
47 🗟		🗄 Coil 10 (PIT)	110 days	Thu 09/03/17	Wed 09/08/17	,																		
51 🗟		Coil 11 (PIT) Coil 11 (PIT)	110 days	Mon 10/04/17	Fri 08/09/17						1									-				
55 🗟		Coil 12 (PIT) Example 12 (PIT)	110 days	Wed 10/05/17	Tue 10/10/17						-													
59 🗟		🗄 Coil 13 (PIT)	110 days	Fri 09/06/17	Thu 09/11/17																			
63 🚭		Coil 14 (PIT)	110 days	Tue 11/07/17	Mon 11/12/17															<u> </u>				
67 🗟		Coil 15 (PIT)	110 days	Thu 10/08/17	Wed 10/01/18	1					-													
71 🗟		Long prototype magnets	704 days	Tue 06/09/16	Fri 17/05/19						1						<u> </u>		÷				++++	
72 🔁		* MQXFLP mirror; coil 4	132 days	Tue 06/09/16	Wed 08/03/17	,											÷							
76 🔧		* MOXFLP1: coil 5.6.7.8	132 davs	Wed 10/05/17	Thu 09/11/17						-								-					
80 🗟		MOXFLP1b: coil 6.7.8.9	, 132 davs	Fri 10/11/17	Mon 14/05/18						-													
84 🖶		* MOXELP2: coil 10.11.12.13	132 days	Tue 15/05/18	Wed 14/11/18	1					1													
88 🕄		* MOXELP2h: coil 12 13 14 15	132 days	Thu 15/11/18	Fri 17/05/19						-											The second se		
4		- mora cr20, con 12,13,14,13	1.25 0.043	1110 13/11/10	1117/03/13			1	:	: :	-		: :	: :	1 : :		: :	1 :	: :		- 1	: :	- 1 - 1 ™	1 :



LARP long models Schedule

- Coil winding starts in December 2014
- Mirror test in September 2015
- First LQXF test in August 2016
- 3 LQXF tested by end of 2017





Cable Compaction - Risk Analysis: Winding stability vs. Sheared sub-elements

Risk	Mitigation plan(s)	Effects of mitigation failure	Probability of mitigation failure	Risk rating
Popped strands	Wind with tool (HQ02/03)			
➔ Electrical failures	Use binder (11 T)			
➔ Degradation	Online turn-turn short detection			
	Impulse test			
	➔ Reject coil after QA tests			



Cable Compaction - Risk Analysis: Winding stability vs. Sheared sub-elements

Risk	Mitigation plan(s)	Effects of mitigation failure	Probability of mitigation failure	Risk rating
Sheared subelements	Extracted strand tests			
➔ Limited stability	Cable tests			
➔ limited magnet performance	➔ Reject unit length			
High Interiore	†Ba:	De de Second		

HC

U.S. LARP

Additional slides



3D magnetic design

(By S. Izquierdo Bermudez, 1PoAN-04)

- From 4 (HQ) to 6 blocks in the ends
 - Impact on field quality: $b_6 < 1.1$ unit and $b_{10} < 0.2$ unit
- Iron pad removed with reduced length
- 1% peak field margin in the end
- Short model
 - Magnetic length 1.2 m
 - Coil length: 1.5 m
 - Good field quality region: 0.5 m







Mechanical analysis

(by M. Juchno)

- Optimization of dimensions and locations of new features
- ≥2 MPa of contact pressure at up to 155 T/m (~90% of I_{ss})
- Peak coil stress: -160/-175 MPa
- Coil displ. from start to nominal grad.
 - Radial/azimuth.: -0.3/-0.04 mm
 - Effect on field quality: 0.75 units of b_6







Quench protection

(see T. Salmi, 2PoCC-03, and G. Manfreda, et al., 2PoCC-05)

- Trace with 4 heaters strips per coil, with 50 µm polyimide insulation
 - Heating stations in outer layer only
 - Heater delay of about 17 ms
- Before, **10** ms of validation and, after, **20** ms of outer-to-inner delay
- Hot spot T of 350 K (34 MIITS) hardly achieved with no margin
- Under study

Luminosity

U.S. LARP

- Modelling of material properties (bronze) and quench-back + *dl/dt* effects
- Reduced delay of heater (25 μm polyimide?) and inner layer quenching



Naming (proposal)



	Drawing	Cryo- magnet	Cold mass	Magnets
Q1		LQXFA	LMQXFA	
Q3		(LQXFB)	(LMQXFB)	MQXF
Q2a		LQXFC	LMQXFC	MQXFL +
Q2b		(LQXFD)	(LMQXFD)	MCBXFA/B
D1		LBXF	LMBXF	MBXF



High

uminosity

6th HL-PLC

SQXF plan and schedule Coil fabrication

CERN

- Fabrication steps
 - Winding + curing + reaction + impregnation

- Fabrication time
 - ~100 days (5 months) per coil
 - 1 coil produced

uminositv

- every 2 months in the 1st year
- every 1.5 months in the 2st year
- every 1 months in the 3st year

LARP

- Fabrication steps
 - First generation
 - FNAL & LBNL: winding + curing
 - BNL & FNAL : reaction + impregnation
 - Second generation
 - LBNL on SQXF
 - FNAL and BNL on LQXF
- Fabrication time
 - ~100 days (5 months) per coil
 - 1 coil produced every month



16/10/20136th HbgPLC

Engineering design (work in progress)





Additional 1% to 2% from higher Tcm*



