

General Machine Timing for the Experiments



Summary of received requests for Safe Machine Parameters (SMP Flags) & Post-Mortem Event

Bruno PUCCIO (AB/CO)

Marc VANDEN EYNDEN (AB/CO)


Javier SERRANO (AB/CO)



Preamble



(most of) Safe Machine Parameters (SMP) are distributed over to the LHC General Machine Timing (GMT) network



- Amongst the different info broadcasted by the GMT, 2 types are only mentioned here:
 - Events not part of the SMP, referred as "Machine Events": like "Post-Mortem" event
 - Events attached to Safe Machine Parameters, like the "SMP Flags":
 - Safe Beam Flags (Beam1 and Beam2)
 - > Stable Beam Flag
 - "Movable device allowed in" Flag




Installation for SMP Flags



It has been agreed that AB/CO will supply the technical solution for supplying Hw signals corresponding to SMP flags (and to Machine Events)...

- GMT crate supplied by AB/CO and installed in each Experiment point
- Connected to LHC General Machine Timing (GMT) network






- And additional Line driver modules
 if distance between CTRx front-panel and corresponding Experiments system > 5 meters)
- AB/CO in charge of managing the CTRx settings.



Limit of responsibility stops at the level of the front-panel.





Installation information request




in order to know type of the crate, quantity of CTRx cards and amount of line drivers:

Installation Form sent to each BISU

needed	100000000000000000000000000000000000000	onnection e length	
(Yes/No)	<= 5m	> 5m	Comments:
- 7			
			needed with cable length (Yes/No) <= 5m > 5m

Summary done few weeks later...



x 6



For more information about the installation: Marc Vanden Eynden/Ocem.ch. Tel. 75578 For more information about the GMT system. Javier Serrano/Ocem.ch. Tel. 73486

Despite some systems are not populated,
VME crates chosen for having generic solution





Received requests for Point 1



Event name	Hw signal needed (Yes/No)	Nbr of co		No. Des	
		<= 5m	> 5m	Comments:	
Safe Beam Flag (beam-1)	Yes	1	1		
Safe Beam Flag (beam-2)	Yes	1	1		
Stable Beam Flag	Yes	1	1		
Movable_device_allowed_in Flag	Yes	1	1		
Post-Mortem	Yes	1	4		
Other Machine Events:	-				
Į.					

From: S. WENIG BISU of: ATLAS Date: 20. 12. 2007



Event name	Hw signal needed				
	(Yes/No)	<= 5m	> 5m	Comments:	
Safe Beam Flag (beam-1)	Yes		1		
Safe Beam Flag (beam-2)	Yes		1		
Stable Beam Flag	Yes		1		
Movable_device_allowed_in Flag	No		0		
Post-Mortem	Yes		1		
Other Machine Events:					
Safe Injection Beam Flag	Yes	>		IF available	

			_
From: A.L. Perrot	BISU of: LHCf	Date: 14/01/08	


VME crate installed in US151 (rack 4Y.02.03.A1)

	ATLAS	LHCf
Nbr of Timing card (CTRV)	2	2
Nbr of Line Driver (CTDAD)	5	3

13 (5+8) connections for ATLAS

ጲ

5 (0+5) connections for LHCf





Received request for Point 2



Event name	A Description of the Control of the	Nbr of connection with cable length		
	(Yes/Nb)	<= 5m	> 5m	Comments:
Safe Beam Flag (beam-1)	YES	YES		77.11
Safe Beam Flag (beam-2)	YES	YES		
Stable Beam Flag	NO			
Movable_device_allowed_in Flag	NO			
Post-Mortem	YES	YES		
Other Machine Events:	1			


From: David Evans BISU of: ALICE Date: 14/12/07

VME crate installed in SX2/CR4 (rack X07)



	ALICE
Nbr of Timing card (CTRV)	1
Nbr of Line Driver (CTDAD)	0

3 (short) connections





Received requests for Point 5



Event name	Hw signal Nbr of conn				
	(Yes/No)	<= 5m	> 5m	Comments:	
Safe Beam Flag (beam-1)	Yes	1		AND (beam1, beam2)	
Safe Beam Flag (beam-2)		1*		Combined with above	
Stable Beam Flag	Yes	1		AND (beam1, beam2)	
Movable_device_allowed_in Flag	Yes	1		OR (beam1, beam2)	
Post-Mortem	Yes	1			
Other Machine Events:					
fresent Flag	Yes	1		OR (beam1, beam2)	
Unstable Flag	Yes	1			
"InjectionThresholdHigh Flag	Yes	1		New flag indicating that the injection threshold is set high (~10 ¹¹) for inject-dustudies, as discussed in MPWG and LPC.	
Nobeam Flag	Yes	1			
Nomode Flag	Yes	1			

From: Jeff Spalding BISU of: CMS Date: Jan 23, 2008
Jeffrey.Spalding@cern.ch



<= 5m 0	> 5m 2	Comments: "Totem Motorization" + "Totem Trigger"
-	2	"Totem Motorization" + "Totem Trigger"
0		twister and with the state of t
0	2	* * *
0	2	* * *
0	2	* + *
0	3	" + " + Totem Electronics
		17
		TA No.
	ō	0 2

(*) Combined Safe Beam Flag not existing

VME crate installed in USC55 (rack S1E8)

	CMS	Totem
Nbr of Timing card (CTRV)	2	2
Nbr of Line Driver (CTDAD)	0	5


5* connections for CMS &

11 connections for TOTEM

From: Mario Deile & Walter Snoeys

BISU of: TOTEM

Date: 1st Feb. 08






Received request for Point 8




Event name	Hw signal needed	Nbr of c with cabl	200400000000000000000000000000000000000	
	(Yes/No)	<= 5m	→ 5m	Comments:
Safe Beam Flag (beam-1)	У	1	0	ACCES 100 -
Safe Beam Flag (beam-2)	У	1	0	
Stable Beam Flag	У	1	1	
Movable_device_allowed_in Flag	У	1	1	
Post-Mortem	У	1	2	
Other Machine Events:	72			

From: R.Jacobson BISU of: LHCb Date: 13 Dec.07

VME crate installed in UX85 (rack D3B09)



9 (5+4) connections





About a "Safe Injection" Flag...



Other Machine Events: Safe Injection Beam Flag	Yes	IF available	InjectionThresholdHigh Flag"	Yes	1	New flag indicating that the injection threshold is set high (~10 ¹¹) for inject-dump studies, as discussed in MPW6 and LPC.
			Nobeam Flag Nomode Flag	Yes Yes	1 1	States, as a season in his to and a co.
From: A.L. Perrot	BISU of: LHCf	Date: 14/0	1/0 From: Jeff Spalding Jeffrey.Spalding@cern.ch	BISU o	f: CMS	Date: Jan 23, 2008

- New name now: SPS Probe Beam Flag
- Required for safe beam transfer between SPS and LHC
- Produced and managed by the SMP system
- Flags only used by the Extraction Beam Interlock system => direct link
- Discussed and agreed in MPWG as essential part for a safe SPS Extraction
 - => corresponding EDMS document in preparation
- (for the time being) Not distributed by LHC-GMT



Planning



> 4th Feb.08:

LEADE Meeting

> 1 week later:

Green light from EXP for implementing the proposed solution



- ➤ AB/CO prepares the necessary Hw material, manages the Ethernet connections, and handles the settings configuration for each CTRV.
- In parallel, EXP manage the installation of the cables



Proposed Milestone:

Having the 4 systems ready by end of April 2008 for performing preliminary tests (=> simulation with fake Flags)



End:



That's all!