






Status of n _TOF Experiment

Enrico Chiaveri

Spokesperson of n _TOF Collaboration






- ✓ Status of Experimental Area EAR-2 Project
- ✓ Status of n_TOF Beam Line
- ✓ Removal of 1st n_TOF Target
- ✓ List of Proposals EAR-1 and EAR-2




Experimental Area(EAR 2) Project


- ▶ Civil Engineering ✓
- ▶ Ventilation ✓
- ▶ Electrical Infrastructure ✓
- ▶ Permanent Magnet ✓
- ▶ Simulations work ✓
- ▶ Beam Line to EAR2 ✓






COMPLETED!











- Permanent magnet blocks $\text{Sm}_2\text{Co}_{17}$, as a flux generator.
- Permanent magnet blocks $\text{Sm}_2\text{Co}_{17}$, compensate radial stray field to improve field quality in Good Field Region.
- Return yoke C10R steel.
- Pole tip C10R steel, smooth the possible differences on the easy axis orientation of the permanent magnet blocks.

Magnet weight ≈ 2000 kg

Picturea













- ▶ Various shielding solutions along the beam line
 1. Concrete blocks above target
 2. Concrete ring above magnet
 3. Steel spheres above magnet with special retain system:





Filter Box:
- design on-going

Magnet:
- assembly on-going at CERN

1st collimator (storage position):
- collimator ordered
- shielding design to be approved (RP)





Configuration for all measurements:

Collimator & Shape	Inner Diameter [mm]
2 nd : conical (2 m Fe + 1 m PE+B)	$d_2 = 20$ $d_1 = 69$
1 st : cylindrical (1 m Fe)	$d_0 = 200$

Both collimators in production resp. ordered




1st collimator is installed below EAR2 filter, inside the vacuum tube for beam shaping and shielding









- ▶ Work on-going for integration of:
 1. Various detector systems
 2. Sample changer
 3. Independent alignment system
 4. Additional shielding








Collimator No. 1



Fixed tube Ø400


Filter box




New bellows DNI60

New bellow DNI60


Collimator I shifted downstream 206 mm



- ▶ Planned location for new vacuum window
- ▶ Sample holder for transmission measurements




New vacuum window and space for sample holder



Vacuum window






- ▶ Al window in front of collimator No. 2 (thickness 0.3 mm, \varnothing DN 100, compliant to resist a shock wave)
- ▶ Second window at the entry of EAR I still needed (Kapton, e.g. \varnothing 65 mm/0.1 mm)
- ▶ Keep DN 400 valve
- ▶ Prepare for a sample holder
 - Depending on dimensions, we need to shift the valve and bellow upstream
 Similar design as the filter box actuators



Window with vacuum bypass

Space gain of 300 mm to integrate sample holder

Inspection of present (2nd) target 12th December 2013





- Campaign to inspect the present operating target to address status and external corrosion
- Endoscope used to externally inspect the target
- No major issues observed:
 - No signs of water at the bottom of the pit
 - Oxidation stains on the external body (expected)
 - 2nd inspection will take place in February to check the status of the neutron window

**Removal of 1st n_TOF target
4th December 2013**



Concrete container from PSI to permanently house the spent target



Preparation of the 375-T8 tunnel in order to contain surfacic contamination in view of target removal and movement



n_TOF EAR1 Proposal Document #	Field of interest	Protons	Year
Re-commissioning of n_TOF EAR1 CERN-INTC-2014-008 / INTC-P-407	Commissioning	3.9E+18	2014
Neutron capture at the s-process branching points 171Tm and 204Tl CERN-INTC-2014-003 / INTC-P-404	Astrophysics	7.5E+18	2014
Radiative capture on 242Pu for MOX fuel reactors CERN-INTC-2013-027 / INTC-P-387	Nuclear Tech.	3.5E+18	2014
Winter SHUTDOWN			
Neutron capture cross sections of 70;72;73;74;76Ge at n TOF EAR-1 CERN-INTC-2013-021 / INTC-P-381	Astrophysics	1.2E+19	2015
Measurements of neutron induced capture and fission reactions on 233U CERN-INTC-2013-041 / INTC-P-397	Nuclear Tech.	4.3E+18	2015
<i>35Cl(n,p)35S for NCT To be proposed (LOI Feb. 2014)</i>	<i>Medical App.</i>	<i>2.0E+18</i>	<i>2015</i>
Total # of protons (all proposals)		3.3E+19	



n_TOF EAR2 Proposal Document #	Field of interest	Protons	Year
Commissioning of n_TOF EAR2 CERN-INTC-2013-043 / INTC-P-399	Commissioning	9.8E+18	2014
γ -ray Energy Spectra and Multiplicities from the Fission of ^{235}U using STEFF CERN-INTC-2014-004 / INTC-P-405	Nuclear Tech.	3.0E+18	2014
Winter SHUTDOWN			
Measurement of the neutron capture cross-sections of ^{53}Mn at EAR-2 CERN-INTC-2014-012 / INTC-P-408	Astrophysics	3.5E+18	2015
Destruction of the cosmic γ -ray emitter ^{26}Al by neutron induced reactions CERN-INTC-2014-006 / INTC-P-406	Astrophysics	5.0E+18	2015
<i>Neutron capture at the s-process branching point ^{147}Pm To be proposed</i>	<i>Astrophysics</i>	<i>2.5E+18</i>	<i>2015</i>
<i>$^{14}\text{N}(n,p)^{14}\text{C}$ for NCT To be proposed (LOI Feb. 2014)</i>	<i>Medical App.</i>	<i>2.0E+18</i>	<i>2015</i>
<i>Feasibility of the (n,γ) on ^{235}U and ^{239}Pu with a fission tagging C_6D_6 setup To be proposed</i>	<i>Nuclear Tech.</i>	<i>2.0E+18</i>	<i>2015</i>
<i>The (n,α) reaction cross section measurement for light isotopes To be proposed</i>	<i>Basic Physics</i>	<i>2.0E+18</i>	<i>2015</i>
<i>Helium production in tungsten relevant to divertors in future fusion reactors To be proposed</i>	<i>Nuclear Tech.</i>	<i>2.0E+18</i>	<i>2015</i>
Total # of protons (all proposals)		3.2E+19	



- ▶ **The n_TOF 2nd experimental area EAR2 Project is according to the planning. Ready for commissioning July 2014**

- ▶ **Refurbishing n_TOF Beam Line ready for July 2014**

- ▶ **n_TOF Proposals :**
 - ▶ CERN-INTC-2014-003 / INTC-P-404 Neutron capture at the s-process branching points 171Tm and 204Tl
 - ▶ CERN-INTC-2014-004 / INTC-P-405 γ -ray Energy Spectra and Multiplicities from the Neutron-induced Fission of 235U using STEFF
 - ▶ CERN-INTC-2014-008 / INTC-P-407 Re-commissioning of n_TOF EAR1
 - ▶ CERN-INTC-2014-012 / INTC-P-408 Measurement of the neutron capture cross-sections of 53Mn at EAR-2
 - ▶ CERN-INTC-2014-006 / INTC-P-406 Destruction of the cosmic γ -ray emitter 26Al by neutron induced reactions