# LHeC

## LHeC ERL Test Facility & SC RF:

#### Fundamental Goals and Motivation:

- → Build up expertise in the design and operation for a facility with a fundamentally new operation mode:
  - → ERLs are circular machines with tolerances and timing requirements similar to linear accelerators (no 'automatic' longitudinal phase stability etc.)
- → Proof validity of fundamental design choices:
  - → Multi-turn recirculation (other existing ERLs have only two passages)
  - $\rightarrow$  Implications of high current operation (3 \* [6mA 12mA] > 30mA!!)
- → Verify and test machine and operation tolerances before designing a large scale facility
  - → Tolerances in terms of field quality of the arc magnets
  - → Required RF phase stability (RF power) and LLRF requirements



## LHeC: Baseline Linac-Ring Option

Super Conducting Linac with Energy Recovery

& high current (> 6mA) tune-up dump comp. RF 10-GeV linac Two 1 km long SC injector 0.12 km lineag in CW operation 0.17 km 10<sup>34</sup> cm<sup>-2</sup> s<sup>-1</sup> Luminosity reach **PROTONS ELECTRONS PROTONS ELECTRONS** Beam Energy [GeV] 7000 60 7000 60

Luminosity [10 <sup>33</sup> cm <sup>-2</sup> s <sup>-1</sup> ]	16	16	1	1
Normalized emittance $\gamma \epsilon_{x,y} [\mu m]$	2.5	20	3.75	50
Beta Funtion $\beta^*_{x,y}$ [m]	0.05	0.10	0.1	0.12
rms Beam size $\sigma^*_{x,y}[\mu m]$	4	4	7	7
rms Beam divergence $\sigma\Box^*_{x,y}[\mu rad]$	80	40	70	58
Beam Current [mA]	1112	25	430 (860)	6.6 (3.3)
Bunch Spacing [ns]	25	25	25 (50)	25 (50)
Bunch Population	2.2*10 <sup>11</sup>	4*10 <sup>9</sup>	1.7*10 <sup>11</sup>	(1*10 <sup>9</sup> ) 2*10 <sup>9</sup>
Bunch charge [nC]	35	0.64	27	(0.16) 0.32

## LHeC ERL RF Choices:



#### LHeC SC RF choice:

- → Daresbury meeting on RF options January 2013:
  - → no existing SC RF technology (ILC & ESS) fits perfectly to the LHeC
  - → no synergy with existing RF power sources at CERN

#### → 800 MHz:

- → minimization of RF power a la Marhauser
- → lower frequency advantageous for beam stability (Wakefields)
- → Synergy with existing RF power sources @ CERN
- → See presentation by Erk Jensen for more details





#### Validation of key LHeC Design Choices:

- → Three re-circulations with high beam current:
  - → Coherent Beam stability due to ions, and wake-fields when triggering transverse perturbations (a la beam-beam)
  - → Pulse stability and reproducibility of beam parameters (intensity, position and size)
  - → Energy spread and beam parameter stability at end of deceleration process
  - → Study of transient ERL dynamics during current ramp-up
- → SC RF Design validation via operation with beam
  - → SC RF behavior with beam
  - → Coupler validation
  - → HOM tolerances and required HOM damping
  - → Beam loading and implied RF controls





- → Injector and gun
  - → Choice of electron sources (Superconducting RF, DC High Voltage etc.)
  - → Injection energy and beam transfer, emittance requirements and preservation, etc.
- → Required beam diagnostics:
  - → Pulse by pulse diagnostics
  - → Single pass beam size measurements etc.
- → Injection line and beam dump tests
  - → Momentum acceptance requirements
  - → Beam extraction at different beam energies and machine protection aspects



### Potential applications beyond an LHeC ERL Test Facility:

- → Magnet and cable quench facility:
  - → Vital for development of new cables and future high field SC magnets (e.g. FCC hh)
- → Test facility for SC RF with beam
  - → Very interesting for development of new SC RF components
  - → e.g. Crab Cavities, SC RF for FCC ee, etc.
- → Test beam for detector component developments
  - → Beam lines with beam energies higher than 100 MeV/c [Peter Kostka]
- → Dedicated Physics Facility
  - → similar to MESA program but at higher energy



- ERL Test Facility layout and parameters:
  - → Possibility for phased installation:
    - → Energy range for each option
  - → Overall floor foot print
    - → Requirements for ERL TF
    - → Requirements for auxiliary applications
  - → Parameter overview

# Planning for each stage


#### Courtesy of Alessandra Valloni

#### Phase 1:

#### SC RF cavities, modules and e<sup>-</sup> source tests

- Injection at 5 MeV
- 1 turn
- 75 MeV/linac
- Final energy 150 MeV

ARC	ENERGY
ARC 1	80 MeV
ARC 2	155 MeV



\*4 SRF 5-cell cavities at 802 MHz

# Planning for each stage


Courtesy of Alessandra Valloni

#### Phase 2:

#### **Test the machine in Energy Recovery Mode**

- Injection at 5 MeV
- 3 turns
- 75 MeV/linac
- Final energy 450 MeV

ARC	ENERGY
ARC 1	80 MeV
ARC 2	155 MeV
ARC 3	230 MeV
ARC 4	<b>305 MeV</b>
ARC 5	380 MeV
ARC 6	455 MeV



Recirculation realized with vertically stacked recirculation passes

## Planning for each stage


#### Courtesy of Alessandra Valloni

#### Phase 3:

#### Additional SC RF modules test Full energy test in Energy Recovery Mode


- Injection at 5 MeV
- 3 turns
- 150 MeV/linac
- Final energy 900 MeV

ARC	<b>ENERGY</b>
ARC 1	150 MeV
ARC 2	<b>300 MeV</b>
ARC 3	450 MeV
ARC 4	600 MeV
ARC 5	750 MeV
ARC 6	900 MeV




## Layout:

#### Courtesy of Alessandra Valloni




## ARC I, III, IV Layout:



#### Courtesy of Alessandra Valloni


- Synchronous acceleration Isochronous arcs
- Achromatic arc
- > FMC optics




Total Arc length for Arc 1,2,3 34.5112 m 94 x λrf


For 6 arcs: 84 DIPOLES 114 QUADRUPOLES

## Linac | Multi-pass optics: Courtesy of Alessandra Valloni



## Linac II Multi-Pass Optics: Courtesy of Alessandra Valloni






FMC = Flexible Momentum Compaction

15

# ptics Option I: ARC III:

#### Courtesy of Alessandra Valloni



9.8° bends

(1 rec. + 3 sec.)

Ldip = 90.58 cm

B = 6.58 kGauss


 $\rho = 230.66 \text{ cm}$ 

9.8° bends


(1 rec. + 3 sec.)

## Optics Option I: ARC V:

#### Courtesy of Alessandra Valloni



# Summary Option | Optics: Courtesy of Alessandra Valloni





FMC = Flexible Momentum Compaction

## ARC Optics Option II:

#### Courtesy of Alessandra Valloni

#### SAME OPTICS LAYOUT FOR ALL THE ARCS 900/750/600/450/300/150 MeV





#### 3 DIPOLES ON TOP OF **EACH OTHER**

\*Attilio Milanese

#### Arc dipoles:

8×22.50 bends

Ldip = 100.6 cm

 $\rho = 256.3 \text{ cm}$ 

#### Arc quadrupoles

Lquads = 30 cm

	1GeV	750MeV	600MeV	450MeV	300MeV	150MeV
B FIELD	1.30 T	0.97 T	0.78 T	0.58 T	0.39 T	0.19 T
	Q1	Q	2	Q3	Q4	
Kq[m <sup>-2</sup> ]	-1.0	1 2.	91	2.09	1.19	

## **Synchrotron Radiation:**

Courtesy of Alessandra Valloni

ARC	E [MeV]	ρ [cm]	∆E [keV]	σ <b>Ε/Ε</b> [%]
1	150	91.459	0.0280	1.17e-5
2	300	91.459	0.4191	6.42e-5
3	450	230.66	0.8230	8.13e-5
4	600	230.66	2.5726	1.53e-4
5	750	230.66	6.2394	2.73e-4
6	900	230.66	12.881	4.47e-4
7	750	230.66	6.2394	5.89e-6
8	600	230.66	2.5726	7.49e-6
9	450	230.66	0.8230	9.98e-6
10	300	91.459	0.4191	1.49e-6
11	150	91.459	0.0280	2.93e-3

← maximum


Beam Energy loss

$$\Delta E = \int P_{\gamma} dt = P_{\gamma} \frac{\pi \rho}{\beta c} \quad \Delta E(GeV) = C_{\gamma} \frac{E^4}{\rho} \frac{1}{2}$$

► Beam Energy Spread  $\frac{\sigma_E}{E} = \sqrt{1.4397 * 10^{-27} \frac{\pi \gamma^5}{\rho^2}}$ 


# Next Steps Towards CDR: Courtesy of Alessandra Valloni

Complete Step 2 and Step 1 configuration and optics layout



## Floor Footprint:

#### Courtesy of Alessandra Valloni



#### **ARCS**

Total length for Arc 1,2,3 34.5112 m 94 x λrf (last cavity linac1 to first cavity linac 2)

Total length for Arc 4,5
34.2704 m
101 x λrf
(last cavity linac1 to first cavity linac 2)

Total length for Arc 6
34.4574 m
101.5 x λrf
(last cavity linac 1 to first cavity linac 2

#### LINAC



#### ONE CRYOMODULE: 8 RF CAVITIES

PARAMETER	VALUE
Frequency	801.58 MHz
Wavelength	37.4 cm
Lcavity= 5λ/2	93.5 cm
Grad	20.02 MeV/m
ΔΕ	18.71 MV per cavity

Total length ~ 13 m

#### CHICANE INJ/EXTR

Length ~ 1.75 m

TOTAL DIMENSIONS
42 m x 13.7 m




Auxiliary Applications: SC Magnet Quench Facility

# Controlled quench tests of SC magnets

Study beam induced quenches (quench thresholds, quenchino thresholds) at different time scales for:

- SC cables and cable stacks in an adjustable external magnetic field
- Short sample magnets
- Full length LHC type SC magnets



Courtesy of Daniel Wollmann And Arijan Verweij

Quench limits of LHC dipole as expected from QP3 simulations for different pulse durations

# Beam parameters to generate a given amount of energy deposition calculations and fluka simulations

Copper target
(no magnetic field)

Cylinder of copper


Radius = 50cm
Length = 100cm

#### Beam parameters

Energy, MeV	Emittance, m	Sigma, cm	FWHM, cm
150	1.70E-07	0.092	0.22
300	8.52E-08	0.065	0.15
450	5.68E-08	0.053	0.13
600	4.26E-08	0.046	0.11
750	3.41E-08	0.041	0.10
900	2.84E-08	0.038	0.09
1000	2.55E-08	0.036	0.08

Results are given for half of bulky target because of symmetry

Binning: 1 mm<sup>3</sup> bins



# Beam parameters to generate a given amount of energy deposition calculations and fluka simulations

Copper target
(no magnetic field)

Cylinder of copper

Radius = 50cm
Length = 100cm


#### Beam parameters

Energy, MeV	Emittance, m	Sigma, cm	FWHM, cm
150	1.70E-07	0.092	0.22
300	8.52E-08	0.065	0.15
450	5.68E-08	0.053	0.13
600	4.26E-08	0.046	0.11
750	3.41E-08	0.041	0.10
900	2.84E-08	0.038	0.09
1000	2.55E-08	0.036	0.08

Results are given for half of bulky target because of symmetry

Binning: 1 mm<sup>3</sup> bins

#### Energy deposition, GeV/cm<sup>3</sup>/e<sup>-</sup>



Beam parameters to generate a given


amount of energy deposition


# electrons
needed to
quench the
magnet

Quench threshold

Maximum value for the energy deposition

#### MB quench limit @ 3.5 TeV





#### $1 \text{ GeV} = 1.602 \times 10^{-7} \text{ mJ}$

MB quench limit 450 GeV is 140mJ/cm³ in 10ms:

~2.2 x 10<sup>9</sup> e<sup>-</sup> @ 1GeV necessary

MB quench limit 7 TeV is 16 mJ/cm<sup>3</sup> in 10ms:

~2.6 x 108 e<sup>-</sup> @ 1GeV necessary

## Summary ERL Test Facility


LHeO

- Test facility for SCRF cavities and modules
- Test facility for multi-pass multiple cavity ERL
- > Test facility for controlled SC magnet quench tests
- > Injector studies: DC gun or SRF gun
- Study reliability issues, operational issues!
- Vacuum studies related to FCC
- Could it be foreseen as the injector to LHeC ERL and to FCC?

TARGET PARAMETER*	VALUE
Injection Energy [MeV]	5
Final Beam Energy [MeV]	900
Normalized emittance γε <sub>x,y</sub> [μm]	50
Beam Current [mA]	10
Bunch Spacing [ns]	25 (50)
Passes	3

→ ERL TF CDR by end 2015

\*in few stages





#### Site options:

- → Many site options presented @ January 2014 LHeC Workshop
- → In Point 2 @ ALICE apparently not really a viable option (tbc)
- **→** SM18:
  - → Existing cryogenic installation
  - → Existing powering infrastructure
  - → Next step should be site specific studies for the ERL TF and auxiliary applications in preparation for the ERL TF CDR



- B. 889 SPS Access point
- B. 897 Central Storage
- B. 867 Radioactive facility

- B. 888 COMPASS
- B. 887 North Hall
- B. 890 EN-CV for North Hall

Nuria Catalan



## ERL-TF possible sites: ALICE





We have started to look into possible existing buildings suited to host the ERL test facility.


# A suitable hall could be in **Building 2275, near LHC P2**

- Current use under investigation
- Power converters already in place
- Geographically perfect as injector for LHeC ERL
- Slightly narrower than required Can it be extended?

N. Catalan Lasheras



# ERL-TF possible sites: SM18?







# Reserve Transparencies:

## ERL Test Facility worldwide (1/2)





Beam Energy	35 MeV
Beam Current	10 mA
Bunch charge	77 pC
RF frequency	1300 MHz
Passes	1
Beam Energy	50 MeV





100 mA
77 pC
1300 MHz
1


Beam Energy	12-26 MeV
Bunch charge	40-60-200 pC
RF frequency	1300 MHz
Passes	1

## ERL Test Facility worldwide (2/2)









Beam Energy	35-125-250 MeV
Beam Current	10mA (100mA)

Bunch charge	7.7pC- 77pC
bunch charge	7.7pc-77pc

RF frequency	1300 MHz
--------------	----------

Passes	1- 2
--------	------

		<b>→4(36)</b>	-(P()0:		-[
	D.	20 M			118
SC RF Gun	DI DI	ookh SC 5 Cell cavity	aven	1	1 2 2 2 2 2
* 2 80	20 MeV	F. 0	ф <del>он</del>	-880-	11
CATHERE 1	3 MeV 2-3 MeV		6 6	20 MeV	

Beam Energy	20 MeV
Bunch charge	0.5-5 nC
Bunch current	300 mA
RF frequency	704 MHz
Passes	1