

# Low Breakdown rate operation of a high gradient accelerating structure under high beam loading conditions



J.L. Navarro (CERN), for the CLIC/CTF3 collaboration



06 - 10 OCTOBER '14  
INN VINCA  
BELGRADE  
SERBIA


EUROPE  
EARTH

ПЦБС14  
LGWS14



B E L G I E

- From CLIC to the breakdown problem
- The Dogleg experiment layout
- First Results
- Next steps
- Conclusions

✓ The study is focused on the accelerating structures of the Main Beam Linac



CR combiner ring  
 TA turnaround  
 DR damping ring  
 PDR predamping ring  
 BC bunch compressor  
 BDS beam delivery system  
 IP interaction point  
 █ dump



- **Traveling waves** cavities
- Nominal gradient  $\sim 100$  MV/m
- Nominal RF pulse length  $\sim 240$  ns (160 ns flat top)
- Peak Power  $\sim 61$  MW
- Max. Surf. Field  $\sim 230$  MV/m


Strong Accelerating fields ( $\sim 100$  MV/m)



Problem of **Break Downs (BD)**: Very fast (10 ns – 100 ns) and localized dissipation of stored energy in the structure.



- Undesired effects:
- Loss of acceleration
  - Damage in the structure
  - Kick in the beam
  - ...

Luminosity Reduction:  
**Max DB rate allow for CLIC specifications:**  
 $3 \cdot 10^{-7} \text{ BD pulse}^{-1} \text{ m}^{-1}$



Beam Loading modifies the gradient distribution along the structure



Average gradient 100 MV/m



Gradient profile along the structure without beam loading

Beam Loading modifies the gradient distribution along the structure



Average gradient 100 MV/m



The beam loading modifies the gradient profile

Beam Loading modifies the gradient distribution along the structure



Average gradient 100 MV/m



The beam loading modifies the gradient profile

Beam Loading modifies the gradient distribution along the structure

Average gradient 100 MV/m





The beam loading modifies the gradient profile



Beam Loading modifies the gradient distribution along the structure



Average gradient 100 MV/m



We do not have anymore 100 MV/m in average.

Beam Loading modifies the gradient distribution along the structure



Average gradient 100 MV/m



We compensate increasing the RF input power

Beam Loading modifies the gradient distribution along the structure


Average gradient 100 MV/m




What is the effect on BD rate?

**Main goal:** Measure and comparison (unloaded vs high beam loading) of the BD rate in high gradient accelerating structure

Experiment located at the **CLIC Test Facility CTF3 @ CERN**









1x




Nx



3000000x




1x



1x




Dogleg



CTF3 Injector


12 GHz RF:  
 ✓ 90 MW RF power



35 m low loss waveguide

Beam:

- ✓ CTF3 Drive Beam modified to mimic CLIC main beam
- ✓ 3GHz beam with nominal current of  $\sim 1.2$  A
- ✓ Pulse length up to 250 ns
- ✓ Energy  $\sim 125$  MeV at structure
- ✓ Up to 25 Hz pulse rep. rate




Gun

MKS03

MKS05

MKS06

MKS07



**Normal conducting** cooper structure

**Travelling wave**

Tapered linearly ( $\emptyset$  from 6.3 to 4.7 mm)

Without HOM Damping waveguides



**24** cells + 2 coupling cells


Nominal accelerating gradient 100 MV/m

$v_g/c$  [%] = 1.8 to 0.9

Filling time = 57.25 ns

$Q_{Cu}$  = 6815





12 GHz accelerating structure surrounded by a complete set of instrumentation:

- 2 inductive BPMs (1 upstream and 1 downstream)
- 6 mm collimator to protect the structure
- Fibre optic and diamond beam loss monitors
- Vacuum pumps and gauges in beam chamber and RF waveguides





## ScandiNova Modulator:


- Designed for 400kV, 300A, 3.25us HV pulse width FWHM, 1.5us RF pulse width at 50Hz repetition rate

Enough power to reach  
100 MV/m loaded  
gradient  
(~43 MW)





## XL5 klystron:

- 50MW, 1.5us rf pulses
- 50Hz repetition rate at 400kV, 300A, 600W rf drive power
- Working frequency 11.99424GHz





## SLED II type pulse compressor:

- Power gain of 2.82
- $Q_{\text{loaded}} = 2.375 \times 10^4$ ,
- Beta = 4.27,
- $Q_0 = 1.31 \times 10^5$
- 5% power loss






## PXI NI unit:

- Real time interlocking
- Data taking and storage
- 12 GHz RF control
- Labview interface with user



Beam



Pulse repetition rate from 25 Hz to 50 Hz (a lot of data, needs pre-selection)


ACQ system stores:



- 1 event per minute
- Breakdown-like events (soft criteria  $\sim$  50% events are fake breakdowns)

Offline analysis selects breakdowns and nominal pulses, computes BDR



Final cuts for BD selection are not completely applied in the following results



## Conditioning period to reach 200 ns pulse length.







A lot of effort was done matching RF and beam phases





Phase variation along the pulse is around 10 degrees





# First Results



# Pulses: 21.25M

REF bre: 102

BDR Tot: 4.8E-6


Start: 16:00 23/09/

- RF
- KP
- Av
- BDR
- D
- D
- CL
- Be
- M
- Pe
- Lo
- IP
- IP
- C
- G
- C
- R
- P
- IN
- P
- P



Data from 23/09/2014 to 02/10/2014

**Very preliminary results!!!!!!**




**Period 1:**  
BD rate:  $3.4 \cdot 10^{-5} \pm 0.4$

**Period 2:**  
BD rate:  $2.0 \cdot 10^{-5} \pm 0.2$


**Period 3:**  
BD rate:  $1.2 \cdot 10^{-5} \pm 0.1$

**Systematic errors not included!!!**

**Preliminary Conclusion:** Beam loading does not show an increased breakdown rate at constant input power



**Main goal:** Measure breakdown rate for nominal CLIC parameters.



**Other measurements:**

- Cell distribution
- Loading levels (RF phase)
- Current dependencies
- Different structures
- ...

- ✓ **Breakdown rate** measurements in **heavy loaded** high gradient structures was a **missing block** in the high gradient program
- ✓ **CTF3/CLIC** collaboration has **successfully set up an experiment** to measure the effect of beam loading at nominal CLIC gradients
- ✓ The experiment **has started collecting data** from end of September
- ✓ After one week of data preliminary analysis shows that the **beam presence does not have a harmful effect on the breakdown rate at constant input power**
- ✓ The experiment will **continue collecting data** to probe different power and loading levels
- ✓ **More detailed analysis will be done** to draw further conclusions

We are ready for new exciting results !!!

## RF/PM

M. Filippova  
 A. Grudiev  
 D. Gudkov  
 P. Guyard  
 A. Olyunin  
 A. Samochkine  
 I. Syratchev  
 A. Solodko  
 P. De Souza

## CTF3

R. Corsini  
 S. Doebert  
 D. Gamba  
 J.L. Navarro  
 T. Persson  
 P. Skowronski  
 F. Tecker


## XBOX

S. Curt  
 A. Degiovanni  
 J. Giner  
 G. McMonagle  
 S. Rey  
 J. Tagg  
 L. Timeo  
 B. Woolley

## BI

M. Kastriotou  
 E. Nebot

J.L. Navarro for the  
CLIC/CTF3 Collaboration



# Backup: CLIC Nominal parameters


---

Average loaded accelerating gradient	100 MV/m
Frequency	12 GHz
RF phase advance per cell	$2\pi/3$ rad
Average iris radius to wavelength ratio	0.11
Input, output iris radii	3.15, 2.35 mm
Input, output iris thickness	1.67, 1.00 mm
Input, output group velocity	1.65, 0.83% of $c$
First and last cell $Q$ -factor (Cu)	5536, 5738
First and last cell shunt impedance	81, 103 M $\Omega$ /m
Number of regular cells	26
Structure length including couplers	230 mm (active)
Bunch spacing	0.5 ns
Bunch population	$3.72 \times 10^9$
Number of bunches in the train	312
Filling time, rise time	67 ns, 21 ns
Total pulse length	244 ns
Peak input power	61.3 MW
RF-to-beam efficiency	28,5 %
Maximum surface electric field	230 MV/m
Maximum pulsed surface heating temperature rise	45 K



---

**Objective:** Transport the beam through the Linac up to the structure requiring...


- Full transmission efficiency
- Minimum beam size on average inside the structure




Maximize relative distances between aperture and beam size (M. Dayyani). MAD model by F. Tecker.







Accelerating gradients achieved in tests.  
Status: 4-9-2012



Structure under test:  
CERN's T24 (12WNSvg1.8 KEK N1)  
No damping




Figure 10: Bead-pulling at 11991.68 GHz












Figure 5: Combined transmission from input to output






# Dog-leg waveguide line installation status.



- ✓ All the components are installed.
- ✓ Connected to accelerated structure and closed for vacuum.
- ✓ Vacuum leaks checked (tight).

Ready to be connected to XBOX1



## RF power transmission measurements




- The measured RF power transmission efficiency is 80%.
- Reflection is below -27dB.
- The group delay time is 75 ns ( $\sim 23.5$  m).

# Overall power transmission efficiency





One way losses in the WG line. From just after PC to the -3dB hybrid in CTF#2



- The overall measured RF power transmission efficiency is 67%.
- The round group delay time is 230 ns ( $\sim 35$  m).
- To provide nominal CLIC RF pulse, XBOX1 klystrons needs to deliver 36 MW x 1.5  $\mu$ s.







# Phase I Results: Running of Dec 2013

And from the RF side:

