


Commissioning and Operation of the Horizontal Test Apparatus at SNS

Presented at:
CEC/ICMC 2015 – C1OrG

Brian DeGraff
Oak Ridge National Laboratory
Spallation Neutron Source

June 29th, 2015



Overview

- **Background**
- **Design & Fabrication**
- **Commissioning & Operation**
- **Current R&D using HTA**
- **Summary**


Background

Motivation for HTA at SNS

- **SNS in operation since 2006**
 - Highest average proton beam linac in the world, 1.4 MW demonstrated
 - SCL: 81 SRF cavities in 23 cryomodules
 - Cryoplant: 2.4 kW at 2.1 K
 - Excellent availability of SCL systems ~98% (including supporting sub-systems)
 - Linac output energy 940 MeV
- **Limiting factor for SRF cavity performance**
 - Electron activity (field emission, multipacting) resulting in end group quench
 - End groups made of reactor grade niobium with lower thermal conductivity
- **Testing cavity performance in horizontal configuration**
 - Aim to reach 1 GeV to provide margin for reliable 1.4 MW operation
 - Horizontal Test Apparatus for R&D in cryomodule-like environment
 - Better understand limiting factors of SNS cavities
 - R&D for performance improvement


What is HTA?

- **Multi purpose test vessel**
 - Demountable cavity for rapid testing
 - Similar RF and cryogenic parameters as cryomodule
 - Cryogenic connection to operating CTF test system
 - Flexible instrumentation capability
 - Three cryogenic helium circuits:
 - Primary liquid helium supply
 - Coupler cooling at 5K
 - Shield cooling



HTA cooling block diagram

- HTA operates in conjunction with the CTF system:



Design & Fabrication


HTA main design features

- Vacuum vessel with two main doors & access ports
- Copper thermal shields cooled to 50 - 20 K with helium
- Access ports to open/close cold manual valves
- Demountable support rails
- P and T instrumentation
- U-tube connections to CTF transfer line
- Fixed dewar for testing without cavity (redundant LL & heater)
- Primary and shield circuit pressure reliefs (1.68 atm & 9 atm)
- SNS coupler & RF connections



HTA specific cooling features

- **Movable primary helium supply bayonet**
 - Single supply and return pipe to HTA Dewar
 - Movable bayonet on primary stinger to control flow path
 - Demonstrated that cavity cooling is possible without adjustment
- **Flanged helium connections within vessel**
 - Minimizes turn around time
- **Copper cooling blocks on cavity end flanges**
 - Improves cooling for cavity end groups (~5 K additional cooling)
 - Shortens recovery time after quench




Examples of HTA instrumentation

- **Instrumentation box outside of HTA**

- Connected to the beam tube extension through the HTA door
- Phosphorous screen and faraday cup to monitor e-activity
- Camera with direct view of cavity volume

- **Additional diodes**

- Monitoring of end-group temperatures
- Help better understand their thermal behavior




Commissioning & Operation

First HTA cool down in June of 2014


- **Initial cryogenic commissioning successful**

- Cool down using the CTF cryogenic plant
- Cooling all three helium circuits in parallel (primary, coupler & shield)
- 28 hours to build liquid helium in the HTA Dewar and cavity helium vessel
- 60 hours to reach thermal stability in end-groups without copper cooling blocks on cavity end flanges



Second HTA cool down

- **Copper cooling blocks installed on cavity end flanges for the second cool down**
 - Provides additional cooling to end-groups
 - Shortens cool down time
 - Improves thermal stability of end groups
 - Thermal stability reached in 33 hours



HTA cryogenic loads

- **Static heat load**

- 9.6 W static heat load to the cavity liquid helium bath calculated by measuring the liquid level drop with the primary JT valve closed
- Static heat load to the shield circuit not determined as no flow meter is available

- **Dynamic heat load**

- Cavity heat dissipation below CTF cooling capacity

- **Liquefaction load to secondary He circuit**

- Circuit cooling the FPC & end-groups cooling blocks
- Cooling flow measured with the outlet valve fully open
 - 0.75 g/s in the range of 6 K to 10 K

Current R&D using HTA


Example of HTA use for R&D

- HTA used is the 2nd step in the plasma R&D



1st phase

R&D with 3-cell and 6-cell cavities




2nd phase

Processing of 6-cell cavity in HTA



4th phase

In-situ processing in linac tunnel




3rd phase

Processing of cryomodule in test cave

In-situ plasma processing using HTA


- Test of plasma processing on single dressed cavities prior to test on cryomodule
- Plasma processing hardware adjacent to HTA vessel
 - Processing occurs with cavity at room temperature
 - Gas manifold to supply process gas (~100 mTorr)
 - RF plasma station to ignite, tune and monitor plasma
 - Processing by-products monitored using RGA
- Two cavities successfully plasma processed in-situ and tested in the HTA



Highlight of plasma processing result using HTA

- In-situ plasma processing improves cavity performance
- Before plasma processing
 - Measured field emission onset 12 MV/m
 - Peak gradient 15.2 MV/m
- After Plasma processing
 - Measured field emission onset 16 MV/m
 - Peak gradient 22 MV/m

[M. Doleans, SNS 2015]



Summary

- **The HTA was successfully commissioned in 2014**
- **It performed as desired over five cryogenic tests over the past two years**
- **Ideal platform for testing cavities and subsystems in a cryomodule like environment while providing great flexibility for instrumentation, for example**
 - Two Cavities were successfully plasma processed in-situ and tested using the HTA
- **Planned activities**
 - Cold-test of cavity with high RRR end-groups
 - Test of 700 kW fundamental power coupler with a cavity
 - 2 K HTA operation using Kinney system

Acknowledgements

THANKS!

I would like to thank many colleagues and support groups at SNS and Ability Engineering for their assistance in performing the HTA testing described in this paper, especially personnel from controls, electrical, RF and water groups.

This work was supported by SNS through UT-Battelle, LLC, under contract DE-AC05-00OR22725 for the U.S. DOE.

- **HTA P&ID:**

