ISTITUTO NAZIONALE DI FISICA NUCLEARE SEZIONE DI MILANO LABORATORIO ACCELERATORI E SUPERCONDUTTIVITA' APPLICATA



Magnet Test Station @ LASA, INFN-Milano


WP10.4 Magnet Test meeting

Giovanni Volpini, CERN 26 November 2014



Test Station & Equipment Review


Experimental area






experimental area @ LASA

INFN




Giovanni Volpini, GSI 29 March 2011





MAGIX Test cryostat





Giovanni Volpini WP10.4 Test Meeting, CERN 26 November 2014



Current source




Three 10 kA x 6 V power supplies available at LASA . They can be operated in series or in parallel.

Current measured through a 10 kA DCCT.


External bus bars designed for 10 kA

A system to operate the power supply in discharge mode is based on a diode bank which sinks the power, in parallel with Mosfet's which short-circuit the diode bank during the current ramp-up. This allows for ~ -15 V during the discharge cycle.

WP10.4 Test Meeting Giovanni Volpini, CERN 26 Nov 2014




Current control



an example : test run 1.5 T to 3 T @ 0.5 T/s





Current leads

EuCARD²

Bare heat exchanger of the 10 kA-class CL designed at LASA and manufactured by RIAL Vacuum.

INFN

The use of CuP allows for optimized heat load performance at I=0



Giovanni Volpini WP10.4 Test Meeting, CERN 26 November 2014



1. QDS (MSS Magnet Safety System)

<u>Initiates a fast discharge</u> or <u>switches off the power supply</u> incase some voltage thresholds on the magnet or on its electrical connection are exceeded. Includes a capacitor bank for firing quench heaters.

2. Current Control & Slow Acquisition

Two different functions, implemented in the same hardware & software system. Slow acquisition monitors and records most important data (temperatures, current, voltage along critical items) from the cooldown to the operation. Data are available to the operator and recorded at about 1 Hz.

3. Fast Acquisition

EUCARD²

Records voltages across the magnet under test with 1 kHz sampling frequence, in coincidence with a fast discharge

4. V*I AC losses measurement system

A dedicated system which measures the AC losses by numerical integration of V*I product, measured by a couple of synchronized VMM.

It is completely independent from other systems, from the voltage taps on. This allows to perform checks, modification on the ground, etc. without affecting other safety-critical systems.

> WP10.4 Test Meeting Giovanni Volpini, CERN 26 Nov 2014



1. Magnet Safety System




16 channels (may be expanded), each: optoinsulated input, bridge/single end independently configurable Voltage thresholds ±4V, ±1.25V, ±500mV, ±100mV Time validation ranges: 0-10 ms, 0-100 ms, 0-1 s Input signal made available in copy Memory of fired channels

> Giovanni Volpini WP10.4 Test Meeting, CERN 26 November 2014


EUCARD²


2. Slow Acquisition

INFN



WP10.4 Test Meeting Giovanni Volpini, CERN 26 Nov 2014





Net work Q performed by the power supply on the magnet between t_0 and t_1 .

$$Q(t_1, t_0) = \int_{t_0}^{t_1} V \cdot I \, dt \approx \Delta t \sum_{j=1}^n V_j \cdot I_j$$

WP10.4 Test Meeting Giovanni Volpini, CERN 26 Nov 2014

cooldown

Large magnet cool down may be be performed:



- with temperature controlled GN, keeping a ΔT of less than 40 K between any of the eight temperature probes located within the cold mass; the ΔT is increased to 50 K, when the hot spot temperatures drops below 200 K;
- with LN, when the cold mass hot spot drops below 127 K;
- with LHe, after thermalizing the cold mass in LN.

Time Table, DISCORAP dipole, 6 tons

- 15/6 cool down start flow rate 400 nL/min GN $\Delta T = 40K$
- 25/6 Tmax = 238 K
- 2/7 Tmax = 126 K
 - , LN is fed directly into the cold mass

 $\Delta T = 50 K$

- 4/7 cold mass at 77 K
- 6/7 LN removal starts
- 7/7 LN removal completed, LHe cooling starts
- 9/7 cold mass at 4 K
- *10/7 cryostat filled, the test starts.*

cooldown

Three pipes carry the cryogen inside the cryostat and the magnet:

- The lower pipe brings the fluid directly inside the magnet. The circumferential gap is sealed with Al tape, so that the fluid is forced to flow within the magnet
- The upper pipe (not seen in the picture) ends near the top of the magnet. Its purpose is mainly to allow a quiter LHe refill during the test.
 - A third pipe is used as syphon for LN removal; the residual LN is then evaporated by means of heaters





Schedule




	HTS magnet test schedule			2015										2016															
		month	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1		
Official milestones/ deliverables	"Internal" milestones (TBD)	stardate							26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44		
MS65		Test station kickoff																											
		Specification drafting, order																											
	M65.1	Component procurement																											
		Test station integration																											
		Test station commissioning																						_					
	M65.2	Magnet delivery																											
D 10.4		Magnet cold test																											
D10.4		Magnet cold test completion						_																				<u> </u>	
MAGIX		Sextupole construction Sextupole test																											
		Octupole and decapole construction																											
		Octupole and decapole test																											
		Quadrupole and dodecapole constructio	n																										
		Quadrupole and dodecapole test																											
		Explanation																											
		Activity																											
		Milestone																											
		Dellesseble																					-						 _
		Deliverable	$\mathbf{\vee}$																										

Giovanni Volpini Giovanni Volpini WP10.4 Test Meeting, CERN 26 November 2014 KEK 20 November 2014



Assembly & Cryostat Insertion

Cold mass on the assembly station







cold mass raising





into the cryostat








Electrical connection between bus-bar & magnet





The END


EUCARD² MAGIX Cryostat **INFN** F-F(1:2) E(1:2) A-A(1:4) ٩ H-H(1:2) (10) * 4 X 66.51 Flangia del eticale d D G-G(1:2) raggi di fondo cava: R 0.1 raggi di testa cava: Rmax n 0 Ō õ




₽



















Δ







Temperature probes on the CM

