



X-Band test stand and accelerating structure testing status

T. Argyropoulos, J. Giner-Navarro, R. Rajamäki, B. Woolley

CLIC Project Meeting #23

CERN 01/12/2015

Acknowledgments: A. Degiovanni, N. Catalan Lasheras, W. Farabolini,

G. Mcmonagle, L. Navarro, I. Syratchev, F. Tecker, W. Wuensch



Outline



- **The Xboxes**
- **Xbox-1\Dogleg experiment**
 - ☐ TD26CC_N1
 - Full history
 - Breakdown analysis
 - Run with the CLIC pulse shape
 - Beam loading experiment
- **Xbox-2**
 - ☐ T24_open
 - Full history
 - Breakdown analysis
 - Radiation issues
- **Conditioning stage of the RF structures under test**
- **Xbox-3**
 - ☐ Status and plans
- **Conclusions**

Xbox-1



OPERATIONAL

**CPI 50MW 1.5us klystron
Scandinova Modulator
Rep Rate 50Hz**

Current test:

**Dogleg beam-loading
experiment, TD26CC#1 (in CTF3
LINAC)**

Previous tests:

TD24R05 (CTF2, 2013)
TD26CC#1 (CTF2, 2013)
T24 (Dogleg, 2014-15)

Xbox-2



OPERATIONAL

**CPI 50MW 1.5us klystron
Scandinova Modulator
Rep Rate 50Hz**

Current test:

T24_OPEN (in halves)

Previous test:

CLIC Crab cavity (2014-15)

Xbox-3



Xbox-3A: OPERATIONAL

Xbox-3B/C/D: COMMISSIONING


**4x Toshiba 6MW 5us klystron
4x Scandinova Modulators
Rep Rate 400Hz**


**LLRF, pulse compressors and
waveguide network to be
completed at the beginning
of 2016**

Medium power test:

3D printed Ti waveguide
X-band RF valve
(Xbox-3A)

Dogleg Experiment






- ❑ TD26CC_N1, tested at Xbox-1 in 2013, was accidentally vented during an unknown period of time.
- ❑ The structure was re-baked out at 650 °C and installed in the CTF3 Linac for the **Dogleg experiment**
- ❑ Need of reconditioning



Xbox-1/Dogleg: TD26CC_N1 - full history





- Gradient
- Norm Grad
- BDs
- BDR
- Pulse width
- Cluster BDs

Conditioning status:
 43.3 MW
 100MV/m
 180ns
 ~1e-5bpp


Gradient at CLIC pulse specs:
 ~85MV/m

# Pulses	Equiv hours @50Hz	Run hours
279.8M	1555	2594.41
# Fake BDs	# BDs	Cluster BDs
38452	10175	5471
Up-time	Mean BDR	Mean Cluster BDR
59.9 %	3.64E-5	1.96E-5

- ❑ Strong effort in breakdown localization techniques and diagnostics
- ❑ The two methods used show similar results
 - ❑ **Edge:** Falling edge of **TRA** and rising edge of **REF**
 - ❑ **Correlation:** Correlation in tails of **INC** and **REF**




- ❑ Phase of the signals is also used to locate the BD
- ❑ 3 phase groups are clearly visible separated by around 120° → corrections applied to the BD location



Good performance (no evidence of hot cells)

- CLIC Pulse shape since mid of October to prepare for the beam arrival






Run with CLIC pulse shape




☐ Problems with many modulator interlocks → solved





Run with CLIC pulse shape


Smooth Run after at 43.3 MW averaged incident power (100 MV/m)



- ❑ Beam set-up by Frank at 26/27 November 2015
- ❑ Change the phase and delay of the klystron to match the beam (initially beam was decelerated)




- ❑ Time only to set-up the interlocks: threshold of the Transmitted energy increased (still lot of margin compared to unloaded BDs)
- ❑ Run on this weekend is scheduled



X-band structure in halves designed by CERN and built by SLAC (A. Grudiev, H. Zha, V. Dolgashev)

Limited by Radiation in the Bunker




- Norm Grad
- BDs
- BDR
- Pulse width

Conditioning status:
 34 MW
 87 MV/m
 155 ns
 4e-6 bpp

Gradient at CLIC pulse specs:
 ~74 MV/m

# Pulses	Equip hours @50Hz	Run hours
235.1M	1306	2007.31
# Interlocks	# BDs	Cluster BDs
5889	5828	3577
Uptime (%)	Mean BDR	Mean Cluster BDR
65	2.48E-5	1.52E-5


Changed pulse length to 155ns



Bunker\RF structure


Radiation detectors

Klystron\Modulator\PC




- ❑ Unpredictable behaviour of the radiation with BDs → limits power level
- ❑ Survey by the Radioprotection group to identify possible sources of radiation → Faraday Cup, Collimator
- ❑ **Short term solution:** shielding them locally with lead
- ❑ **Long term solution:** enhance the roof of the bunker (20 cm more concrete)



Example of Radiation in Xbox-2 bunker



Radiation




- Same BD analysis applied using the amplitude and the phase of the recorded signals



Good performance (no evidence of hot cells)




RF structures conditioning



Gradient scaled at 200 ns and 1e-6 bpp

BDR scaled at 200 ns and 100 MV/m


Good conditioning of the accelerated structures




Similar like previous structures

TD26 almost recovered to the old condition stage

Summary of tested structures





6.5-7MW Klystron

Directional Coupler

Vacuum Port

3D Printed Waveguide

Solid state 320W amplifier

RF Stainless Steel Load




3D Printed waveguide results



~150 Million Pulses
acquired in just 2 weeks
with only 50% uptime.

200 Hz rep. rate makes
data taking faster!





Xbox-3 Status and plans



Klystron/Modulators

- All 4 klystron/modulator units from Toshiba/Scandinova have been installed and tested in diode mode
- Klystron A has been tested with RF up to 7.25MW output power $\sim 2\mu\text{s}$ pulse width
- New water pump delivered to be installed in the next few weeks to increase cooling capacity such that Xbox 2 and 3 can run simultaneously
- 4, 400W solid state pre-amps ordered to arrive by end of January. (We have already tested one prototype at CERN, performance is good.)

Waveguides + High power RF components

- All high power waveguide components are due to arrive early January
- New RF valve design tested performance is much improved
- Pulse compressors will be later.. (Delay of 1-2 months due to leaking waveguide components)
- Support beams are in place for the waveguide system

LLRF and Controls

- PXI crates are purchased and at CERN. Control software is being developed (from X-box 2 code) to increase rep. rate to 400Hz and to switch between 2 channels @ 400 Hz
- LLRF mixing crates are under fabrication with 90% of components already at CERN
- All crates should be finished by end of January.

Commissioning to start in February



Conclusions



- ❑ Xbox 1 and 2 are running at full capabilities to perform the required high-power tests for the CLIC prototypes
- ❑ Xbox 3 all components will be here by the end of January → commissioning to start in February
- ❑ Dogleg experiment with Xbox-1 and CTF3 beam will study the beam loading effect on the breakdown rate
- ❑ Data analysis is ongoing for a better understanding of the BD phenomena in real cavities
- ❑ Two test stands running with different structures → possibility of testing different operating strategies




Thank you for you attention



Extra Slides

❑ Problems with breakdowns in the area around the Pulse Compressor



- ❑ Some issues with the TWT amplifier (50 Hz not optimum ?) → induce a BD or interlock. Quite frequent lately → important to be solved

