

ISOLDE Technical Report

Richard Catherall

ISOLDE Technical Coordinator

50th INTC meeting 1st July 2015




Outline

- Target developments
- REX Linac
- RILIS
- Ion Source and Beam Manipulation Development Team
- Automatic Beam Tuning
- Fast Tape Station



Target Developments: Recent results


• 8B beams



- Target material: Carbon nanotubes (MWNCT), ρ=0,43 g/cm3
- Standard Ta container, cold transfer line, VADIS ion source
- SF₆ in container, $(0.37*10^{-4} \text{ mbar*I/s}, p(SF_6)\sim 1-2 \text{ bar})$

Release of ⁸B & ISOLTRAP's MR-ToF:

- No ⁸BF_n⁺ (n=1,2,3) or Oxyflourines detected
- Positron activity on A=8 corresponds to 3*10² I/uC
- Proof that activity originates from ⁸B still pending



Target unit #513: (Same characterisics as #499,

higher SF₆ injection)

Release of ⁸B & LAI (Tengblad et al.):

- ⁸BF₃⁺ (n=1,2,3) detected this time!
- Positron activity on A=46 corresponds to 3x10⁴-10⁵/uC (~InA stable contaminant also detected)

Ch. Seiffert, J. Balof, et al.


Target Developments: Recent results





• Negative beams :

• Negative ion source prototype (GdB₆ tube ion. Menna et al. NIMB. 266(2008)

4391)







Offline efficiencies 2015: ϵ (Br⁻,l⁻) = 17% @1700C with some questions remaining

Online TISD with Nb #535 and ThO #540 targets, starting this week

Y. Martinez, J. Ballof, T. Mendonca

Status of the refurbishment of the REX linac:





Power converters and magnets ready for beam:

- New power converters for quads (19 units) fully functional
- New cooling water circuits for all the quads operational
- Electrical short in last triplet repaired and triplet refurbished
- Additional tests and measurements in other quadrupoles completed (thermal switches characterized, temperature rise measured...)

RF systems:

- Maintenance and refurbishment of amplifiers for RFQ, IH structure, buncher and 7 gap structures completed
- ✓ RFQ recalibrated and stable at 10 Hz, 1 ms / 40 kW pulses
- ✓ Buncher stable at 10 Hz, 1 ms / 1.4 kW pulses
- Temporary 9gap amplifier stable at 1Hz, 300 us, 45 kW
- RF power in 7 gap structures for a short period of time
- Connections to HIE-ISOLDE RF reference completed
- Power in the IH structure / long RF tests for the other cavities delayed to week 27
- Ramp up in duty cycle delayed to week 28






Courtesy of J. A. Rodriguez Rodriguez


Final 9gap amplifier schedule to arrive in week 31. Commissioning completed by week 35



Vacuum systems:



✓ Beam down to first diagnostics box (between RFQ and buncher)




Treshold 150 200 250 Position MCP image of the beam after the RFQ

Courtesy of J. A. Rodriguez Rodriguez

New RILIS Remote Control Room





NB:Tisa

doi:10.1016/j.nimb.2013.08.058

Improved scanning software & DAQ

https://cds.cern.ch/record/2014923

Hg (April '15, IS598)

Au (May '15, IS534)


'On-call' for most RILIS runs.



M.Sc. Thesis of R.E. Rossel
RILIS Equipment Acquisition Control Tool (REACT) is being developed by *Ralf Rossel*.



New ionization scheme for Te



New possibility of clean tellurium beams at ISOLDE

For:

HIE-ISOLDE

¹¹⁶⁺¹¹⁸ **Te**


Coulomb excitation

http://cds.cern.ch/record/1319097/files/INTC-P-296.pdf

+ others

PhD work: T. Day Goodacre






- First on-line RILIS ion beams from liquid targets (Cd from Sn and Hg from Pb)
- Up to 2x efficiency improvement observed for Hg and Cd (compared to VADIS only)
- Higher purity Ba beams compared to Surface + RILIS source

New Ion Source (and beam manipulation) Development Team









Automatic Beam Tuning

- Nelder-Mead simplex algorithm applied directly to the hardware
- An automatic robust optimisation program for tuning the beam through complex systems.


Faster and less tedious for the operator








Fast Tape Station



- A final design is now in place and production drawings in progress
- Procurement of parts already started
- Construction and detector development this autumn
- On-line commissioning (at LA2?) as from 2016
- Final installation 2016/2017 shutdown
- A spare tape station to be built
- Excellent support throughout EN





Thank you for your attention