


Controls and Software

What did we learn with beam in 2008


Chamonix 2009 - Eugenia Hatziangeli

Acknowledgements


- ▶ J. Lewis, I. Kozsar, JC. Bau, C. Roderick, R. Billen, G. Kruk, W. Sliwinski, J. Wozniak, M. Gourber-Pace, N. Hoibian, M. Misiowiec, P. Charrue, J. Lauener, N. Stapley, K. Sigerud, V. Tsaplin, M. Buttner, M. Sobczak, M. Arruat, F. Locci, A. Radeva, S. Deghaye, C.H. Sicard, V. Baggiolini, R. Gorbonosov, D. Khasbulatov, M. Zerlauth, N. Trofimov, ...
 - ▶ Collaborators (FNAL, GSI, Dubna): almost all projects - excellent work
-




LHC Controls Infrastructure




- The 3-tier architecture
 - Hardware Infrastructure
 - Software layers
- Resource Tier
 - VME crates, PC GW & PLC dealing with high performance acquisitions and real-time processing
 - Database where all the setting and configuration of all LHC device exist
- Server Tier
 - Application servers
 - Data Servers
 - File Servers
 - Central Timing
- Client Tier
 - Interactive Consoles
 - Fixed Displays
 - GUI applications
- Communication to the equipment goes through Controls Middleware CMW






- ▶ **Preparation for beam**
- ▶ Start up 2008 challenges and outlook
- ▶ What we learnt
- ▶ Summary




Preparation for Beam

- ▶ All Controls infrastructure deployed and required functionality tested
 - ▶ Individual high level control tests => dry runs
 - ▶ From CCC using controls infrastructure and software
 - ▶ Check the functionality of the individual systems
 - ▶ Full integration tests performed with all systems driven through operational cycles => Full system tests
- ▶ Dry runs and TI8/TI2 beam tests -2003 onwards
 - ▶ Initial versions LHC Core controls (LSA) tested repeatedly
 - ▶ Several CO services put in operations (Fixed Displays, Logging, Software Interlock system)
 - ▶ LEIR & SPS operational software 2005-06
 - ▶ LSA operational deployment
 - ▶ Injection Dry run Dec 2007
 - ▶ Validation of the LHC Timing system - OK
 - ▶ Full CO scalability tests May-June 2008
 - ▶ Aim to identify areas of concern
 - ▶ LSA, Logging, Data Concentrators, Middleware, Timing, SIS, LASER, DIAMON, RBAC
 - ▶ Full dry runs TI8, TI2 31st July, 1st Aug
 - ▶ Final check out and tests 7-8 Aug
 - ▶ Five preparatory Injection test Aug - Sep 2008



- ▶ Preparation for beam
- ▶ **Start up 2008 challenges and outlook**
- ▶ What we learnt
- ▶ Summary





LHC Software Architecture - LSA


- ▶ LSA is the core control system for LHC, used to
 - ▶ Manage equipment configuration & states
 - ▶ Manage machine settings
 - ▶ Drive the accelerators through their cycle
- ▶ Overall LSA worked very well and provided all required functionality for LHC
 - ▶ It was well established (first used in 2003)
 - ▶ Core functionality was tested and improved before LHC first beam



- LEIR (partial controls, since 2005)
- SPS and all its transfer lines (full controls, since 2006)

- ▶ Major reworking (refactoring) - April '08
 - ▶ Introduced new LHC-related concepts (Beam Process)
 - ▶ Extensions for FGC & new implementations for RF & Collimators
 - ▶ Transactional behaviour (commit/rollback) for FGC & Collimators
 - ▶ Bottom-up propagation of Trims to keep the parameter space consistent
 - ▶ Mechanism for trim critical setting (BLM thresholds)
 - ▶ Data Concentrators (BLM, BPM)






LSA Outlook for 2009

- ▶ Complete online check of any hardware settings

- ▶ MCS devices
- ▶ Integration with SIS and Sequencer



- ▶ Continue preparation of the Test environment


- ▶ Test devices and configuration for driving settings for key equipment (FGC, Collimators, RF, BLM)
- ▶ Integration with the CO test bed (FESA, CMW, Timing)


- ▶ Improvements in the core logic and generic applications

- ▶ Performance tuning
- ▶ Better error reporting
- ▶ Diagnostic information to DIAMON

- ▶ Apply the Finite State Machine concept to operational processes


- ▶ Implementations for accelerator mode & beam mode






Sequencer

- ▶ The Sequencer automates the execution of task sequences (injection, ramp...)
- ▶ The Sequencer helps the operators not to forget anything - sequences can be complicated and with several steps
 - ▶ HWC already relies heavily on the Sequencer
 - Powering Groups of Circuits
 - Ramp & squeeze
- ▶ The Sequencer for beam operations was developed by a Controls and OP collaboration
 - ▶ First used operationally in SPS - end 2007
- ▶ The Sequencer for beam operations was used for all controls tests
 - ▶ Inject & Dump, Inject and circulate
 - ▶ Commissioning of LBDS
 - ▶ All necessary sequences for beam were ready
- ▶ The Sequencer was proven to be an excellent and vital LHC commissioning tool




Outlook for 2009

- ▶ Conjugate flexibility with safety
 - ▶ Provide different operating modes: MD (flexible), OP (rigorous)
 - ▶ Ensure some tasks are carried out
- ▶ Improve the User Interface
- ▶ Simplify the sequences and tasks
- ▶ Manage sequences better
- ▶ Integrate sequencer with other applications



Several Reusable Components in LHC


- ▶ Excellent experience in LHC with Controls components deployed **previously in other machines**
 - ▶ Sequencer (SPS, HWC)
 - ▶ Fixed Displays (LEIR, SPS, HWC, CPS)
 - ▶ Software Interlocks System (developed for the SPS used operationally since 2007)
 - ▶ Alarm system - LASER (LEIR, SPS, HWC, CPS)
 - ▶ Analogue Observation - OASIS (LEIR, SPS, CPS)
 - ▶




Timing and Synchronisation

The LHC timing is 'loosely' coupled to the injector chain only during injection


- ▶ The data exchange with the injectors during injection is complex
- ▶ Testing with beam was essential
 - ▶ Timing dry run - Dec 2007
 - ▶ Two controls tests - Aug 2008
 - limited impact
 - in the shadow of HWC & Injectors
 - ▶ Injection tests Aug - Sep 2008
 - Issues
 - RF synchronization
 - Extraction timing LTIMS
 - Timing tables update






1st Injection Test - RF Synchronisation

- ▶ RF Injection parameters must be established in the RF system **450ms before** the first CPS batch is extracted towards the SPS
- ▶ They must also remain stable for at least 1 sec after extraction towards the SPS has taken place
- ▶ The actual implementation sent the RF parameters **far too late (25ms)** so the **beam was not correctly transferred** from the SPS to the correct Ring and Bucket
- ▶ The cause was **quickly identified and resolved on the spot!!!**
 - ▶ The test of the LHC filling use case was not sufficient - lack of RF synch went unnoticed as we did not have beam







2nd Injection Test - Extraction Timing & Timing Tables


- ▶ Local timing LTIM in the FE got corrupted & disabled
 - ▶ The SPS extraction forewarning timing was not sent

- ▶ Errors in the table update protocol between the LHC gateway and the master and slave LHC timing crates
 - ▶ Injection timing table was not loaded




A quick solution was provided for both issues on the day

- ▶ The problems correctly fixed the following day



Timing Outlook 2009

- ▶ No fundamental changes in the LHC timing
 - ▶ All important issues have been resolved
- ▶ Consolidation of all LHC timing components - aim for reliability
- ▶ LHC timing test bed available to be deployed
 - ▶ Intensive testing of the complete system





Databases & Logging - Hitting the Limits


Hardware limit

- ▶ I/O (end 2007)
 - MeasDB and LogDB on same ageing hardware
 - ↳ Purchase new hardware & separate into 3 high-availability DB services - Mar 2008
 - ↳ Install additional LDB storage Mar-Dec 2008
- ▶ CPU (Sep-2008)
 - Simultaneous data writing and extraction MDB→LDB of the same (most recent) data delayed occasionally data transfer
 - Improved filtering code
 - Rationalized MDB backup time

Software limit


- Logging client cannot cater for increasing client requirements, namely LHC BLM
 - ~4000 monitors, 100 000 variables/second
 - ↳ BLM data volume reduced by 30% (6/9 r.sums)
 - ↳ Data rate reduced by a factor 2 (every 2sec)
- Client API bottleneck at serialization of data input
 - ↳ Massive // in the data entry API
 - ↳ Possibility to log on fixed frequency + on change
 - ↳ Dump data on disk if DB down






Evolution of the Logging - Data Volume

LHC Logging Service - Logged records





Databases & Logging Outlook 2009

- ▶ Address **performance** issues to fulfil nominal logging requirements

Client requirements in terms of data rates (BLM, ...)

- ▶ **Increased processing power** MDB => better and/or more performing nodes in the cluster - Feb 2009
- ▶ **Increase //** => Spread the concentrators & loggers on several dedicated servers
- ▶ **Increased hardware performance** => New powerful DB HW

- ▶ Provide **maximum availability**


New infrastructure has high-redundancy for high-availability

- ▶ **Most interventions are fully transparent**
- ▶ **Persist data in local files** if MDB not available (1 day max) with automatic data transfer to MDB

- ▶ Scale in function of **data volumes**

LHC Data rates estimated ~10 - 25TB/year

- ▶ Disks were installed just-in-time (Mar-Dec 2008)
- ▶ Extra disks will be required before end of 2009
- ▶ **Do we really need to log all this data?**



Middleware CMW & JMS

CMW

- ▶ Blocked/loss of **subscriptions** or blocked **get/set** operations, unable to handle **high load** affected FESA servers (BI, BT, Collimators, Timing,..) and PO
 - ▶ Several bugs were discovered and solved at the RDA level and few in the FESA framework
 - ▶ In total **6 formal releases** were made in the space of 5 weeks which fixed >10 serious bugs
 - ▶ **CMW GW** were put in place to protect simultaneous accesses to (BI) FE

Outlook for 2009

- ▶ FESA/CMW servers are in a much better shape now than ever
- ▶ Few known RDA issues remain to be solved

JMS - victim of its own success

The **usage** of JMS was growing beyond expectations (>100 connected physical clients, 25/CCC rest from offices, GPN,..)


- ▶ Insufficient throughput
 - ▶ Data delivered: 10-15 MB per second
 - ▶ Around 4 million messages a day
- ▶ Broker **unstable** or connections **frozen**

Mainly reactive approach in 2008

- ▶ Tune configuration, upgrade hardware & JMS software,...)
- ▶ Protection of resources for CCC
 - ▶ Primary broker for CCC, secondary broker for GPN

Outlook for 2009


- ▶ Increased manpower for support
- ▶ Provide better **monitoring** of the JMS Brokers & internal system parameters
- ▶ Create a consolidated set of test to test future JMS broker updates and configurations
- ▶ Investigate and install **clustered broker sets** for increased reliability (failover)



Role Based Access Control - RBAC


- ▶ RBAC works by giving people **ROLES** and assigning **PERMISSIONS** to ROLES to access device properties (**Authenticate & Authorise**)
- ▶ Integrated into the BE controls middleware and a collaboration project with LAFS

- ▶ Deployed in **2008** for the LHC dry-runs and start up
 - ▶ Objective: RBAC all LHC Applications
- ▶ **75 %** of all applications were RBACed
- ▶ **Most of the equipment** were RBACed (PO, BI, BT)
 - ▶ RF & Collimators were getting started
- ▶ RBAC was quickly embraced by equipment groups
 - ▶ High expectation to get protection from unauthorized access to their equipment




Outlook for 2009

- ▶ Ensure all operational GUIs and equipment are RBACed
- ▶ Make sure the **RULES** and **ROLES** are correct and contained (LHC Control Security Panel)
- ▶ Default access mode will be **strict** in 2009
 - ▶ Each application will need an RBAC token



- ▶ Preparation for beam
- ▶ Start up 2008 challenges and outlook
- ▶ **What we learnt**
- ▶ **Summary**



So ... what did we learn?

▶ Testing is essential to success


- ▶ The majority of Controls infrastructure was thoroughly tested over many years 2003 ->
 - Dry runs, cold check out, full machine checkouts
- ▶ The core controls (LSA, SIS, ...) and services (Sequencer, Logging, ...) were used operationally in other machines
 - Constant exercising of the software - most bugs/inadequacies were surfaced
 - Functionality was well tuned
 - Refactoring made software robust and simpler each time

▶ Nevertheless we had few issues with systems used **1st time with beam** or in this scale


- ▶ Controls is the first infrastructure needed to be available, difficult to *steal* time from user to test our own
- ▶ For certain system only the beam revealed the problem (Timing)
- ▶ Not enough integration testing facilities - room for improvement
 - Service libraries (CMW, Timing, FESA, ...) that affect several systems (BI, XTIM, BT,..)
- ▶ Testing without correct initial conditions will not reveal all the problems
 - Scalability tests gave us some indications of the weak components
 - When full LHC load hit the controls system we saw clearly the bottlenecks

▶ To avoid the same mistakes again

- ▶ Invest in proper test facilities - Controls test bed
- ▶ Ask for **dedicated Controls testing time** in the Accelerator schedule
 - already planned for Injectors



- ▶ **Overall the Controls infrastructure has worked well**
 - ▶ Thanks to early deployments, reusability across machines, cold checkouts, dry runs, full machine checkouts which were extremely useful to identify and correct bugs/features before startup with beam
- ▶ A lot of work has been **invested in functionality and safety** (RBAC, MCS, SIS)
 - ▶ All necessary functionality for beam was there
 - ▶ Several core systems have been protected against damage by ignorance
- ▶ Still many new requirements/functionality to be implemented in 2009
- ▶ **Strong investment in reliability of the Infrastructure**
 - ▶ A monitoring infrastructure **DIAMON** (in unison with LASER) is put in place to aid operations and CO experts to diagnose/repair controls problems
 - ▶ Individual test set ups in labs (timing, LSA)
 - ▶ Controls (integration) **Test Bench** in preparation
- ▶ Not to forget the **Injector Renovation**
 - ▶ The work to renovate the LHC Injectors with the present Controls Infrastructure is advancing and the first validation of the architecture is positive



Thank You
