




## CTF3 Collaboration Meeting 27. – 28.1. 2009



**TBL Quadrupoles**

Antony Newborough CERN TE/MSC/MNC





# Outline

- **What are the TBL Quadrupoles?**
- **Design and Specification**
- **Production**
  - **16 Series magnets (BINP)**
  - **Proto-type magnet (CERN)**
- **Schedule**



# What are the TBL Quadrupoles?



*Quad*  
*BPM*  
*PETS*

**Quadrupole magnets for the 16 TBL (Test Beam Line) cells for the focusing of the beam during deceleration and power extraction.**

- Single TBL Cell




# Design and Specification

## Main parameters:



<b>BASIC</b>		
Number of magnets		16 + 4 spare coils
Aperture radius	mm	19
Nominal gradient (at 8 A)	T/m	7.14
<b>FIELD QUALITY</b>		
Good field region	mm	$r \leq 15$
Gradient homogeneity $\Delta Gdl  /  Gdl $ at $G_{nom}$		$\leq \pm 2 \times 10^{-4}$ at $x, y \leq 15$ mm
<b>EXCITATION</b>		
Nominal current	A	8
Nominal voltage	V	8.5
Dissipated power at $I_{rms}$	W	68
Magnet resistance (at 20°C)	$\Omega$	1
Magnet inductance	mH	140
<b>DIMENSIONS AND WEIGHT</b>		
Yoke length	mm	170
Yoke width	mm	236
Yoke height	mm	236
Yoke weight	kg	39
Overall length	mm	215

Project started – September 2007




**Magnetic Design:**  
Th. Zickler  
– Finalised June 08.

**Technical Specification:**  
A. Newborough - April 2008



**Engineering Drawings:**  
T. Sahner and D. Steyaert  
- April 2008


**BINP collaboration confirmed May 08, design finalised July 2008.**




# Production - 16 Series magnets (BINP)



October 2008 Measured and actual coordinates



Deviation from draft, locating targets



**mating surfaces & pole  
tolerances  $\pm 15 \mu\text{m}$**

**General tolerance  $\pm 30 \mu\text{m}$**




# Production - 16 Series magnets (BINP)



## October 2008

### 5.3 INSPECTION OF COIL № 17

No	PARAMETER	MEASURED	REFERENCE
1	Checking of the dimensions of the coil before impregnation	Ok	Ok
2	Checking of the dimensions of the coil after impregnation	Ok	Ok
3	Visual checking for quality of insulation of conductors in the coil	Ok	Ok
4	Electrical resistance of the coil at ambient temperature	270 mOhm	x mOhm for 16 °C for y °C
5	Electrical resistance for 20° C	274 mOhm	z mOhm
6	Leakage current between the coil terminations and bath at 1 kV	0	<100 μA
7	Electrical resistance between the coil terminations and bath at 1 kV (DC) after 8 hours	Ok	>100 MOhm
8	Turn-to-turn isolation (10V per turn)	Ok	Ok



- 68 - coils produced 16 magnets + spare

- 1<sup>st</sup> set completed end of October 08

- Series Completed November 08



# Production - 16 Series magnets (BINP)



October 2008



October 2008




December 2008

November 2008

The gap between surfaces of segment and base plate (2 measures). Nominal : 0.02 mm.			
6		1	0.02 mm
		2	0.02 mm
The gap between shims and base plate (4 measures). Nominal : 6.25 ± 0.02 mm.			
7		1	6.26 mm
		2	6.25 mm
		3	6.25 mm
		4	6.26 mm
Non-perpendicularity of surfaces of the segment (3 measures). Nominal: 0.2 mm			
8		1	0.2 mm
		2	0.2 mm
		3	0.1 mm




- 64 - quadrants
- 1<sup>st</sup> set completed end of November 08
- Series Completed December 08



# Production - 16 Series magnets (BINP)



December 2008



- Pre-series assembly Dec 08
- Power test Dec 08
- Basic magnetic measurement Jan 08, full measurement Feb 08 (1-2 weeks delay)
- Series completed end of Jan 08






# Production - Proto-type magnet (CERN)

## Coil with Indirect Cooling

CERN Proto-type





- 1 option for drive beam quads for CLIC
- Air cooling unrealistic
- Direct water cooling not reliable enough
- Charged resins being Investigated for improved heat transfer



# Production - Proto-type magnet (CERN)

## Yoke – Electrical Discharge Machining (EDM)



Isometric view  
Scale: 1:2



- 1<sup>st</sup> attempt March 08
- **Bonding problems with the steel**
- **Stopped until new steel delivery**



## Schedule

- **Assembly of 16 magnets finished – end of January**
- **Magnetic Measurement**
  - **Rotating coil – End of January**
  - **Hall probe array – Mid February**
- **Shipping**
  - **To leave BINP – mid February**
  - **Delivery to CERN – February - March**
- **Acceptance Tests – 1 Week**  
(Electrical Test, thermal measurements and installation of interlocks)
- **Magnetic Measurement – 1 to 2 weeks (one magnet)**
- **Installation – March/April**



CALIFES correctors



TL2 & CLEX correctors



TL2 vertical dipoles



TL2 & TL2'

# Other Work



TL2 & CALIFES



CALIFES, TBTS & TBL



TL2' & TBL



CALIFES & CTF2



CALIFES



July 08



December 08

VivoCAM TL2\_XLC\_0500\_QFL\_0570\_QDL\_0550