

TEST BEAMS FOR LHC, SLHC AND FUTURE LINEAR COLLIDER DETECTORS

Ingrid-Maria Gregor, DESY



Thanks to:

Laza Dragoslav (#54), Lucie Linssen (#56), Felix Sefkow (#34),


Henric Wilkens, Beniamino Di Girolamo, Kunihiro Nagano,
Antonello Di Mauro, Maxim Titov, Nigel Hessey, Rolf Lindner
Horst Breuker, Edda Gschwendtner, Christoph Rembser

**New Opportunities in the
Physics Landscape at CERN
May 11-13 2009**

LIFE IS A TEST BEAM ...

Role of Test Beams in a HEP Experiment

- Conception
- Conceptual design, choice of detectors/technologies
- Technical design, prototypes construction and testing
- Detector construction
- Calibrations
- Commissioning
- Data taking
- Analysis, systematics studies




... the same for all kind of particle detectors

LIFE IS A TEST BEAM ...

Role of Test Beams in a HEP Experiment



- Conception
- Conceptual design, choice of detectors/technologies
- Technical design, prototypes construction and testing
- Detector construction
- Calibrations
- Commissioning
- Data taking
- Analysis, systematics studies



... the same for all kind of particle detectors


2008 RECFA coordinated EU FP7 proposal (DEVDET) showed strong needs for test beams and test beam infrastructures

ATLAS COMBINED TEST BEAM 2004



- Drift chambers: beam position
- Scintillators: trigger
- Calorimeters on moving table
- H8 beam: Energy: 1 to 350 GeV

CMS COMBINED TEST BEAM (2006)



“IP”

CMS phi slice test

- HB: 2 wedges
 - 8 ϕ segments
 - $\Delta\phi = 40$ deg.
- HE:
 - 4 ϕ segments
 - $\Delta\phi = 20$ deg.
 - HO: Ring 0, 1, 2
- ECAL: SM9

+ Real Electronics


- excellent particle ID in H2 beam line

TEST BEAMS CURRENT LHC EXPERIMENTS

- After an impressive test beam program over the last 15 years
-> not ready
- Experience of previous HEP experiments: test beam after start of data taking helping to understand data
 - e.g. calorimeters
- And then the future ...

TEST BEAMS CURRENT LHC EXPERIMENTS

- After an impressive test beam program over the last 15 years -> not ready
- Experience of previous HEP experiments: test beam after start of data taking helping to understand data
 - e.g. calorimeters
- And then the future ...




Collimation phase 2

Linac4 + IR upgrade phase 1

EXPERIMENTAL CHALLENGES (S)LHC

- Detector is designed for $L_{\max} = 10^{34} / \text{cm}^2/\text{s}$
 - Phase 1 (3 times than design) is already a challenge, in particular given such a short time scale (~ 5 years)
 - Phase 2 is 10 times than design L_{\max} !
- Huge particle rates
 - High occupancy in tracking detectors
 - degradation of performance
 - Saturation effects in forward calorimeter
 - Trigger and DAQ should handle > 10 times higher rates
- Radiation damage
 - Inner Detectors will be partially (phase 1) or completely replaced (phase 2)
 - On-detector r/o electronics should be radiation tolerant up to $10^{16} \text{ n}_{1\text{MeV}} / \text{cm}^2$ (one order of magnitude more than current LHC experiments)


Example: ATLAS




Simulated by I. Dawson with FLUKA

SLHC DETECTOR R&D



- R&D on new detection techniques is already under way:
 - new pixel technologies (planar, 3D sensors, diamond ...)
 - new silicon strip technologies
 - silicon photomultipliers (SiPM)
 - thick GEMs
 - heavy fibers, new scintillating crystals
 - new diamond devices for luminosity monitoring,
 - use of quartz plates in calorimetry
 - ...
- Continue to require use of test beams first for R&D and eventually for calibration of the detectors that will be built into the experiments



3D sensors



THGEM




(S)LHC TEST BEAM NEEDS

- **Alice:**
 - mostly test beam time needed at PS, only few tests at SPS
 - semi-permanent setup (PS T4)
- **ATLAS:**
 - test beam time at SPS H8 high intensity beam line (e.g. ~250 days in 2009)
 - Magnet, Beam Telescope, gas system
 - permanent setups at SPS H8/H6
- **CMS:**
 - H2 with 3T magnet and very low energy beam
 - permanent setups at SPS H2/H4
- **LHCb:**
 - also test beam time at SPS
 - semi-permanent setup in SPS H6
- actual number of weeks per year hard to estimate at this time
- but no indication of a decrease in the test beam needs by the LHC community
- **Test beam facilities needed until well into sLHC running (>2020)**


ILC AND CLIC

- ILC: $E_{CM} = 500 \text{ GeV}$, upgradeable to 1 TeV, 300ns bunch spacing



- CLIC: $E_{CM} = 500 \text{ GeV} - 3 \text{ TeV}$, 0.2ns bunch spacing, more BG

- In general, compared to LHC much more benign radiation environment
- Detector focus on precision
- CLIC detector: must work from 0.5 – 3 TeV
- CLIC and ILC detectors R&D have 90% overlap
- 10% difference in backgrounds, fast timing, deeper HCAL,...



CDR by end 2010


R&D COLLABORATIONS




ILD



SiD



4th




- Detector concept groups submitted LOI end of March
- To be evaluated by international advisory group for technical design phase
- Organized by sub-detector
- Global participation
- task sharing, common infrastructure
- open to different technologies
- **Large test beam campaigns**




LC DETECTOR TECHNOLOGIES

Examples, not complete!

- Vertex detectors
- Main tracking
 - TPC + Si
- EM calorimeters
 - Integrated ultra-low power electronics
- HAD calorimeters
 - Novel photo-sensors
 - Digital approach







Micro-pattern gas detectors
Silicon readout, Medipix



LC TEST BEAM, PRESENT


- Vertexing/tracking tests using EUDET pixel telescope (DESY and CERN)
- TPC tests in field cage and magnet (sc, 1T) at DESY
- CALICE em+had calo test beam at CERN and Fermilab
-



Analysis in close contact with G4 team

FUTURE LC TEST BEAM STUDIES

- Standalone tests
 - normal slow extraction
 - with ILC-like time structure
 - ⊙ Vertex detector readout during or after bunch train (depending on technology)
 - ⊙ Space charge in TPC, r/o electronics
 - ⊙ Calorimeter: electronics




- 1 ms bunch trains, 300ns spacing
- Should be possible at PS test beam

FUTURE LC TEST BEAM STUDIES


- Standalone tests
 - normal slow extraction
 - with ILC-like time structure
 - ⊙ Vertex detector readout during or after bunch train (depending on technology)
 - ⊙ Space charge in TPC, r/o electronics
 - ⊙ Calorimeter: electronics

- Combined test beams
 - realistic full-size prototypes become available -> system integration and test
 - Technology and physics

- Needs a versatile facility with interchangeable sub-detectors
 - Open to all concepts - and beyond LC



- 1 ms bunch trains, 300ns spacing
- Should be possible at PS test beam



LC TEST BEAM NEEDS

- Electrons, muons and hadrons (pions, tagged protons)
- 1-100 GeV single particles
 - PFLOW goes for single particles, ILC mean pion energy 10 GeV
 - Vertex detector single point precision: multiple scattering up to 100 GeV!
- Future: multi-particle events from targets
- Large statistics: 100 configurations * 1 million events
 - PFLOW: tails, fluctuations, sub-structure, correlations

Magnet

- Vertex detector resolution, mechanical stability
- TPC sine-qua-non; resolution
- Calorimeter: shower broadening
- ~ 3T desirable, 1 T maybe sufficient
- TPC: solenoid
- Calo: could do with dipole

Linear Collider test beams in 2008:

- Vertex/tracking (EUDET, DEPFET, LCFI, ...)
 - 6 groups, 65 days at SPS, 10 days at PS
 - => similar demand in future
- Calorimetry
 - 1 group, 10 days at SPS, 30 days at PS
 - => plans for more calorimeter tests (CALICE)

RD51 TEST BEAM FACILITY AT SPS/H4

RD51 Motivation and Main Objective:

World-wide coordination of the research in the field to advance technological developments of Micropattern Gas Detectors


- many partners from sLHC and LC

- Installation of the RD51 test beam setup at CERN including **“semi-permanent”** infrastructure is well progressing:
 - services and gas system,
 - common detectors for trigger and tracking,
 - common DAQ and analysis software



- ➔ allow to reduce installation dead times and to avoid duplication of efforts and resources
- SPS/H4 beam line has been chosen for the availability of the large “Goliath” dipole magnet, and for the large amount of space in the experimental zone
 - RD51 test-beam periods in 2009: June 21- July 5, October 22-31

SPS SECONDARY BEAMS




[Edda Gschwendtner]

- Number of experiments versus year from 2001 on
- Test beam experiments rose due to LHC tests but did not decrease after LHC experiment installation
- “peak” at 2006/2007 -> more LC test beams
- Increase of number of experiments expected in the future

2009 SPS FIXED TARGET PROGRAM

Experiments and test beams

	P1	P2	P3	P4	P5	P6
	35 30 Apr 4 Jun	35 4 Jun 9 Jul	35 9 Jul 13 Aug	35 13 Aug 17 Sep	35 17 Sep 22 Oct	32 22 Oct 23 Nov
T2 -H2	EA 3 CMS CASTOR 12 CREAM 7 NA61 TR 5 CMS HCAL 8 WCALO 11 CMS 10 CMS 4 CMS 10 NA61 18 NA61 35 NA61 11 CREAM 7 NA61 17 NA61 24 NUCLEON 8					
T2 -H4	CERF 0 CMS ECAL 10 NA63 7 SITRD 7 SITRD 11 RD51 15 CMS 8 CMS 6 DREAM 16 CALICE 7 RPC 8 CALO 9 COMPASS 7 CALET 7 INSURAD 14 CMS 5 CMS 5 NA63 20 UA9 10 RD51 10 CMS 9 LHCf 13					
T4 -H6	EA 3 CMS BCM 7 MMEGAS 7 ATLAS MMEGAS 3 ATLAS MMEGAS 7 ATLAS RD42 7 ATLAS 7 ATLAS LUCID 14 ATLAS MMEGAS 8 EUDET 14 EXPER 6 LCFI 7 PILC 8 SILC 12 ATLAS 7 ATLAS 8 ATLAS 2 ATLAS 7 ATLAS 7 RD42 7 ATLAS LUCID 13 ATLAS FP420 8 ATLAS 3DS-58f 14 MonoP 8 ATLAS MMEGAS 7 3					
T4 -H8	EA 3 ATLAS 3DSi 17 ATLAS 4 ATLAS 10 ATLAS 7 ATLAS 3 ATLAS MDT-Roms 13 ATLAS 2 ATLAS 13 UA9 12 ATLAS RP 7 ATLAS RP-MDT-MPI 13 AMS 19 AMS 28 UA9 22					
T4 -P0	EA 3 NA62 8 NA62 16 NA62 28 NA62 7 NA62 7 28 35 30 NA62 5 NA62 10 22					
T6 -M2	EA 3 COMPASS 24 COMPASS 35 COMPASS 35 COMPASS 35 COMPASS 35 COMPASS 32					
CNGS	EA 3 CNGS 24 CNGS 35 CNGS 35 CNGS 35 CNGS 35 CNGS 32					



Test beams H2-H8 only:


SUPPORT AND INFRASTRUCTURE

Support by CERN

- Basic installation support
 - electronics hut with beam control terminal
 - computer network connection
 - crane usage (with operator)
- Assistance for beam tuning and operation
 - provision of beam position monitors
 - provision of (threshold) Cerenkov counter(s) (not all beam lines)

What additional infrastructure is needed ?

- Discussions showed: experiments and R&D groups have similar ideas about the needed additional infrastructure at the beam lines
 - magnets
 - trigger devices and logic
 - tracking telescope(s)
 -



Example: Bonn ATLAS telescope

MAGNETS

Goliath

- EHN1, H4 beam line
- large classical dipole
- $\sim 160 \times 240 \times 360$ cm
- 0.85 T field



Morpurgo

- EHN1, H8 beam line
- Superconducting dipole,
- diam. 1.6 m, ~ 4 m overall length,
- 1.56 T field at 5000A, used by ATLAS, contains a rail system for inserting detectors

**Clear interest from community
for more magnet facilities.**



CMS test beam magnet

- EHN1, H2 beam line
- M1 magnet,
- superconducting
- large dipole, 82 cm gap
- 1.4 m diameter, Field 3T



EUDET BEAM TELESCOPE




EUDET Telescope in CERN SPS H6B

- Pixel Beam Telescope will be at CERN
~June-November 2009

**Clear interest from community
for additional telescopes.**

PIXEL BEAM TELESCOPE:

- 6 layers of Monolithic Active Pixel Sensor (MAPS) detectors
- Pointing resolution: CERN SPS $\sim 3 \mu\text{m}$
- DUT positioner
- DAQ system (trigger, hardware + software)
- Analysis Software
- Demonstrator telescope in use since summer 2007



SUMMARY

- LHC experiments
 - after start of data taking fine details start to emerge that require exercising a realistic copy of the system in controlled conditions.
 - better understanding of detectors might be necessary (e.g. calorimeters)
 - need of test beam facilities until ~2012
- sLHC Detector R&D has started
 - many new technologies are already being studied
 - after technology decision similar exhaustive TB program as for LHC needed
 - test beams needed until >2020 (permanent installations)
- LC - CLIC and ILC detectors have 90% synergy -> test beam efforts cover both
 - realistic prototypes under way
 - next step: integrated test beam (tracking + magnet + calorimetry) --> permanent installation
 - test beams needed until >2020
- Additional infrastructure as magnets and beam telescopes needed
- Education - hands on detectors for students often only possible during test beam