



# CTF3 status + experimental program

What can be expected by 2010 +  
possible improvements afterwards

Frank Tecker – CERN  
for the CTF3 team

- Introduction
- CTF3 status + achievements
- CTF3 experimental program
- Conclusion







# CTF 3




- demonstrate **Drive Beam generation** (fully loaded acceleration, bunch frequency multiplication 8x)
- Test CLIC **accelerating structures**
- Test **power production structures (PETS)**

- 2003 Injector + part of linac
- 2004 Linac + 30 GHz test stand
- 2005 Delay Loop
- 2006/07 TL1 + Combiner Ring
- 2008/09 New photo-injector, TL2 + CLEX







# CLEX – Installation status



- TL2, TL2', CALIFES, and TBTS lines finished had first beam
- Shutdown 08/09:
  - Initial TBL installed
  - Tail Clipper in TL2
- Summer/Autumn 09
  - TBTS accelerating structure
  - continue TBL installation (see Steffen)







# Some Highlights since last ACE



- new RF deflectors allowed high current CR operation
- **TBTS PETS** produced RF power (as shown by Igor)
- CALIFES probe beam studies
- transported to end of TBTS
- PHIN photoinjector successful run
- careful RF setup for long pulses in view of DL/CR combination
- Delay loop beam reestablished







# CTF3 base line programme



## CTF3 – R&D Issues - where



R.Corsini




# Comparison CLIC - CTF3



	CTF3	CLIC
Energy	0.150 GeV	2.4 GeV
Pulse length	1.2 $\mu$ s	140 $\mu$ s
Multiplication factor	2 x 4 = 8	2 x 3 x 4 = 24
Linac current	3.75 A	4.2 A
Final current	30 A	100 A
RF frequency	3 GHz	1 GHz
Deceleration	to ~50% energy	to 10% energy
Repetition rate	up to 5 Hz	50 Hz
Energy per beam pulse	0.7 kJ	1400 kJ
Average beam power	3.4 kW	70 MW



- Still **considerable extrapolation** to CLIC parameters
- Especially total beam power (loss management, machine protection)
- Good understanding of CTF3 and benchmarking needed




# Full beam-loading acceleration in CTF3




- high current **routine operation demonstrated**



- **Measured RF-to-beam efficiency 95.3%**
- **Theory 96%**  
(~ 4 % ohmic losses)






# Beam current stability



- operation **sensitive to beam current variations**
- instable, defective gun made commissioning very tedious
- repaired, much more stable this year
- stability  $\sim 0.1\%$  end-of-linac,  $\sim 0.2\%$  combiner ring
  
- we see current variation over the pulse  $\Rightarrow$  different energy
- $\Rightarrow$  feed-forward needed  
foreseen in gun but not implemented
- **Energy stability**
  - RF phase stabilisation for klystrons put into operation
  - short term jitter presently  $\sim 0.5 \cdot 10^{-3}$






# SHB system – Phase coding




- Key parameters for the SHB system:
- 1) time for **phase switch**  $< 10$  ns (15 1.5 GHz periods)
  - 2) **satellite** bunch population  $< 7$  %  
(particles captured in 3 GHz RF buckets)

## phase switch:




Phase switch is done within eight 1.5 GHz periods ( $< 6$  ns).


## satellite bunch population:




Satellite bunch population was estimated to  $\sim 8$  %.




# Delay Loop operation




- 1.5 GHz sub-harm. bunching system
- 1.5 GHz RF deflector



# Delay Loop – full recombination



- 3.3 A after chicane  $\Rightarrow$   $< 6$  A after combination (satellites)






# Demonstration of frequency multiplication




## CTF3 - PRELIMINARY PHASE 2001/2002

Successful **low-charge demonstration** of electron pulse combination and bunch frequency multiplication by up to factor 5

Streak camera image of beam time structure evolution







# RF injection in combiner ring



- combination factors up to 5 reachable in a ring

$$C_{ring} = (n + 1/4) \lambda$$







# Combination setup procedure



- Developed a setup procedure to optimize combination
- 5 parameters
  - **Amplitude** and **phase** in each deflector
  - **RF frequency** (no wiggler for path length tuning)
- Monitor **trajectory** differences over various turns






# Isochronicity Tuning




- ring optics needs to be **isochronous** to keep short bunch length  
=> high power extraction efficiency
- Streak Camera observations




non-isochronous – 2<sup>nd</sup> turn



isochronous – 60<sup>th</sup> turn




$\Delta p \propto \frac{\Delta p}{p}$   
↑



→ Time



- **momentum compaction**  
 $\alpha_p < 10^{-4}$




# CR RF deflectors $\Rightarrow$ Instability



- RF deflectors had a vertical mode that deflects the beam
- Could be minimized by proper phase advance – not done









# CTF3 combiner ring - latest status



- Recombination at higher current achieved
  - DL bypassed (no holes, missing factor 2)








# Measurement of the ring length




- BPR: RF Phase Monitor
- Mix of the beam induced signal and internal frequency (3 GHz)
- FFT of the signal




- Wiggler behaviour as expected
- About 1.5 mm difference only
- control to better than **0.5 mm**



# Bunch length measurements






# State of the art today




- ongoing Drive Beam generation demonstration in CTF3.
  - **Full beam loading** (95% transfer), high current operation (up to 5A) of drive beam linac
  - Sub-Harmonic bunching, **phase coding** (8.5% satellites)
  - Bunch train recombination factor 2 in **Delay Loop** (from 3.5 to 7 A)
  - Bunch train recombination factor 4 in **Combiner Ring** (3 to 12 A)
  - **Isochronous operation** of ring,  $\alpha_p < 10^{-4}$
  - Transverse rms **emittance**  $100 \pi$  mm mrad (end of linac only)
  - **Bunch length** control to  $< 1$  mm rms (end of linac only)
  - Control of **ring length** to better than 0.5 mm
  - Beam **current stability**  $\sim 0.1\%$  end-of-linac,  $\sim 0.2\%$  combiner ring




# The final combination...



- Delay Loop and Combiner Ring combination **simultaneously**
- Operation becomes more demanding
- Stability + reproducibility
- current fluctuations over the pulse
- (RF phase variation over the pulse - not for CLIC)
- Isochronicity
- Emittance in combination
- Bunch length control
- ...




30 A current !



# To be addressed ...




- Full **bunch length** manipulations **in TL2** after combination
- RF power production in CLEX
- **Two-beam operation** in TBTS (relevant CLIC sub-unit)
- **Deceleration** stability
- **Loss management**, machine protection system
- Satellite bunches
- Photo injector option
- ...



# 2009 experimental program





- **30 GHz:** One structure test (TM02) + breakdown studies ✓
- **PHIN** Beam characterization, reach  $\frac{1}{2}$  of nominal bunch charge ✓
- **CALIFES** Beam characterization, beam to TBTS (most likely reduced current)
- **Delay Loop** Back in operation, retrieve combination x 2 ( $\sim 7$  A)
- **Comb.Ring** Final optics checks, isochronicity, put together with DL ( $> 24$  A)
- **TL2** Complete commissioning (tail clipper), bunch length control  
 $> 20$  A to users
- **TBTS** PETS to nominal power/pulse length (15 A, recirculation)  
Beam commissioning of probe beam line  
First accelerating structure tests (one structure – CLIC G)  
Two-beam studies (de-/acceleration), initial breakdown kick studies
- **TBL** PETS validation (100 MW, **need  $> 20$  A**)  
beam line studies (2-3 PETS ?)
- **Others** CDR studies in CRM, beam dynamics benchmarking,  
stability studies, control of beam losses




# Long DB pulses in CTF3



- DL length limits to 140 ns
- Longer pulses** at the expense of **lower current**
- use **recirculation** in the TBTS PETS
- model well understood








# Goals for 2010




- **DB Linac** current + energy stability  $\sim 10^{-3}$
- **Comb.Ring** Final combination together with DL ( $> 28$  A)  
combined emittance  $< 150 \pi$  mm mrad
- **TL2** Complete bunch length control ( $< 1$  mm)  
 $> 28$  A to users
- **TBTS** PETS to nominal power/pulse length (15 A, recirculation)  
Accelerating structure tests  
Two-beam studies (de-/acceleration), breakdown kick studies
- **TBL** beam line studies (8 PETS)  
deceleration studies (by  $\sim 33\%$ )
- **Others** Beam loading compensation of probe beam,  
phase stability, ...




# Phase measurement & feed-forward



- phase stability  $0.2^\circ @ 12$  GHz (46fs) required
- electronics tested in CTF3 and demonstrated **sub-10 fs resolution**
- FP7 Task 9.5: Drive Beam Phase Control (F. Marcellini/LNF)
  - RF monitor (INFN/CERN) – final tests in CTF3
  - Electro-optical monitor (design, prototype, tests PSI)
- Common characteristics:
  - Very low coupling impedance
  - Filters to reject wake fields and RF noise
  - Application also in other machines where precise high frequency beam phase detection is necessary










# CTF3 drive beam linac evolution




- Increase power to increase current/energy




$I_{\text{Linac}}[\text{A}]$	$I_{\text{CLEX}}[\text{A}]$	T [MeV]
0.1	0.72	246
3.6	25.9	156
4.9	34.9	125
0.1	0.72	279
3.6	25.9	179
4.9	34.9	143
0.1	0.72	303
3.6	25.9	203
5.3	38.2	154
0.1	0.72	402
3.6	25.9	270
5.3	38.2	206





# Instr. Test Beam Line, ITB




- Dedicated beam line for beam diagnostics R&D using CALIFES beam
  - low  $\varepsilon$  beam well known and characterised at location of test device
  - possibility to achieve very short bunch length, variable time structure
  - Independent of drive beam operation
- Test & experiments which could be performed in ITB
  - BPM & WCM developments
  - Coherent diffraction radiation monitors
  - Longitudinal profile monitors
  - Halo monitors
  - ...
  - Beam loss monitors
  - Single shot emittance measurements
  - Test of CLIC X-band crab cavities
  - Wakefield measurements (i.e. collimators)



# Photo-injector option




- Smaller transverse emittance, shorter bunches, no energy tails, no satellites
- Lower current
- Single bunch option will allow:
  - high precision beam optics check and correction
  - high precision CSR measurements in DL, CR and TL2 bunch compressor.
  - $\delta$  response of PETS and beam instrumentation




# Photoinjector PHIN




- **very successful** runs end 2008/2009
- transverse optics + beam-loading studies
- long-term behaviour ( $Q_e$ ) to be studied
- **Phase coding** to be demonstrated



	<b>PHIN design</b>	achieved Apr. 2009
RF power [MW] unloaded	13	13
beam energy [MeV]	5-6	5.3
number of bunches	1908	3000
bunch spacing [ps]	666.7	666.7
charge per bunch [nC]	2.3	~2.3 (@500ns) 1.5 (@1270ns)
repetition rate [Hz]	5	0.8
bunch length FWHM [ps]	< 10	< 10 ?
rms. energy spread [%]	< 2	0.5
n. emittance [ $\pi$ mm mrad]	< 25	5-7
vacuum pressure [mbar]	$< 2 \times 10^{-10}$	$< 4 \times 10^9$ (no NEC)






# Validation of DB scheme



Parameter	Unit	CLIC nominal	Present state	Objective 2010	Objective 2012
<b>I initial</b>	<b>A</b>	<b>7</b>	<b>5</b>	<b>5</b>	<b>5</b>
<b>I final</b>	<b>A</b>	<b>100</b>	<b>12</b>	<b>30</b>	<b>30</b>
<b>Q<sub>b</sub></b>	<b>nC</b>	<b>8.4</b>	<b>4</b>	<b>2.5</b>	<b>2.5</b>
<b>Emittance, norm rms</b>	<b>π mm mrad</b>	<b>≤ 150</b>	<b>100 (end of linac)</b>	<b>≤ 150 (comb. beam)</b>	<b>≤ 150 (comb. beam)</b>
<b>Bunch length</b>	<b>mm</b>	<b>≤ 1</b>	<b>≤ 1 (end of linac)</b>	<b>≤ 1 (comb. beam)</b>	<b>≤ 1 (comb. beam)</b>
<b>E</b>	<b>GeV</b>	<b>2.4</b>	<b>120</b>	<b>120</b>	<b>150</b>
<b>T<sub>pulse</sub> initial</b>	<b>μs</b>	<b>140</b>	<b>1.4</b>	<b>1.4</b>	<b>1.4</b>
<b>T<sub>pulse</sub> final</b>	<b>ns</b>	<b>240</b>	<b>140 (240)</b>	<b>140 (240)</b>	<b>140 (240)</b>
<b>Beam Load. Eff.</b>	<b>%</b>	<b>97</b>	<b>95</b>	<b>95</b>	<b>95</b>
<b>Deceleration</b>	<b>%</b>	<b>90</b>	<b>-</b>	<b>50</b>	<b>50</b>
<b>Phase stability @ 12 GHz</b>	<b>degrees</b>	<b>0.2</b>	<b>-</b>	<b>?</b>	
<b>Intensity stability</b>		<b>7.510<sup>-4</sup> to few 10<sup>-5</sup></b>	<b>10<sup>-3</sup></b>	<b>?</b>	




# CTF3 operation



- 1 staff + 1 fellow + 1 Research Associate operate routinely the machine
- + support from other staff partially + 1 fellow for stability/feed-back studies
- 1 white paper post to be opened now
- maximize run time by 2 'shifts' per day presently not done any more
- Supervision of linac by shift operators foreseen and starting
- Weekly supervisor to coordinate activity
- Daily commissioning meeting
- Remarks:
  - Work concentrated on commissioning of new components
  - Increased complexity
  - Higher demand for availability of components
  - Full recombination (DL + CR) to be demonstrated
  - Operation becomes more demanding in terms of stability
  - Review the performance and identify bottlenecks





# Conclusion



- **Drive Beam generation** very well covered
  - **fully loaded operation** demonstrated and routinely used
  - **bunch train combination** principle shown (DL/CR)
  - optimization procedures developed
  - full current **DL/CR combination** will be **done soon**
  - **performance and stability still to be addressed**
- next major steps:
  - **two beam tests** in TBTS
  - **drive beam deceleration** in TBL
- Many options for the TDR phase => see Roberto's talk
- **Many THANKS to all collaborators!**