

Equipment status for temperature regulation on top of current leads

Tests in CNGS

Equipment status

Test periode	Regulator 1	Regulator 2	Regulator 3	SSR 1	SSR 2
6 -> 20 oct 08	Stopped the 11th → HS N: $13 \cdot 10^9 \text{ cm}^{-2}$	Stopped the 15th → restart N: $28 \cdot 10^9 \text{ cm}^{-2}$		Stopped the 11th by Reg 1 N: $13 \cdot 10^9 \text{ cm}^{-2}$	Stopped the 15th by Reg 2 N: $28 \cdot 10^9 \text{ cm}^{-2}$
27 may -> 15 june 09		N: $4 \cdot 10^9 \text{ cm}^{-2}$	N: $4 \cdot 10^9 \text{ cm}^{-2}$	N: $4 \cdot 10^9 \text{ cm}^{-2}$	N: $4 \cdot 10^9 \text{ cm}^{-2}$
27 may -> 30 june 09		N: $47 \cdot 10^9 \text{ cm}^{-2}$	Stopped the 20th N: $7 \cdot 10^9 \text{ cm}^{-2}$	Stopped the 20th by Reg 3 N: $7 \cdot 10^9 \text{ cm}^{-2}$	N: $47 \cdot 10^9 \text{ cm}^{-2}$
Cumul	N: $13 \cdot 10^9 \text{ cm}^{-2}$ HS	N: $75 \cdot 10^9 \text{ cm}^{-2}$ 1 stop but still working	N: $7 \cdot 10^9 \text{ cm}^{-2}$ 1 stop Still OK ?	N: $20 \cdot 10^9 \text{ cm}^{-2}$ 2 stops by reg1 & reg3 Still OK ?	N: $75 \cdot 10^9 \text{ cm}^{-2}$ 1 stop by reg2 but still working

N: Fluence of 1MeV neutrons equivalent

Tests in CNGS in 2008

- 2 control units were installed in CNGS with 2 controllers and 2SSR (25A and 50A)
- First tests occurred from the 6th to 20th oct 2008
 - First unit (with SSR 50A): Operationnel until the 11th oct.
 - Hadrons ($E > 20\text{MeV}$) = $12 \cdot 10^9 \text{ cm}^{-2}$
 - Neutrons ($E_{\text{eq}} 1\text{MeV}$) = $13 \cdot 10^9 \text{ cm}^{-2}$
 - Second unit (with SSR 25A) : Operationnel until the 15th oct.
 - Hadrons ($E > 20\text{MeV}$) = $28 \cdot 10^9 \text{ cm}^{-2}$
 - Neutrons ($E_{\text{eq}} 1\text{MeV}$) = $32 \cdot 10^9 \text{ cm}^{-2}$
- 2 units stayed in zone until the 20th oct.
 - Hadrons ($E > 20\text{MeV}$) = $50 \cdot 10^9 \text{ cm}^{-2}$
 - Neutrons ($E_{\text{eq}} 1\text{MeV}$) = $55 \cdot 10^9 \text{ cm}^{-2}$

Tests in CNGS in 2009

- In oct 08 the display of the 2 regulators did not work.
- In April 09, the 2 units were tested. The 2 SSR worked perfectly well as well as one of the regulator (from unit 2).
- For phase 1, the regulator of the unit 1 has been replaced and the 2 control units are now in CNGS (TSG46) but not directly exposed in front of the tunnel but slightly protected by the wall.
- For phase 2, the 2 units have been slightly moved forward to the gallery, the radiation received is almost 10 times higher than before (phase1)
- Phase 1
 - Dose (TGS4.CNGS08:Dose_LS) = 0.18 Gy
 - Neutrons = $4.3 \cdot 10^9 \text{ cm}^{-2}$
- Phase 2 (until the 30th june)
 - Dose (TGS4.CNGS08:Dose_LS) = 1.1 Gy
 - Neutrons = $47 \cdot 10^9 \text{ cm}^{-2}$