


CMS Solenoid Construction and Test









CMS is a general purpose LHC detector based on a solenoidal magnetic field of 4T in a 6m diameter free bore, the detector layout is organized around the Magnet



2006 LHC DAYS IN SPLIT




Diocletian's Palace/Palazzo Milesi, Split, Croatia 2 - 7 October 2006





On the 22nd August 2006 the CMS Magnet has successfully reached its target field of 4 T



This result is the coronation of 15 years of efforts provided by all the Participating





Genesis of CMS Coil



At the end of 1990 Michel, Jim, Karsten & Radi requested for their experiment CMS:

To have a solenoid around 6 m diameter and 13 m long with at least 3.5 T and if possible 4 T as ultimate field.

H. Desportes & R. Duthil / CEA Saclay and A.Hervé/ CERN

were approached for their great experience in the conception of big magnets for High Energy Physics experiments





CMS wrt ALEPH



Aleph, at LEP, has always been considered as a mock up for CMS


	CMS	ALEPH	factor
Inner Bore	6.3 m	4.96 m	1.25
Length	12.5 m	6.35 m	2
Central field	4 T	1.5 T	2.6
Nominal current	19 kA	5 kA	4
Stored Energy	2.65 GJ	137 MJ	20
Cold mass	220 t	25 t	9





Absolute and Specific stored Energy of Main large magnets for HEP Experiments

CERN










From Aleph

- Passive protection by Quench-Back effect
- Al stabilized NbTi conductor (insert of CMS)
- Indirectly cooled at 4.5 K by thermo siphon circuits
- Inner winding vacuum impregnated with epoxy resin New for CMS
- Mechanically reinforced conductor (to contain magnetic forces)
- 4 Layers (because of needed Ampere-turns)
- 5 modules (to limit unit length of conductor)



The Preliminary design Design was achieved in 1996 by CEA







CMS



CMS Coil Parameters



Magnetic field at center	4 T	
Nominal current	19120 A	
Stored Energy	2650 MJ	
Peak field at conductor	4.6T	
Coil Length	12.5 m	
Coil made of 5 modules with length	2.5 m	
Inner Diameter	6320 mm	
Outer Diameter	6950 mm	
Each module is made of 4 layers		
Required conductor length	4 x 2400 m	
Module Weigth = $4 \times 8300 \text{ kg}$ (Conductor)		
+ 8000 kg (Mandrel)	42 t	
Total weigth of the coil	220 t	





1993-1996 Early developments for 55km of CMS insert











Construction of the Yoke 1998 - 2002





Pre-assembly at Deggendorf (1999)



Extraction of YB+2 from the Ferris wheel assembly tooling (2001)

Final assembly at CERN





The Yoke has been completed in 2003 to be ready to accept the cold mass and the muon chambers












The CMS Conductor feasibility was proven in 1999 and 2 years were needed for the fabrication of its main



components


















The Fabrication of the CMS conductor took place between 2001 and 2003













The winding has been done by ANSALDO Superconduttori under the supervision of INFN Genova from 2000 until 2005









S IN SPLIT /Palazzo Milesi, 7 October 2006



Impregnation of the first module Feb 2003





Split, Croatia 2 - 7 October 2006



After impregnation each upper surface of modules was machined for good coupling









Coil Module Transportation Jan2004 / Feb 2005














Pile-up of module at SX5







Electrical connection and instrumentation









Hydraulic connections

-





The 5 modules piled up (February 2005)



The cryogenic circuit closed to the chimney





Thermal shield installation Feb-June 2005







Coil Swiveling August 2005









Coil insertion









The Inner thermal shield being inserted in its vactank Sept 2005





Split, Croatia 2 - 7 October 2006



Connection to the cryogenic chimeny









Installation and connection of the current leads







The current lead chimney assembly





Cryogenics





The plant has been specified for the following performance:

- During cool down : up to 30 kW
- In steady state : 800 W at 4.45 K + 4500 W at 60-80 K + 4 g/s liquefaction
- In failure mode : up to 40 g/s liquefaction

The compressor station, installed in 2001 has been commissioned mid 2002

The cold box has been installed from May to Nov 2002 and commssioned from July 2003 until March 2005



Some problems encountered the to oil coales cer perfanoanded Whith Whith Whith pollution of the circuits) and start up of the 3rd stage turbine in the course which had Repetitive Tailine ace/Palazzo Milesi, Split, Croatia 2 - 7 October 2006






Nominal performance of the cryo plant were reached in March 2005 with the help of an addititional thermal load to simulate the coil



• Refrigeration power as a function of T









CMS Power Converter: 20 kA; +26/-23 V



Type: Tyristor bridge rectifier, bipolar in voltage, Output nominal voltage: -23V .. +26V Output nominal current: 20000 A Nominal power for ramping-up: 520 kW Mains supply voltage: 400V, 50Hz, 3-phase Mains supply current: 320 Arms Voltage ripple: 1 % Current precision: 5 ppm pk-pk







Dump resistor at SX5










Closing of the vacum tank flanges





January 2006: End of the CMS Magnet Manufacturing





Cool down of the Coil went smoothly










Shrinkage and stress after cool down



	Design value	Measured value
Cold Mass Shrinkage		
Longitudinal	26 mm	27 mm
Radial	14 mm	15 mm
Tie rod stress due to cool-down		
Vertical	50 MPa	47 MPa
Radial	150 MPa	156 MPa
Longitudinal	250 MPa	234 MPa




Displacemet mm





Test Configuration in the SX5










- The Magnet Commissioning has been coupled with a so called Cosmic Challenge Test to show good working of the whole detector
- This goal has implied the mounting of a significant part of Muon Chambers in the Yoke and Hcal + Ecal + Tracker parts
- The exercise has lasted until July 2006





HCAL Barrel inserted







Insertion of the Tracker










Barrel Yoke ready for closure with endcaps June 2006









Survey has been constantly assured to reach an alignment of 1 mm wrt the ideal axis







Diocletian's Palace/Palazzo Milesi, Split, Croatia 2 - 7 October 2006



Another basic achievement was the correct closing of all the Yoke elements



Air pads + grease pads are used to move each of the 11 elements of CMS

The preliminary marking of the position on the floor has been done to stay within a +/- 5 mm tolerance and get then an alignement with an accuracy of 1 mm with respect to the ideal magnetic axis of the yoke








Mid July 2006 CMS Closed: ready to inject high currents











Goals :

- Ramp the Coil up to nominal current and check the 3 standard discharging modes comparing measures with design values
- In particular: overpressure during a fast discharge, final temperature of the coil after a FD, voltage on the current leads, real time constants of the circuits, temperature wrt to He flow in the current leads etc....






Magnet Control



MCS : Magnet Control System

- MSS : Magnet Safety System
- CDS : Constructor Detection System







The Core to run the Magnet is the Cold Mass and its electrical behavior



- L = 14 H
- R = 30 mOhm at Room Temp


R fd = 30 mOhm

R sd = 2 mOhm

V of power supply is +26/-23V corresponding to a max theoretical di/dt of +1.8 A/s and -1.6 A/s

In practice (including line resistance and inductance) these values become +1.7 A/s to ramp up and -1.4 A/s to ramp down

In case of problems on the main the discharge can be done on a resistor bank in a "slow" mode to keep the magnet superconductive or a "fast" mode in case of quench





Powering and discharging modes




FD : 190 s (pseudo time constant) on a 30 mOhm Resistor

SD : 300 minutes on a 2 mOhm Resistor

Power supply : from +1.7 A/S to -1.4 A/s (+26/-24V)

The ramping down with power supply is the standard mode because is driven by voltage (control of the speed) and allows flat tops and restarts







Powering steps as made during commisioning





- 25 July : 1 kA then 3.5 kA as preliminary test and discharge with power supply
- 26 July : 7.5kA followed by a fast dump which looked OK
- 31July : reached 12.5kA and generated a FD, but the magnetic relief valve did not work and we got the rupture of the safety disk.
- During the following week a mechanical relief valve was added in parallel
- 11 August : reached 15 kA (3T) followed by a good FD but magnetic safety valve not repetitive
- 17August: reached 17.5 kA followed by a very encouraging FD
- 22 August : reached 19kA and 4T, however a fast dump was accidentally triggered by the bad behavior of a DCCT in the stray field, nevertheless the FD behaved as expected. Shielding of the DCCT was improved.
- 26 and 27 August : the magnet has been operated constantly at 18kA (3.8T) for MTCC.
- 28 August : the magnet has been ramped up to 19.14 kA (4T + 3.05%) and staid at the nominal field to the completing the technical tests. It has been followed by a fast discharge still triggered by the DC Collarzo Milesi, by a fast discharge still triggered by the DC Collarzo Milesi,



Magnet cycles in August 2006










Fast discharge pressure rise curves





He release during a Fast Discharge



QuickTime[™] and a YUV420 codec decompressor are needed to see this picture.





Magnet Commissioning




Main Results of the Magnet Test





Current and and coil maximum temperatures during FDs with a FD at 19.14 kA and 15 kA










Current and Coil Resistance during a FD










FD Current Decays





time, in s





Decrease of time constant with current



Opening of breakers Time constant variation 1.1 FD at 7.5kA 1 -FD at 12.5kA 0.9 -FD at 15kA -FD at 17.5kA 0.8 -FD at 19kA 0.7 0.6 I / Io 0.5 0.4 0.3 0.2 0.1 0 60 120 180 240 300 0 360

Comparison of fast discharges

time, in s



2006 LHC DAYS IN SPLIT Diocletian's Palace/Palazzo Milesi,

Split, Croatia 2 - 7 October 2006



Coil Voltage during FD at 19 kA



time, in s








Quench back of the coil during a FD at 7.5 kA

Module CB/0 fully quenched 350s before CB/-1



Coil temperatures with a FD at 7.5kA




Delay in quenching of each module at 12.5 kA



Quench back of the coil during a FD at 12.5 kA

Module CB/0, CB/-1 and CB/+1 fully quenched 40s before CB/-2 and CB/+2



Coil temperatures with a FD at 12.5kA






Dealy in quenching of each module at 19 kA

Quench back of the coil during a FD at 19.12 kA

All modules fully quenched 10s after CB/0





Summary table of FD parameters



FD current (kA)	Coil maximum temperature (*)	Coil average temperature	Coil maximum voltage	Coil energy	Time constant I ₀ /e
7.5	21.4 K	17.6 K	198.0 V	395 MJ	500 s
12.5	53.0 K	43.3 K	330.4 V	1.097 GJ	353 s
15	66.9 K	54.1 K	403.6 V	1.575 GJ	263 s
17.5	79.4 K	63.2 K	475.0 V	2.144 GJ	200 s
19.01	86.1 K	68.9 K	517.3 V	2.530 GJ	177 s
19.14	86.8 K	69.6 K	513.4 V	2.564 GJ	-

(*) always on CB/0, inner radius











Temperatures and electrical resistance during the fast discharges



time in s



Temperatures of resistance during the fast discharges











Water cooled busbars

The water flow was set lower than specified at 4m3/hr, following a 1-hour test at 20kA on a short circuit:

	Ambient temperature	Bar temperature	Braids temperature
Ground level	24° C	27.2° C	27° C
On top of YB/0	29° C	27.7° C	31° C to

During the test, the temperature didn't exceed 27° C, average was 25° C, with an average ambient temperature of 21° C, at nominal current and during the 2-days run.






Stresses on CB0 mandrel



As shown on the fig. 2, the Von Mises stress measured is 34 MPa at zero field and 138 MPa at 4T. These values are in complete agreement with the computation performed by C. Pes in 1998 (32 MPa at zero field and 138 MPa at 4T) ! (see report 5C 2100 T –M 1000 031 98)



Stresses on CB/0 external cylinder



Vertical tie rods



The stress is between 75 and 92 tons each (weight + cooling+ magnetic forces) wrt 321 t max admissible Forces on the vertical tie rods Tested in Saclay up to 100 tons

→ TV-1 **—*T**V+2 current, in kA






Longitudial tie rods



The stresses are between 40 and 50 tons each wrt 202 t max admissible, TL4 takes the charge later due to a higher pre-stress









Displacement of Disk YE+1 compressed by 12.000 t











Diocletian's Palace/Palazzo Milesi, Split, Croatia 2 - 7 October 2006







Displacements of YE/+1 with respect to YB/+2 on the outer radius and on the cart








Due to the 10'000-tonne magnetic attraction force, the Nose moves toward IP by 16mm!







The 600 mm thick iron YE1 disk behaves like a Belleville washer and rotate around the circumferential line of Zstops





Some consideration



- The Coil has a stable and reliable behavior in all conditions
 - No spontaneous quench has occurred
 - Two FD have been generated by the effetct of the fringe field on some ancillaries
 - The regulation of the Helium flow on the current leads must be optimized to avoid under cooling of these elements





Next future actions



- Check the slow discharge behavior in parallel with the field mapping campaign (October 2006)
- Lower elements in the experimental cavern immediately after (starting November 2006)







The experimental cavern is being equipped with ancillaries 2005 Sept 2006








Main beam test at 2500 t pulling on the main plug (1700 t + 800 t additional)








Diocletian's Palace/Palazzo Milesi, Split, Croatia 2 - 7 October 2006



Lowering test with 250 t








Diocletian's Palace/Palazzo Milesi, Split, Croatia 2 - 7 October 2006




Jack system to open and close CMS in the UXC





















- The success of the Magnet Project, coupled with the Cosmic Challenge Test, is a major achievement for CMS
 - All the Institutes are represented in the CMS Magnet and one of the efforts has been to give direct involvement to Instituites and Companies from every participating country







Copper Busbar in the pillar wall







Installation of Copper Busbar







CMS



Installation of Copper Busbar









Gold AWARD to Koncar



















- After 15 years from early design, R&D, preindustrialization, 6 years of construction and about one year of installation, CMS coil has been tested successfully.
- From cryogenic, electrical and mechanical tests the coil fulfills all specifications and seems easy to operate.
- Installation of CMS detectors inside the experimental area can proceed.





Prospect for future (2)



- ATLAS central solenoid and CMS solenoid have used different techniques to achieve a high E/m ratio.
- There is a common proposal* to mix the two techniques to produce an even stronger conductor.
- This should allow the design of CMS-like solenoids with central field up to 5T.
- * A. Yamamoto, D. Campi et al.









- This good result open the way to the design of 5 T solenoids for future experiments.
- The way the CMS collaboration has been organized financially and technically to build the magnet seems a good model to follow.

