



Development, test, installation, and commissioning of the 3 MW superconducing EcoSwing wind power generator

Markus Bauer on behalf of the EcoSwing consortium Thu-Mo-Or18-01 – MT26, September 26, 2019, Vancouver, Canada

Acknowledgements to the Team ecoswing



Alexis Riviere Anders Rebsdorf Anne Bergen Ans Veenstra Aurélie Fasquelle Aymen Ammar **Bastian Schwering** Benoît Dupont **Bob Deobil** Carsten Bührer Cédric Dupont Christian Broer Christian Koppe Christian Kruse Christian Mehler Daniel Laloy David Laurent Frederick Deneubourg

Hans Kyling Hendrik Pütz Hermann Boy Jan Wiezoreck Jean-Luc Lepers Jean-Philippe Francke Jens Krause Jesper H.S. Hansen Jürgen Kellers Kazu Raiiu Kimon Argyriadis Konstantin Yagotyntsev Marc Dhallé Marcel ter Brake Markus Bauer Martin Keller Martin Pilas Matthias-Klaus Schwarz

Michael Reckhard Mogens Christensen Nathalie Renard Patrick Brutsaert Peterson Legerme Roland Stark Sander Wessel Sofiane Bendali Stephane Eisen Thomas Hisch Thomas Skak Lassen Thorsten Block Tiemo Winkler Torben Jersch Trevor Miller Vadinho Debrito Werner Prusseit Yoichiro Ikeya Yves Debleser





The EcoSwing Story





See

https://www.theva.com/video-zum-abschluss-des-ecoswing-projekts/

https://www.youtube.com/watch?v=NxMkZHyM9UQ

Or



Publications (published):

- Song et al.: Designing and Basic Experimental Validation of the World's First MW-Class Direct-Drive Superconducting Wind Turbine Generator, IEEE Transactions on Energy Conversion DOI: 10.1109/TEC.2019.2927307
- Winkler et al.: The EcoSwing Project, IOP conf. series: Mat. Sc Eng. DOI:10.1088/1757-899X/502/1/012004
- Slides on AC loss calculation (in German): https://elenia.tubs.de/fileadmin/content/sls/9sls/04 Kra use.pdf

Publications (submitted)

- SUST: Design and in-field testing of world's first ReBCO rotor for a 3.6 MW wind generator
- IEEE TEC: Ground Testing of the World's First MW-Class Direct-Drive Superconducting Wind Turbine Generator
- Applied Energy: Commissioning of the World's First MW-Class Direct-Drive Superconducting Generator on a Wind Turbine



Agenda




- Overview on project
 - Design, component testing, assembly
- Ground testing in Bremerhaven, Germany
- Installation and operation on wind turbine in Thyboron,
 Denmark
- Summary




Our ambitions







- Design, develop and manufacture a full-scale multi-megawatt superconducting wind generator
- Install this superconducting drive train on an existing modern wind turbine in Thyborøn, Denmark, replace existing PM generator (3 MW Class, 14 rpm, 128 m rotor)
- Prove that a superconducting drive train is lighter, smaller and cost-competitive.
- Start Date: 2015-03-01 End Date: 2019-04-30



UNIVERSITY OF TWENTE.


THEVA





Elements of the EcoSwing superconductive generator






EcoSwing design



- Decreased diameter from 5.4 m (PM generator) to 4 m
- Built EcoSwing generator:
 25 % weight reduction
 compared to PM generator
 of same diameter

Commercial design:
 40% weight reduction compared to PM generator.





Qualification of Materials and Procedures Just a few examples...



Qualification of superconductive joints



Validation of magnetic properties





Validation of copper RRR

ECOSWING Copper pie	eces				
Potential measured across 2.5 cm					
Measurement current: 1A at low ter 273.15 K	mperatures, 0.1A at				
Operator: Jaap Kosse					
Measurement date: 14/10/15					
Sample	RRR (273.15/10)	RRR (273.15/30)	R at 273.15K [Ω]	R at 10K [Ω]	R at 30K [Ω]
Piece 2, Electrical connection, #1	124.2	81.6	4.403E-04	3.545E-06	5.395E-06
Piece 2, Electrical connection #2	123.5	81.8	4.575E-04	3.705E-06	5.596E-06
Piece 3, Cooling Plate, #1	78.6	59.0	9.524E-04	1.212E-05	1.613E-05
Piece 3, Cooling Plate, #2	78.7	59.2	9.471E-04	1.203E-05	1.600E-05



Qualification of Materials and Procedures Just a few examples...




 Qualification of lubricants and adhesives

 Qualification of structural materials (w/ TNO Delft)

 Qualification of getters, sealants, procedure for affixing MLI...






HTS full scale coils



Main characteristics

- Used wire: Standard THEVA Pro-Line HTS conductor with 100 μm Copper lamination
- Each coil contains more than 500 m of HTS wire and has about 200 turns
- Insulated design, 12 μm thin insulation foil
- Coils are 1.4 m long, double pancake
- Potted in resin
- Operating temperature < 30 K, conduction cooled




EcoSwing rotor coil





Type test and routine test of HTS coils






40% 20%

- Performance better than expected
- Nearly linear I_c(T)

Temperature (K)

→ Type test passed on first attempt



Type testing first coil




77K routine testing of coils





Simple setup to test in liquid nitrogen



- Fast and efficient series testing in liquid nitrogen (77K, -196°C)
- All coils exceeded performance criteria (120 A)
- Coil production yield:
 - Overall 89% (45)
 - Second half: 100% (20)

Successful small series production of HTS coils!






Assembly of a superconducting generator























Main components of cooling system on rotor














- Contacts with tested heat flow resistance
- Monitoring of temperatures: 90 sensors (rotor alone)



Cooling system




Concept:

- Conduction cooling with rotating GM cryocoolers
- Tested off the shelf components
- New: rotational He gas (warm) feedthrough solution to exchange cold heads with cold rotor



- SRDK-500B cryocoolers
- F-70 compressors.

30K	80/95 W	
Power (50/60Hz)	7.5/9.0 kW	
Maintenance	expected every 18.000 hrs	
Orientational Dependence	<30%	



- At standstill orientational dependence of cryocooling is detectable
- Rotation leads to homogenization of temperatures






Ground testing at IWES



Steps during ground testing at DyNaLab of IWES in Bremerhaven:

- Mounting hub adaptation and generator
- Rotor cool down
- Excitation of the rotor at standstill
- Rotation
- Short circuit test
- No load test
- Power generation








1st cool down before ground test





Cooling down period faster then calculated 14 days compared to 18 days

Cooling power exceeds expectations

Overall temperature level was lower than anticipated

· Thermal design conservative

Cryostat vacuum better then expected

- 2.7·10⁻¹⁰ bar and self-sustaining
- No pump required during operation


Cryogenic system fulfilled all specifications!




Excitation of HTS field windings



First excitation of HTS field winding at standstill in Bremerhaven



- Debugging of control and QD system
- Optimization of filter constants and threshold values
- Test of shutoff safety chain




Excitation up to 275 A



Some detail findings No load tests



- Stator voltage reached nominal at 260 A rotor current
- The no-load curve does not show any unexpected behavior and is better than the 2D-FEM calculated one.
- With full 3D FEM including end windings no-load curve was fully reproduced.







But not everything went as expected......







Quench of one coil



During further increase of excitation current one coil quenched

- voltage rise detected by QD system
- automatic shut down
- temperature rise in quenched coil of up to 4.5 K





Analysis of quench



Detailed analysis of temperatures and voltages

→ Only one coil with defect already before the quench

After the quench

 \rightarrow higher resistance in quenched coil (1.7 m Ω)

No damage to other coils

→ QD system prevented further damage


Possible reasons:

- Coil only tested in LN2
 → conditions (T, B) differ from final operation conditions
 - → Damaged wire with local I_c drop not detected
- Insulation failure leading to local heating
- Damage of coil after the QC test



Some detail findings Partial power test with defect coil







Repair of the rotor




Repair steps

- Transport of the generator to suitable place (cranes, welding..)
- rotor and stator separated
- vacuum recipient opened by cutting open the welding seam
- coil exchanged
 - MLI, el. + thermal connections, screws...
- Reassemble, re-weld, evacuation

Excitation for operation: 330 A <









But not everything went as expected......



But did we learn something?



Learnings



Positive findings

- QD system worked correctly
- □ Operation with derated excitation (39%) is possible even with a defect HTS coil
- ☐ HTS rotors can be repaired



Improvements in QC

- ☐ QC testing should mimic the operational stress level as good as possible
 - → HTS tape should be tested with similar I/Ic even if at different T and B conditions
- ☐ Insulation (turn to turn, layer to layer, coil to ground) has to be included in QC even if there is very little voltage drop at normal conditions



Commissioning on turbine in Thyborøn, Denmark



Commissioning on the wind turbine:


- Preinstallation of components
- Mounting of generator, converter, water cooling, DAQ, ...
- Connection to PLC of wind turbine
- Safety testing
- Rotor cool down
- Excitation of the rotor
- No load rotation
- Stepwise increase to full power production





2_{nd} cool down on turbine







12 days from 28.9.2018 until 9.10.2018


Power generation and cooling



2 MW test run 255 A excitation




Installed on wind turbine



Experience with cooling system

- Off the shelf components worked as specified
- Rotation of cryocoolers is no problem (15 rpm)
- Conduction cooling is reliable
- Influence of power generation on temperatures is small





Power production



- Stable operation at 2 MW power level in unattended mode
- 2 weeks of continuous operation (remotely monitored)
- Short circuit in the converter system at 3 MW prevented reaching final 3.6 MW
 - Resonance in generator-tower cables-inverter
 conventional technology
 - No problems in the rotor, no doubt that 3.6 MW are possible

In total power was fed into the grid for 650h!

Many Danish households could claim

"powered by superconductivity".

3 MW test run 330 A excitation

Conclusions



- The world's first superconducting generator was successfully built and operated on a wind turbine.
- This in general demonstrates
 - compact and simple use of superconductors,
 - superconductor technology and cryocooling is stable and robust.
- Superconducting generators can be
 - much smaller than present day "state of the art" generator (Ecoswing: 5.4 m → 4 m)
 - much lighter than present day "state of the art" generator (- 50 %)
- The same technology can be applied to other slow rotating machines
 - Motors and generators for ship propulsion
 - Hydro power generators



Thank you!





