




LHCf Status Report




Yoshitaka Itow
Solar-Terrestrial Environment
Laboratory
Nagoya University
for the LHCf collaboration

LHCf: detector overview




Arm#1 Detector
20mmx20mm+40mmx40mm
4 SciFi tracking layers

$44X_0,$
 $1.6 \lambda_{int}$





Arm#2 Detector
25mmx25mm+32mmx32mm
4 Silicon strip tracking layers



Calibrate cosmic ray interactions
for very forward energy spectra
at LHC energy

- Discriminate a good model
- Input data for model building




Model difference in very forward at 14TeV

LHCf 2010 runs

- Successful data taking at 7TeV collisions is ongoing.
 - Integrated Luminosity $\sim 1\text{nb}^{-1}$ before Apr Tech.Stop.
 - $\sim 10\text{M}$ showers and 35K π^0 s obtained (arm1+arm2).
- Detector shows good performance with stable quality.
 - Energy scale calibration with a π^0 peak.
 - Good stability $< \pm 1\%$ level. Yet no radiation problem.

LHCf 7TeV run in Apr2010



Total Stats in Mar30th – Apr 26th 117 hours
(Detector at beam center / Nominal Gain)






	γ -like	had-like	π^0	Livetime(*)
Arm1	1.6e6	2.8e6	10 K	96%
Arm2	2.0e6	4.0e6	25 K	93%

(*) Deadtime mostly due to detector moving into beamline


LHCf observed 7TeV collisions at 0-degree

1 TeV gamma-ray shower @ Arm2


Particle Hit maps





The π^0 peak at 7TeV



- The robust sample
- Good energy calibrator (sys err so far +10% -5%)




Expected mass resolution 5% and 3%



Arm2 event display

Quick look at 7TeV collisions (Arm2)




■ Colliding bunch
■ Non-colliding bunch

High statistics !!
 Only 1.5% of total data are used


Very clean data!!
 BKG due to beam-gas collisions is ~ 1%

Detector gain stability in Apr 2010




Laser gain calibration for scintillator layers

± 1% level stability !



π^0 mass peak



cumulative dose



0.045Gy


FrontCounter as a good luminosity monitor

Stay all the time



Page1
LHCf page



- FC is working very well for luminosity monitoring
- Continuous monitoring w/ independent DAQ now available. See Page1 "LHCf experiment"
- Conversion to "luminosity" from FC rate is now under study by MC



Analysis of 900GeV runs in 2009



- Stable beams at 900GeV, 06.Dec. – 15.Dec (27.7 hours)
 - 2,800 and 3,700 showers in Arm1 and Arm2, for $\sim 5e5$ collisions at IP1
- Progress in Analysis since last LHCC
 - Refine analysis tools and fix final data sets for Dec09 run.
 - Absolute energy calibration by π^0 peak at 7TeV

Expected spectra with each hadron interaction model




Particle Identification

- Clear discrimination between γ and hadron showers based on shower transition curves.
- Basic agreement in the PID parameter (L90) distribution
- Checking systematics for SPS calibration data (50-200GeV for electrons, 150, 350 GeV for protons)




“Very” preliminary spectra from 900GeV runs in 2009

Normalized by gamma-like entry
Gamma-ray like @Arm1



Hadron like @Arm1




- Reasonable agreement with MC
- Conservative systematic error for energy scale +10% -4% assigned
- Checking detector response for hadron showers by SPS 350,150GeV p data

Adding May 900GeV runs, 100K showers now (Dec09 x15) !

Plan for coming months

- Nominal data taking at 7TeV Typical unit 10K π^0 w/ $\sim 1\text{nb}^{-1}$
 - So far collected $\sim 10\text{K}$ π^0 s at beam center.
 - Another $\sim 10\text{k}$ π^0 s will be collected at -10mm below center to cover P_T gap (for arm1 from this May run)
 - Another runs for checking systematics with a few different configuration (HV, trig threshold, etc..)
 - High statistic w/ 1 or 2 settings (for η meson, etc.)
- Possible beam crossing angle run($140\mu\text{rad}$) at 7 TeV
 - Enhance rapidity coverage; $\eta > 8.7 \rightarrow \eta > 8.4$
 - Important to check flux center moving downward w.r.t. crossing angle
- Finally, LHCf de-installation
 - When luminosity reaches too high ($> 10^{31}\text{cm}^{-2}\text{s}^{-1}$, or 2pb^{-1})

Study of η in a high statics sample

 η

Next milestone: η meson


- η/π^0 ratio or η production spectra vary a lot among different interaction models. A good handle to probe the models, though irrelevant to air shower development.
- Another calibration point for more robust energy scale
- Typical $\eta/\pi^0 = 10^{-3} \sim 10^{-4}$ at 7TeV. Good to collect $\sim 1M \pi^0$ ($\sim 100\text{nb}^{-1}$)

Strangeness production (K^0 , Λ) is under study

LHCf removal and toward the phase-2

- When luminosity become too high ($>10^{31}$ cm⁻²s⁻¹, 2 pb⁻¹), LHCf will go out from the TAN (Radiation damage at plastic scintillator ~ 1 kGy @ 2 pb⁻¹ for 20% degradation)
- De-installation work should be quickly done during monthly Technical Stop.
- Probably not earlier than the next Technical Stop in June. We'd like to revisit the scheduling issue when LHC luminosity profile gets clearer in June.
- After removal, beam calibration again by a SPS test beam.
- Revisit LHC at the next energy upgrade. R&D and fabrication of rad-hard GSO scintillator are on-going for the "phase-2" LHCf detector.

A new GSO scintillator layer





Summary

- LHCf has started physics program quite successfully.
 - 6K showers at 900GeV (now getting 6 times more in May !)
 - 10M showers and 35K π^0 at 7TeV
- Detectors working beautifully without any serious trouble.
 - Very clean ! Negligible beam-gas background
 - The π^0 peak demonstrates good performance as expected.
- As luminosity growing up, high stat run and other optional runs to be discussed
 - High stat run for η mesons
 - Crossing angle commission ← important step to “phase-2”
- Rapid progress in analysis. Almost ready to publish physics !
 - 900GeV results and 7TeV results
 - Finalizing SPS test beam data to confirm energy scale, PID and hadron shower response at a few 100 GeV.

Crossing angle for LHCf 7TeV run

Shown in 99th LHCC, Sep2009




With 140 μ rad crossing angle,
neutral flux center is lowered by 2cm.
Rapidity coverage: $>8.7 \rightarrow >8.4$.

- w/o crossing : 30%acc. @ $X_f = 0.22$
- w/o 140 μ rad : 50%acc. @ $X_f = 0.22$


- If possible, it is nice to have a crossing angle during LHCf run.
- LHCf can measure crossing angle by fitting shower center ($\Delta Y \sim 1\text{mm}$ for 100sec @ $L=10^{29} \rightarrow \Delta\alpha \sim 7\mu\text{rad}$) to be distributed by DIP.

Beam gas BG at Dec09 900GeV runs

Hit map of Gamma-rays




Background due to beam-residual gas collision is about 10%




Comparison between tower calorimeter towers of Arm2

Gamma-ray like




Hadron like




Flat spectra
in $\eta > 8.7$
at 900GeV

Comparison between two Arms

Gamma-ray like



Hadron like





Both detectors
working
without any
biases

-Front Counter-

- Thin scintillators with $8 \times 8 \text{ cm}^2$ acceptance, which have been installed in front of each main detector.

Schematic view of
Front counter



- To monitor beam condition.
- For background rejection of beam-residual gas collisions by coincidence analysis