



BNL - FNAL - LBNL - SLAC


LHC Accelerator Research Program Magnet Development

GianLuca Sabbi

for the US LARP collaboration



HE-LHC Workshop, October 14, 2010




LARP Program Goals

Coordinates LHC Accelerator Research in the US:

- Started by DOE in 2003, progression from USLHC construction
- Collaboration of four national Labs: BNL, FNAL, LBNL, SLAC
- Funding level: \$12-13M/year (FY06-FY11)

Goals:


- **Extend and improve the performance of LHC**
 - *Maximize scientific output in support of the experiments*
- **Maintain and develop US Labs capabilities**
 - *Prepare for future projects*
- **Research and training for US accelerator physicists and engineers**
- **Advance US and international collaboration on HEP projects**



LARP

Overview of LARP Activities

Accelerator Systems



Instrumentation

- Luminosity monitor
- Tune tracker, AC dipole
- Schottky monitor


Accelerator Physics

- Electron cloud instability
- Beam-beam studies
- Crab crossing

Collimation

- Rotatable collimators

Magnet Systems



Materials

- Strand characterization
- Cable development

Model Quadrupoles

- Technology Quadrupoles
- High-field Quadrupoles

Long Quadrupoles

- Coil fabrication
- Structure and assembly
- Instrumentation and Test

Program Management

Programmatic Activities

- Toohig Fellowship
- Long Term Visitors




Magnet R&D Program

- Goal: **Develop Nb₃Sn quadrupoles for the LHC luminosity upgrade**
- Potential to operate at higher field and/or larger temperature margin
- Follows Nb₃Sn development and demonstration by CDP & US Labs

LARP is a focused R&D program with specific scope & objectives:

- Application: High Luminosity LHC
 - Timescale: ~2014
 - Budget: ~7M\$/year
 - Magnet type: Large aperture IR Quadrupole
 - Conductor: Nb₃Sn
- Specific focus has been a key element of program success
 - Considerable progress to date, much work is still required



LARP



Nb₃Sn Challenges

Brittleness:


- React coils after winding
- Epoxy impregnation

Strain sensitivity:

- Mechanical design and analysis to prevent degradation under high stress



Material	NbTi	Nb ₃ Sn
Dipole Limit	~ 10 T	~ 17 T
Reaction	Ductile	~ 675°C
Insulation	Polymide	S/E Glass
Coil parts	G-10	Stainless
Axial Strain	N/A	~ 0.3 %
Transverse stress	N/A	~ 200 MPa



Program Components

1. Materials R&D:

- *Strand specification and procurement*
- *Cable fabrication, insulation and qualification*
- *Heat treatment optimization*

Ongoing

2. Technology development with Racetrack Coils:

- *Subscale Quadrupole (SQ)*
- *Long Racetrack (LR)*

Completed

3. Cos 2 θ Quadrupoles with 90 mm aperture:


- *Technology Quadrupole (TQ)*
- *Long Quadrupole (LQ)*

*Completed
~75%*

4. Cos 2 θ Quadrupoles with 120 mm aperture:


- *High-Field Quadrupole (HQ)*
- *Long High-Field Quadrupole (LHQ)*


*~30%
Starting*



LARP






Magnet Development Chart





LARP

Magnet Series





A fully integrated program: HQ example

- Cable design and fabrication LBNL
- Magnetic design & analysis FNAL, LBNL
- Mechanical design & analysis LBNL
- Coil parts design and procurement FNAL
- Instrumentation & quench protection LBNL
- Winding and curing tooling design LBNL, FNAL
- Reaction and potting tooling design BNL
- Coil winding and curing LBNL
- Coil reaction and potting BNL, LBNL
- Coil handling and shipping tooling BNL
- Structures (baseline, revised, mirror) LBNL, BNL, FNAL
- Assembly (baseline, revised, mirror) LBNL, BNL, FNAL
- Magnet test LBNL, CERN, FNAL
- Accelerator Integration BNL, LBNL, FNAL



Magnet Tests in the last 12 months

- Dec. 2009 LQS01a (first Long Quadrupole) - FNAL
- *Achieved target gradient of 200 T/m*
- Dec. 2009 TQS03c (high stress) - CERN
- *88% SSL w/200 MPa average coil stress*
- Feb. 2010 TQS03e (cycling) - CERN
- *No degradation after 1000 cycles*
- May 2010 HQS01a (first High-Field Quadrupole) - LBNL
- *>155 T/m @4.5K, already above NbTi limit @1.9K*
- June 2010 HQS01b (revised coil-structure shims) - LBNL
- *First Quench >150 T/m (78%); insulation failure*
- July 2010 LQS01b (revised coil-structure shims) - FNAL
- *Rapid training to >220 T/m @4.5K; retained at 1.9K*
- Oct. 2010 HQS0c (two new coils) - LBNL
- *Underway – Insulation integrity checks*



Progress on Key Technical Issues (1/5)

Strand design and fabrication:

- + Solid performance from RRP 54/61 in LR, TQ, LQ, HQ models
- + New RRP 108/127 shows improved stability and robustness
- Only one vendor and production cycle is 12 (15) months
- Piece length (esp. 108/127) not yet sufficient for efficient production

Cable design and fabrication:

- + Three cable designs developed (LR, TQ/LQ, HQ)
- + More than 7 km of cable fabricated with minimal losses
- Control of inter-strand resistance not yet incorporated in magnets

Conductor performance:

- + Demonstrated capability of achieve full conductor potential
- + Demonstrated excellent tolerance to high stress levels
- + Stability margins always sufficient to reach performance goals



Progress on Key Technical Issues (2/5)

Quench performance and training:

- + Achieved **high gradient** - TQ: 238 T/m, LQ: 225 T/m, HQ:156 T/m
- + **Fast training** in optimized models (SQ, LR, TQ, LQ, HQ)
- + **Steady progress** through systematic analysis and correction

Magnetic and mechanical design:

- + Complete FEA modeling capabilities and high quality data
Performance issues can be quickly understood and corrected
- + Further optimization underway for integration and production

Stress limits:

- + Satisfactory performance up to **~250 MPa peak, ~200 MPa average**
- + **No degradation in TQ after 1000 cycles**



Progress on Key Technical Issues (3/5)

Coil fabrication technology:

- + Steady improvement in tooling and procedures
- + Distributed coil fabrication shows flexibility, robustness
However: insulation failure in recent HQ test
- + Successful length scale-up in LR and LQ
However: full coil modeling framework is not yet available

Quench protection:

- + Key parameters are well understood
Propagation, detection & heater delays, peak temperatures
- + Steady improvements in modeling and heater fabrication
- Protection is intrinsically challenging
- Quench process in superfluid He may compromise heaters



Progress on Key Technical Issues (4/5)

Alignment and field quality:

- No coil alignment in LR, TQ, LQ models
Neither during fabrication nor at assembly/excitation
- + Coil alignment features introduced in HQ models
Shows good mechanical performance while engaging keys
- Dynamic effects are not yet controlled
Cables with cores will be introduced in HQ models

Accelerator integration:

- + Studies underway to further optimize alignment, field quality, cooling, heat transfer, radiation damage etc.
- Much work left to do in this area

Working with CERN on design requirements and options
Opportunities for collaboration with EuCARD, KEK, CERN etc.



Progress on Key Technical Issues (5/5)

Radiation and thermal management:

- + Thermal margins are intrinsically high compared to NbTi
- Heat transfer is limited due to epoxy impregnation
- Epoxy is also the weak point in terms of radiation damage
- + Field/aperture margin can be effectively used for absorbers


Production issues:

- + Demonstrated distributed production, extensive shipping
- Insulation failures observed in recent HQ tests
Need more focus on reliability vs. performance
- + Insulation options for long cables are under development
- + Timeline from specifications to test is similar to NbTi
- Current infrastructure is limited to 4 m coil length



Next steps: 90 mm Long Quadrupoles

- Fully reproduce performance of the TQ short models
 - Higher gradient (220 T/m in TQS02, 240 T/m in TQS03)
 - Fast training (plateau in 5-10 quenches, no retraining)
- Systematic analysis of coil length effects
 - Detailed modeling of the reaction process
 - Understand/optimize coil strain state after reaction
- Design and process optimization for construction
 - Coil size control/reproducibility
 - Protection heater design, esp. for inner layer
 - One-side loading with 4 m keys/bladders
 - Cable insulation techniques for production



Next steps: 120 mm High Field Quadrupoles

Present focus: address electrical insulation issues in HQ

- Progress on **results analysis and identification of root cause**, other contributing factors and possible solutions
- Near term: enhanced QA and selection of coils
- Long term: design modifications for improved robustness


Short model R&D:

- Performance limits, training, **pre-load optimization**
- **Quench protection and thermal studies**
- **Cored cables** to control dynamic effects
- **Structure optimization** for production and accelerator integration
- **Field quality** characterization and optimization


Scale-up to Long HQ model as a technology demonstrator for HL-LHC



From LARP R&D to HL-LHC Construction



- Assuming technology decision at the end of 2013 and installation in 2012
- 3 years for coil fabrication requires 2 production lines of full length coils
- 64 full length coils required i.e. one new coil completed every ~2 weeks



LARP

LARP R&D relevant to HE-LHC

- IR Quadrupole development
- HE-LHC dipoles will require Nb₃Sn technology
 - *Cabling and insulation of long ULs*
 - *Long coil fabrication, mechanical structures*
 - *Instrumentation and analysis*
 - *Field quality, quench protection*
- From cold mass development to accelerator integration:
 - *Cooling, helium containment, alignment*
- Development of radiation tolerant components
- Capability to organize/integrate R&D effort across Laboratories
- Initial feedback on series production and operation issues:
 - *Infrastructure, production steps/times/cost*
 - *Reliability, failure rates in production/operations*



HE-LHC R&D outside the scope of LARP

- HTS materials development
- HTS (Bi-2212) coil fabrication technology
 - chemical compatibility, reaction process
- Cabling, in particular for YBCO tapes
- High field dipole designs:
 - Small aperture, block geometry
 - Two-in-one layout
- Hybrid Nb₃Sn/HTS coils:
 - internal splices or independent powering
 - nested assembly and mechanical support
- Scale up to dipole length (additional factor of 2-3)
 - Coil fabrication, sagitta, quench protection
- Technology transfer, large scale production



Summary

- A large knowledge base is available after 5 years of fully integrated effort involving three US Labs and CERN
- Demonstrated all fundamental aspects of Nb₃Sn technology:
 - *Steady progress in understanding and addressing R&D issues*
- R&D effort should now focus on increased reliability, accelerator integration and production-oriented processes
 - *Recent HQ insulation failure is a timely reminder*
- HL-LHC is a key step for all future high-field applications
 - *First demonstration represents a significant opportunity and risk*
 - *Strong synergy on technical and production issues*
- Next few years will be critical and much work is still left to do
 - *Integrate effort with CERN, EuCARD, KEK, US Labs*