LHC transverse Damper Observations versus expectations

W. Hofle BE/RF/FB

CERN BE-RF team for ADT

L. Arnaudon, P. Baudrenghien, A. Butterworth, G. Cipolla, F. Dubouchet, D. Glenat, W. Hofle M. Jaussi, G. Hagmann, F. Killing, *G. Kotzian*, R. Louwerse, J. Molendijk, E. Montesinos, J. Noirjean, A. Pashnin, V. Rossi, *M. Schokker*, *D. Valuch*, U.Wehrle, F. Weierud

With participation of JINR, Dubna, E. Gorbachev, V. Zhabitsky et al.


Acknowledgements:

- U. Wienands (SLAC), V. Lebedev (FNAL)
- BE-BI, BE-OP, in particular D. Jacquet, V. Kain

Overview

- □ what we designed for: brief system overview, expectations and limitations
- □ commissioning the damper feedback loop, tune shift
- □ diagnostics with damper signals
- □ hump control and tune measurement
- **G** gain: performance (damping time) at injection and with colliding beams
- □ abort gap cleaning pulse shape
- □ summary and plans for 2011

Transverse Damper / Feedback



need real-time digital signal processing

Match delays: t _{signal} = t _{beam} + MT $_0$

 T_0 : beam revolution time

M=1: very common -> "One -Turn-Delay" feedback But M>1 also possible

phase and delay adjustments


- **damping**: of transverse injection oscillations
- □ feedback: curing transverse coupled bunch instabilities
- excitation: of transverse oscillations, tune meas. / abort gap cleaning ...

High expectations, facing the unknown

- injection damping requires strong kicks, 2 μrad @450 GeV/c, 900 kV
- LHC design report call for damping time of 4.1 ms (46 turns)
- **D** plan: use damper during injection plateau and ramp, switch off during collisions
- during the design stage worried that due to noise damper could not be used
- **2010** run showed that we can use damper with colliding beams
- efforts put into designing electronics and software paid off
- □ thorough testing, power system running reliably since first commissioning in 2008
- mitigation of 2009 interference (8 kHz) !

The LHC Transverse Damping System high power part

Naming: #1 to #16 (power team), H1, H2, H3, H4, V1, V2, V3, V4 .B1/B2




Module share common resources, power converters, LL

ADT amplifiers in tunnel point 4 RB44 and RB46


Overview of signal processing

intensity nomalised bunch position digitised and synchronised (two pick-ups)



Limitation


roll-off of kick strength and gain towards 20 MHz (7% at 20 MHz)



10 20 bin number 80 MHz 30

40

-0.6




phase response compensated by a digital filter adapting required gain to bunch spacing needs some tuning for 2011 → prepare set of filters for different bunch spacings

25 ns: 20 MHz, 50 ns: 10 MHz, 75 ns: 6.7 MHz

Limitation: ADT and bunch spacing


issue: full kick strength only available for frequencies up to 1 MHz

 \rightarrow need to play some "tricks"



Example: 150 ns peak hold scheme

150 ns peak hold



less gain when operated with isolated bunches (used first in fill 1305)

150 ns bunch trains

less gain for bunches at edge of batch but similar , i.e. full gain for center of batch [assuming common error of batch] later adapted this to 75 ns and 50 ns spacing

2011: preparation of settings for different bunch spacings

First Damping of Injection errors

Pickup Q7

Pickup Q9

damper off

x 10⁴

1.5

0.5 0 -0.5 -1 -1.5

-2

-2.5 L 0

2000

3000

1000

5000

4000


Turn

7000


6000

8000

9000




damper on




Surpassing Design Specifications

High gain

Lower gain



40 turns damping achieved




Vector sum versus FIR phase shifters

- currently a 7-tap FIR filter is used to adjust the feedback phase
 - \rightarrow introduces 3 turns additional (group) delay in processing;
 - together with 1-turn delay and notch: 4.5 turns delay
 - \rightarrow phase error from tune change \rightarrow 4.5 x 2 π x Δ Q
 - disadvantage: FB only works within a relatively narrow tune range, +/- $\pi/4$ for +/- 0.028
 - advantage: processing gain (both pick-ups used with full amplitude, good for S/N) easier to set-up (both pick-ups can work independently)
- vector sum: three times less sensitive to tune variations disadvantage: loss of S/N


2011: keep FIR, but maybe test vector sum and evaluate S/N

Tune shift



estimate that phase adjustment overall better than 30 degrees improvement possible in 2011 using tune shift method

Tune shift versus phase setting




17

Diagnostics: the fixed display

Damper off


Beam 1: Transverse injection transient, pilot, Thursday, 10.06.2010, 13:12



Diagnostics: the fixed display

Damper off


Beam 1: Transverse injection transient, pilot, Thursday, 10.06.2010, 13:12



W. Hofle, ADT @ Evain

Offline analysis

C:\ADT_11MAR10\Rpos_damper_off




fit: Q'=5.5, μ = 0.6x10⁻⁴, Δ x= 0.5 σ , Q_H=0.28, Q_S=5.6x10⁻³, no damper

Can this be made a tool for chromaticity estimation (from pilot injection) ? Needs ppm change of damper settings from pilot to nominal, plus some programming


Damper off

Damping with ions, 1st injection



Less than 20 turns damping

Damping with ions, last injection



Less than 20 turns damping

Reducing effect of external perturbations using the transverse feedback "hump control"

assuming hump is an external perturbation (not an instability) \rightarrow a high gain is required in the feedback to reduce effects on the beam

for off-tune perturbation using the PU vector sum should be more efficient, but lower S/N but closed loop transfer function for the noise suppression contains BTF !


on the other hand, if hump is off-tune its effect on the beam emittance is probably small, while contribution at the tune frequency (if any) is cured by feedback

 \rightarrow performance improvements for S/N will help and permit tests with vector sum!


Tune measurement options

BBQ	\rightarrow	relies on residual oscillations on the beam that are not controlled
Schottky	\rightarrow	relies on residual oscillations
BBQ + excitation	\rightarrow	with damper quite strong excitation necessary (blow-up ?)
PLL + damper	÷	cleaner spectrum with FB on, blow-up to be checked calibration of PLL depends on damper settings
stop band	\rightarrow	should be equivalent to higher noise in damper hence more blow-up, do this on witness bunch?
tune from FB	\rightarrow	we are checking the feasibility, 10 ⁻³ accuracy seems possible, long lead time for development

What we should see on damper (feedback on)




Damper signals measured




best method of averaging the spectra needs to be studied dip less pronounced at nominal intensity

Measurements of September 5, 2010 (beam 1 horizontal as function of damper gain)




ightarrow should get same in one shot from 999 bunches, but streaming the data is an issue



450 GeV: What was the gain / damping time ?

Injection damping fill 1268 (August 9, 2010)



data logged since summer, but no automatic tool to compute damping time / inj. error

3.5 TeV: Kicking non colliding bunch with damper on (20 August 2010)





Figure 1.2: Envelope fit example for Beam 1, Q7 data, -19 dB gain setting.

U. Wienands


used Qkicker and synchronised observation with damper

Damping time versus gain at 3.5 TeV



U. Wienands


Damping time versus gain at 3.5 TeV



 \rightarrow suggests practically no or very little damping at zero gain


Principle of Abort Gap Cleaning

resonant excitation of transverse oscillations capture of beam by aperture limit (collimators)




LHC nominal bunch pattern 2808 bunches

amplitude modulated at frequency close to betatron tune (covers a range of tunes in steps)



cleaning pulse (gate) centered in abort gap modulation of pulse with betatron frequency full amplitude up to ~ 1 MHz possible

Abort Gap Cleaning Pulse



Summary of 2010

✓ commissioned damper at 450 GeV, during ramp and with colliding beams

- ✓ nominal damping rate reached and surpased
- \checkmark commissioned operation with bunch train
- ✓ commissioned damper for ions at 450 GeV and with colliding ion beams
- ✓ abort gap cleaning and injection slot cleaning successfully used
- ✓ diagnostics (logging, fixed display, multi-bunch acquisition) available
- (in)compatibility with tune measurement somewhat surprised

Plan for 2011

- "ppm" loading of settings for different operation mode (trains, intensity)
- improving filters, best frequency response for given bunch spacing
- fine adjustment of phase and delay
- vector sum ?
- program gain via a normalised function (scale with energy), in physical unit τ
- improve multi-bunch acquisition (more than 8 bunches)
- post mortem logging (?!)
- move to standard operation the beam cleaning (abort gap / injection slot)
- improvements in abort gap cleaning pulse shape, investigate
- commission damper in squeeze
- study noise and propose improvements (2012 more pick-ups, Q8, Q10 ??)
- work on compatibility with tune feedback (witness bunches ?)
- study feasibility of tune determination from residual FB signal