

# The Low-Power SPL (LPSPL)

Frank Gerigk

Beam'07, 1-5 October 2007

# Outline

- ✦ requirements & basic parameters,
- ✦ linac layout,
- ✦ RF system & cryo-modules,
- ✦ civil engineering,
- ✦ outlook.

# Motivation

upgrade of the LHC proton injector chain:

- ✦ remove reliability concerns in the chain,
- ✦ provide a beam suitable for all foreseen LHC upgrade scenarios,

provide an injector that can be upgraded to supply protons for:

- ✦ neutrino physics,
  - ✦ Eurisol/ISOLDE upgrades,
  - ✦ performance improvement for SPS fixed target physics,
- ➔ see R. Garoby (Tuesday, 9:00 this workshop)

# Baseline parameters

## **low-power** operation (LPSPL): injection into PS2

- ✦  $1.5 \times 10^{14}$  particles per pulse ( $H^-$ ), 1 Hz (design for 2 Hz),
- ✦ 4 GeV, 0.2 MW
- ✦ 1.2 ms pulse length for 20 mA average pulse current.

## **high-power** operation (SPL): PS2 plus high-power

- ✦  $> 1.0 \times 10^{14}$  particles per pulse ( $H^-$ ), 50 Hz,
- ✦ 5 GeV, 4 MW,
- ✦ 0.4 ms pulse length for 40 mA average current.

# SPL machine layout

- Linac4 will inject at 160 MeV into the PSB,
- during construction and commissioning of the LPSPL, Linac4 will continue as PSB injector and provide beam to commission SPL/PS2,
- when PS2 is running, the “switching” area will be replaced with a 160-180 MeV normal conducting linac.

## Linac4 (160 MeV)

## SC-linac (4/5 GeV)




# main parameters

| SPL type                                 | full-power | low-power |
|--|------------|-----------|
| E [GeV]                                  | 5.0        | 4.0       |
| $P_{\text{beam}}$ [MW]                   | >4         | 0.192     |
| $f_{\text{rep}}$ [Hz]                    | 50         | 2         |
| $I_{\text{average}}$ [mA]                | 40         | 20        |
| $t_{\text{pulse}}$ [ms]                  | 0.4        | 1.2       |
| $n_{\text{protons/pulse}}$ [ $10^{14}$ ] | 1.0        | 1.5       |
| Max. filling time PS2 [ms]               | 0.6        | 1.2       |
| $n_{\text{klystron}}$ (Linac4 + SPL)     | 19+53      | 19+24     |
| $n_{\text{SC cavities}}$                 | 234        | 194       |
| inst. $P_{\text{RF(peak)}}$ [MW]         | 220        | 100       |
| $P_{\text{facility}}$ [MW]               | 38.5       | 4.5       |
| $P_{\text{cryo, electric}}$ [MW]         | 4.5        | 1.5       |
| $T_{\text{cryo}}$ [K]                    | 2          | 2         |
| length [m]                               | 534        | 459       |

# SC cavities

## peak surface fields (electric)




- ✦ max. surface fields are based on measured cavity performance,
- ✦ surface fields: 50 MV/m and 100 mT are challenging but seem realistic for pulsed operation,
- ✦ **chosen gradients: 19/25 MV/m for  $\beta=0.65/1$**

P. Pierini, INFN

# SC cavities

## peak surface fields (magnetic)




- ✦ max. surface fields are based on measured cavity performance,
- ✦ surface fields: 50 MV/m and 100 mT are challenging but seem realistic for pulsed operation,
- ✦ **chosen gradients:**  
**19/25 MV/m**  
for  $\beta=0.65/1$

P. Pierini, INFN

# Basic $\beta=0.65$ cryo-module

doublet focusing, 2 periods per module



Beam dynamics incl. error studies and steering: R. Duperrier, D. Uriot, CEA

# Basic $\beta=1$ cryo-module


doublet focusing, 1 period per module



Beam dynamics incl. error studies and steering: R. Duperrier, D. Uriot, CEA

# SPL cryo-module

principle: start from the TESLA/ILC design...



- ❖ long modules with a low number of cold/warm transitions and low static losses,
- ❖ cold quadrupoles,
- ❖ high packing factor,
- ❖ requires high reliability of all components and several years of R&D!

# SPL cryo-module & RF system

## in preparation for a viable design we need to:

- design and construct a full-scale cryo-module (adapting the TESLA/ILC approach to 704 MHz),
- test cavities in the cryo-module at full power and full duty cycle (LPSPL & SPL),
- test the complete RF system (5 MW pulsed klystron @ 704 MHz, RF splitting: up to 16 cavities powered by one klystron!),
- test high-power phase shifters, control system, cavity tuning, etc.
- collaboration with DESY/INFN/CEA/IN2P3 mandatory!


# SPL cryo-module & RF system

## in preparation for a viable design we need to:

- design and construct a full-scale cryo-module (adapting the TESLA/ILC approach to 704 MHz),
- test cavities in the cryo-module at full power and full duty cycle (LPSPL & SPL),
- test the complete RF system (5 MW pulsed klystron @ 704 MHz, RF splitting: up to 16 cavities powered by one klystron!),
- test high-power phase shifters, control system, cavity tuning, etc.
- collaboration with DESY/INFN/CEA/IN2P3 mandatory!

bids for funding of cryo-module development and RF test stand (FP7, etc) are in preparation.


# Site layout SPL




# Installation LPSPL/SPL

- All underground installations like: tunnels, water pipes, cryogenic lines, cryostats, electricity supplies are designed for the multi-megawatt SPL,
- For the LPSPL ~half the number of klystrons/power supplies is installed, services (*cryo-plant, cooling towers, electrical substations*) and surface buildings are designed for low duty cycle & lower current, space foreseen for full-power SPL,
- ➔ e.g: for the LPSPL the complete power supplies fit into the klystron tunnel, for the full SPL half of the equipment is above ground,
- For the full SPL the installations and services need to be upgraded/replaced.

# Preliminary tunnel layout



# Preliminary tunnel layout



klystron tunnel  
(diameter: 6 m)

accelerator tunnel  
(diameter: 4.5 m)

# staged transition from LPSPL to SPL

## phase 1: upgrade from 2 to 50 Hz

- ✦ 20 mA, 4 GeV, 1.6 MW,
- ✦ provide:
  - ✦ PS2: 1 Hz, 1.2 ms
  - ✦ high-power: 50 Hz, 0.4 ms,
- ➔ replace all klystron modulators and power supplies (including Linac4),
- ➔ new infrastructure for electricity, water, cryogenics,
- ➔ new surface buildings.

# staged transition from LPSPL to SPL

## phase 2: upgrade from 20 to 40 mA, 4 to 5 GeV

- ✦ 40 mA, 5 GeV, 50 Hz, 4 MW,
- ✦ provide:
  - ✦ PS2: 1 Hz, 1.2 ms,
  - ✦ high power: 50 Hz, 0.4 ms,
- ➔ install 8 additional cryo-modules,
- ➔ double the number of klystrons & power supplies in the SC part,

# what we have done so far

- 2006 SPL conceptual design report remains valid (CERN-AB-2006-081, now different energy and a preliminary stage),
- Linac4 is approved,
- a cost & performance comparison of LPSPL and an RCS was published in May'07 (CERN-AB-2007-014-PAF),
- the LPSPL is now the baseline scenario for LHC proton injector upgrade,
- established a CERN working group for SPL high-power RF tests (cryogenics, RF, power, ...),
- first tunnel integration exercise is completed,
- consistent layout for a completely new proton injector chain is found (Linac4, SPL, PS2),

# what comes next...

- ✦ finalise the siting exercise: feasibility study and civil engineering cost estimate for the end of 2007,
- ✦ FP7 bid for the construction of a full cryo-module with 2 cavities (+ 6 dummies?) in collaboration with CEA, INFN (?), DESY, IN2P3,
- ✦ FP7 bid for a high-power RF test stand at CERN, making use of the existing infrastructure in SM18 and equipping it for 704 MHz (5 MW klystron, RF distribution, modulator, etc),
- ✦ ... *and of course*: high-duty cycle H- source, SC quadrupoles, detailed beam dynamics, radiation protection, etc
- ✦ elaborate a technical design report including costs for a project decision in 2011/12.