

Thoughts of the assembly process

8 February 2021

Tsunayuki Matsubara

Thoughts of assembly process

What we would like to investigate with the assembly process:

- **Efficient works** (e.g. Preparations, Space arrangement, Worker's manual, Work timeline)
- **Safety** (Risk analysis, Countermeasure, Documentation to the facility)
- **Person power** (On-site manager, Expertise, Part time by JPN contractors?)
- **Support by the facility** (Shipment, Storage, Contractor's work)
- **Detector checks in each stage** (QC, QA, Commissioning)
- **Interference with other works in the NA/NM buildings**

Ref.) Questions about contractor's work

(from Tsukamoto-san)

(4) sFGD Truck unloading

- I think the wooden box is supposed to be disassembled after unloading.
- Is the platform assembling supposed to be asked to a contractor ?

(5) sFGD installation


- "Crane is also necessary to lower the front-end electronics crates for two sides. " --> Does this mean that front-end electronics lowering is supposed to be asked to a contractor ?

(6) general requests


Shall I ask you for cartoons/slides/pictures which can help/show us to understand/know some details which cannot be explained by texts only ?

Ref.) Integration timeline

We still do not know the reasonable timeline for the integration



- ① Cube + box assembly (Most urgent)
- ② Fiber/MPPC/Calib. system to the box
- ③ Electronics cables / crates to the box
- ④ Detector box installation to the basket



① Cube + box assembly

It's just my initial thoughts

—	Shipment / storage
—	Heavy equipment
—	Assembly work
—	Detector check

-- 2021.11? ~ 2022.1? -----

- Preparation for the cube+box assembly

- (Receipt) Unloading of the platform, Assembly stand, Transport box, Box parts (Forklift)
- Preparation of lifting structure? (Crane?)
- Preparation of tools like tyvek, screws, lightning, anti-dust cover, helmets, gloves, etc...?
- Platform assembly (Crane?)
- Assembly stand assembly
- Workbench assembly
- Arrangement of space (Crane & Forklift?)
- (Receipt) Unloading of the first 3 plates (Forklift?)
- Box 3 plates assembly
- (Receipt) Unloading of the last 3 plates (Forklift?)

Seismic point is the main issue left for the decision of assembly place. (CERN or Japan)
→ the most urgent issue

- Cube+box assembly --> Procedure to be clarified

- Layer-by-layer assembly with the platform movement
- (QC/QA) Take pictures from top and two sides to check quality later if necessary
- (QC/QA) Height measurement to check the hole alignment if useful
- (QC/QA) Box closure test during the assembly work before the last 3 plates delivery?
- Box closure of side plates
- Soft form layer installation
- Box closure of top plate (Crane?)
- Bracket attachment
- Clean-up of the unnecessary materials. Disposal or storage (Forklift?)

② Fiber / MPPC / Calib. system to the box

It's just my initial thoughts

-- 2022.2? ~ 2022.5? -----

—	Shipment / storage
—	Heavy equipment
—	Assembly work
—	Detector check

- Preparation for the next step

- (Receipt) Loading of another assembly stand (Forklift)
- Box fixation to the new assembly stand (Crane)
- (QC/QA) Box deformation measurement?
- Arrangement of space (Crane, Forklift or Chill roller?)
- (Receipt) Loading fiber containers, MPP64-PCBs and calibration modules.
- Preparation of tools like screws, screw drivers, helmet, gloves, black sheets, etc...
- Preparation of the quick QC system
- Preparation of the safety equipment to work under the box

- Integration of the fiber, MPPC64-PCBs & calib. modules [2]

--> Procedure to be clarified

- Fiber insertion with softform, removing fishing lines and metal rods.
- Fiber cut after the insertion
- (QC/QA) Quick QC of fiber during the insertion work with dedicated setup
- Insertion of the alignment pins for the MPPC64-PCB
- MPPC64-PCB attachment for the area where the QC is performed
- (QC/QA) Serial numbers should be managed to keep tracking.
- (QC/QA) Quick QC for all fibers & MPPC64-PCBs after mounting all channels
- Calibration system attachment
- (QC/QA) Test of calibration module after the attachment
- Light tightness
- (QC/QA) Quick check of the light tightness
- Cabling of the calibration system
- Clean-up of the unnecessary materials. Disposal or storage. (Forklift?)

③ Electronics cables / crates to the box

It's just my initial thoughts

—	Shipment / storage
—	Heavy equipment
—	Assembly work
—	Detector check

-- 2022.6? ~ 2022.7? -----

- Preparation for the next step

- (Receipt) Loading two sets of integrated crates elec. modules, cables and so on (Forklift?)
- (QC/QA) Evaluation test of FEBs at J-PARC before mounting on surface
- Preparation of the commissioning like DAQ PCs

- Integration of Electronics cabling crate mounting [3] --> Procedure to be clarified

- Cabling on the box surface up to the MIB
- Mounting of two sets of the integrated crates to the assembly stand (Crane?)
- Cable slack management
- Installation of Backend, FEB, Voltage module
- (Cooling pipe connection is not necessary?)
- DAQ connection for the commissioning on surface
- (QC/QA) Commissioning for all channels with the LED calibration system
- (QC/QA) Commissioning with cosmics. External trigger? Self trigger?
- Detaching of the crate and temporal cable bundling for installation (Crane?)
- Clean-up of the unnecessary materials. Disposal or storage. (Forklift?)

④ Detector box installation to the basket

It's just my initial thoughts

—	Shipment / storage
—	Heavy equipment
—	Assembly work
—	Detector check

-- 2022.8? ~ 2022.9? -----

- Preparation

- (Receipt) Unloading of the lifter?, guide rail, cooling pipe, cables, etc...
- (QC/QA) Measurement of the modified basket? Should be done in advance if possible
- Setting guide rail to the basket if necessary?
- Consultation with contactor for the installation work
- Q. How about the work at the SS floor?

- Installation [4] --> Procedure to be clarified

- Transport on the surface with the stand (Crane truck or Chill roller? (Less vibration?))
- Detaching from the stand and down to the pit (Crane at NM building)
- Fixing the box to the basket
- Hoist ring removal?
- (QC/QA) Measurement of the envelope after the installation for a record (sim. input?)
- Installation of the electronics crate to the basket
- Cooling pipe connections
- Various cable connections
- (QC/QA) Commissioning for all channels with the LED calibration system
- (QC/QA) Commissioning with cosmics. External trigger? Self trigger?
- Repair work if necessary? (Crane, Crane truck or Chill roller?)
- Clean-up of the unnecessary materials. Disposal or storage (Forklift?)