



Specific Case : Crab-cavities

Alignment review 2019

Vivien RUDE

2019-08-26

Context

- **Assembly measurements of the DQW prototype**
 - Measurement on the associated infrastructures
 - Workflow (Assembly of the Crab-cavities)
 - Installation of FSI system
 - Validation at warm and cold conditions
 - Installation of the DQW prototype in SPS tunnel
- **Extrapolate to the next Crab-cavities**
 - Extrapolate to the RFD prototype
 - Extrapolate to the 10 Crab-cavities assembled through in kind contribution (from UK and Canada)

Objective of this presentation:

To give you an idea review of the different steps activities for the assembly measurements of the DQW prototype.


→ *Review of the activities linked with crab-cavities in the chronological order*

Outline

- **Assembly measurements of the DQW prototype**
 - Measurement on the associated infrastructures
 - Workflow (Assembly of the Crab-cavities)
 - Installation of FSI system
 - Validation at warm and cold conditions
 - Installation of the DQW prototype in SPS tunnel
- **Extrapolate to the next Crab-cavities**
 - Extrapolate to the RFD prototype
 - Extrapolate to the 10 Crab-cavities assembled through in kind contribution (from UK and Canada)

Measurement on the associated infrastructures

- Trolley
- Gantry crane



Measurement on the associated infrastructures

- Trolley
- Gantry crane

ISO 5

Vanne 1

Cav.1

Cav.2

Vanne 2

Trolley



ISO 4





Objective :
Path of the component (Trajectory) :
< 0.1 mm for 1 m of displacement

Measurement on the associated infrastructures

- Trolley
- Gantry crane


Objective :
Path of the component (Trajectory) :
< 0.1 mm for 1 m of displacement



Measurement on the associated infrastructures

- Trolley
- Gantry crane

Objective :
Path of the crane (Trajectory) :
< 1 mm for 1 m of displacement



Measurement on the associated infrastructures

- Trolley
- Gantry crane





Objective :
Path of the crane (Trajectory) :
< 1 mm for 1 m of displacement

Outline

- **Assembly measurements of the DQW prototype**
 - Measurement on the associated infrastructures
 - **Workflow (Assembly of the Crab-cavities)**
 - Installation of FSI system
 - Validation at warm and cold conditions
 - Installation of the DQW prototype in SPS tunnel
- **Extrapolate to the next Crab-cavities**
 - Extrapolate to the RFD prototype
 - Extrapolate to the 10 Crab-cavities assembled through in kind contribution (from UK and Canada)



Workflow (Assembly of the Crab-cavities)

- Determination of the mechanical axis → Capacitive plate of the cavities
- Fiducialisation of the Dressed Cavities
- String line assembly in clean room
- Installation of the others components on the string line
- Final alignment of the string line
- Installation of the top plate (supporting plate of the string line)
- Insertion of string line in the cryomodule



Workflow (Assembly of the Crab-cavities)



- Determination of the mechanical axis → Capacitive plate of the cavities
- Fiducialisation of the Dressed Cavities
- String line assembly in clean room
- Installation of the others components on the string line
- Final alignment of the string line
- Installation of the top plate (supporting plate of the string line)
- Insertion of string line in the cryomodule



Metrology step	Cavity 1	Cavity 2
Before treatment	-0.691	-0.291
After treatment	-0.673	No metrology
After tuning	-0.661	-0.165
Capacitive plate : Pins check	-0.553	No metrology
After tank welding	-0.557	-0.040

Workflow (Assembly of the Crab-cavities)

- Determination of the mechanical axis → Capacitive plate of the cavities
- **Fiducialisation of the Dressed Cavities**
- String line assembly in clean room
- Installation of the others components on the string line
- Final alignment of the string line
- Installation of the top plate (supporting plate of the string line)
- Insertion of string line in the cryomodule




3D measurement of :

- Mechanical axis
- Position of FPC, Coupler, Tuner, ...
- FSI targets
- BCAM targets
- Laser Tracker targets

Workflow (Assembly of the Crab-cavities)

- Determination of the mechanical axis → Capacitive plate of the cavities
- Fiducialisation of the Dressed Cavities
- **String line assembly in clean room**
- Installation of the others components on the string line
- Final alignment of the string line
- Installation of the top plate (supporting plate of the string line)
- Insertion of string line in the cryomodule

Vertical displacement between :
Without vacuum and under vacuum




Objective / Results :

- Alignment before the assembly : < 0.1 mm (regression line)
- Control the alignment after the assembly : < 0.2 mm (regression line)
- Impact of vacuum on the string line : < 0.1 mm




Workflow (Assembly of the Crab-cavities)

- Determination of the mechanical axis → Capacitive plate of the cavities
- Fiducialisation of the Dressed Cavities
- String line assembly in clean room
- **Installation of the others components on the string line**
- Final alignment of the string line
- Installation of the top plate (supporting plate of the string line)
- Insertion of string line in the cryomodule



Objective / Results :

- Cryogenic line : at 1 mm
- Oblong bellows plate : at 1 mm
- ...





Workflow (Assembly of the Crab-cavities)

- Determination of the mechanical axis → Capacitive plate of the cavities
- Fiducialisation of the Dressed Cavities
- String line assembly in clean room
- Installation of the others components on the string line
- **Final alignment of the string line**
- Installation of the top plate (supporting plate of the string line)
- Insertion of string line in the cryomodule

Objective / Results :

- Alignment : < 0.1 mm






Workflow (Assembly of the Crab-cavities)

- Determination of the mechanical axis → Capacitive plate of the cavities
- Fiducialisation of the Dressed Cavities
- String line assembly in clean room
- Installation of the others components on the string line
- Final alignment of the string line
- **Installation of the top plate (supporting plate of the string line)**
- Insertion of string line in the cryomodule


Objective / Results :

- Installation of the top plate : at 0.2 mm
- Installation of the string line : at 0.2 mm
- Taking into account the trajectory of the gantry crane



Workflow (Assembly of the Crab-cavities)

- Determination of the mechanical axis → Capacitive plate of the cavities
- Fiducialisation of the Dressed Cavities
- String line assembly in clean room
- Installation of the others components on the string line
- Final alignment of the string line
- **Installation of the top plate (supporting plate of the string line)**
- Insertion of string line in the cryomodule




Workflow (Assembly of the Crab-cavities)

- Determination of the mechanical axis → Capacitive plate of the cavities
- Fiducialisation of the Dressed Cavities
- String line assembly in clean room
- Installation of the others components on the string line
- Final alignment of the string line
- Installation of the top plate (supporting plate of the string line)
- **Insertion of string line in the cryomodule**

Objective / Results :

- Installation of the cryomodule: at 0.2 mm
- Taking into account the trajectory of the gantry crane



Outline



- **Assembly measurements of the DQW prototype**
 - Measurement on the associated infrastructures
 - Workflow (Assembly of the Crab-cavities)
 - **Installation of FSI system**
 - Validation at warm and cold conditions
 - Installation of the DQW prototype in SPS tunnel
- **Extrapolate to the next Crab-cavities**
 - Extrapolate to the RFD prototype
 - Extrapolate to the 10 Crab-cavities assembled through in kind contribution (from UK and Canada)

Installation of FSI system

- Calibration of FSI feedthrough
- Installation of FSI feedthrough on the cryomodule
- Installation of FSI targets

Objective / Results :

- Calibration : < 0.01 mm



[C-Ki] : Measured distance with FSI

$$\begin{pmatrix} X_{K_i} \\ Y_{K_i} \\ Z_{K_i} \end{pmatrix} = \begin{pmatrix} X_C \\ Y_C \\ Z_C \end{pmatrix} + \begin{pmatrix} U_X \\ U_Y \\ U_Z \end{pmatrix} * Dist_i$$

Installation of FSI system

- Calibration of FSI feedthrough
- **Installation of FSI feedthrough on the cryomodule**
- Installation of FSI targets



Objective / Results :


- Accuracy : < 0.02 mm

3D measurement of :

- Cryomodule
- FSI feedthrough

Installation of FSI system

- Calibration of FSI feedthrough
- Installation of FSI feedthrough on the cryomodule
- **Installation of FSI targets**



Objective / Results :

- Accuracy : < 0.02 mm

3D measurement of :

- Dressed cavities
- FSI targets

Outline




- **Assembly measurements of the DQW prototype**
 - Measurement on the associated infrastructures
 - Workflow (Assembly of the Crab-cavities)
 - Installation of FSI system
 - **Validation at warm and cold conditions**
 - Installation of the DQW prototype in SPS tunnel
- **Extrapolate to the next Crab-cavities**
 - Extrapolate to the RFD prototype
 - Extrapolate to the 10 Crab-cavities assembled through in kind contribution (from UK and Canada)

Validation at warm and cold conditions

- Installation of an alternative monitoring system (BCAM system) → For Cross-checking measurement
- Validation at warm
- Impact of vacuum on the string line
- Impact of transport on the string line
- Validation at cold condition

Objective / Results :


- 3D measurement of the supporting plate for the BCAM : < 0.02 mm
- Installation of the supporting plate on the cryomodule : < 0.02 mm
- Installation of BCAM targets
- Installation of BCAM window





Validation at warm and cold conditions

- Installation of an alternative monitoring system (BCAM system) → For Cross-checking measurement
- Validation at warm**
- Impact of vacuum on the string line
- Impact of transport on the string line
- Validation at cold condition

Objective / Results :
• Intercomparison : < 0.05 mm



Radial position (relatif with respected to AT401 measurement)




Validation at warm and cold conditions

- Installation of an alternative monitoring system (BCAM system) → For Cross-checking measurement
- Validation at warm
- **Impact of vacuum on the string line**
- Impact of transport on the string line
- Validation at cold condition

Objective / Results :

- Impact of vacuum on the jumper : up to 0.3 mm
- Impact of vacuum on the Cryomodule : up to 0.7 mm
- Impact of vacuum on the Couplers : up to 0.2 mm
- Impact of vacuum on the dressed cavities : up to 0.2 mm



Validation at warm and cold conditions


- Installation of an alternative monitoring system (BCAM system)
- Validation at warm
- Impact of vacuum on the string line
- Impact of transport on the string line**
- Validation at cold condition

Objective / Results :


- Impact of transport : $< 0.05 \text{ mm}$



BEFORE TRANSPORT



AFTER TRANSPORT




— Nominal position (300K)
 - - - Nominal position (2K)
 — determined with FSI measurements
 — determined with BCAM measurements

Validation at warm and cold conditions

- Installation of an alternative monitoring system (BCAM system)
- Validation at warm
- Impact of vacuum on the string line
- Impact of transport on the string line
- Validation at cold condition**

Objective / Results :
• Intercomparison : < 0.05 mm

— Nominal position (300K)
- - - Nominal position (2K)
— determined with FSI measurements
— determined with BCAM measurements



Outline

- **Assembly measurements of the DQW prototype**
 - Measurement on the associated infrastructures
 - Workflow (Assembly of the Crab-cavities)
 - Installation of FSI system
 - Validation at warm and cold conditions
 - **Installation of the DQW prototype in SPS tunnel**
- **Extrapolate to the next Crab-cavities**
 - Extrapolate to the RFD prototype
 - Extrapolate to the 10 Crab-cavities assembled through in kind contribution (from UK and Canada)


Installation of the DQW prototype in SPS tunnel

- Definition and determination of a local network
- Implantation and marking
- Validation and installation of the SPS tunnel table
- Installation of cryomodule
- Long term follow up (using FSI measurement)

Objective / Results :


- Accuracy : < 0.15 mm

Synoptic of network points



Legend

	Quadrupole		Reference network points (wall 1)
	Quadrupole axis (In and Out)		Reference network points (wall 2)
	Quadrupole fiducials		Reference network points (floor)
	Crab-Cavities area		Reference network points (ceilling)




Installation of the DQW prototype in SPS tunnel

- Definition and determination of a local network
- **Implantation and marking**
- Validation and installation of the SPS tunnel table
- Installation of cryomodule
- Long term follow up (using FSI measurement)

Objective / Results :

- Accuracy : few mm




Installation of the DQW prototype in SPS tunnel

- Definition and determination of a local network
- Implantation and marking
- **Validation and installation of the SPS tunnel table**
- Installation of cryomodule
- Long term follow up (using FSI measurement)

Objective / Results :

- Installation of SPS tunnel table : few mm




Installation of the DQW prototype in SPS tunnel

- Definition and determination of a local network
- Implantation and marking
- Validation and installation of the SPS tunnel table
- **Installation of cryomodule**
- Long term follow up (using FSI measurement)

Objective / Results :

- Installation of cryomodule w.r.t. the nominal position : < 0.1 mm




Installation of the DQW prototype in SPS tunnel

- Definition and determination of a local network
- Implantation and marking
- Validation and installation of the SPS tunnel table
- Installation of cryomodule
- **Long term follow up (using FSI measurement)**

Objective / Results :

- Repeatability: < 0.02 mm



Outline

- Assembly measurements of the DQW prototype
 - Measurement on the associated infrastructures
 - Workflow (Assembly of the Crab-cavities)
 - Installation of FSI system
 - Validation at warm and cold conditions
 - Installation of the DQW prototype in SPS tunnel

 - **Extrapolate to the next Crab-cavities**
 - Extrapolate to the RFD prototype
 - Extrapolate to the 10 Crab-cavities assembled through in kind contribution (from UK and Canada)
-
- **For the assembly of the RFD prototype and the 10 series, the same assembly steps will have to be followed**
 - **In the LHC, no installation of translation table is foreseen**
 - **All measurements were documented.**
 - **Procedures for transfer knowledge are under preparation and we will assist the collaborators for the keys steps**

Thank you
for your attention