

MICE RF Coupling Coil Magnets Update

Derun Li

Center for Beam Physics

Lawrence Berkeley National Laboratory

October 6, 2010

Sofia, Bulgaria

Acknowledgements

LBL , HIT MICE team members

In particular

SINAP MICE team members

Lixin YIN, Li WANG, Yun CAO and Sen SUN

**Most of the work in this presentation
are from them**

Summary

- Overview of the MICE CC fabrication plan
 - Organization and responsibilities
- Coil winding status at Qi Huan Corp.
 - 1st MuCool coil winding ~ 50% finished
- MICE CC Cryostat design review at SINAP (Shanghai Institute of Applied Physics)
 - Held at SINAP, October 13-14, 2010
 - Updates of major (proposed) changes of the updated design
- Update from HIT (Harbin Institute of Technology)
 - ICST test system
 - Welding of cold-mass cover plate
- Schedule and near term plans
 - Updated schedule



Overview of CC Fabrication Plan

- Organization and responsibilities
 - LBNL responsible for MICE CC magnets, HIT responsible for the design and fabrication, in collaboration with LBNL
 - Recent responsibility changes
 - LBNL responsible for the cryostat design, in collaboration with SINAP (under US-China HEP Collaboration Agreement); an updated addendum signed between LBNL and HIT in early-August 2010
 - HIT oversee the fabrication with assistance from LBNL
 - ICST test system
 - Cover plate welding of the cold-mass
- CC fabrication at Qi Huan Corp., Beijing
 - Fabrication contract signed mid-March 2010
 - 1st MuCool coil winding started early-July 2010, now ~ 50% finished



Coil Winding at Qi Huan Corp.

- 1st coil winding started early-July 2010
- 50% complete now
- 12 SC wire joints, wire width variations
- Average 2 layers/day (166 turns x 96 layers)
- Expected to complete by end of Nov. 2010
- Cold-mass cover plate welding contract signed mid-August 2010 at HIT




Update from Qi Huan Corp.



Coil winding



SC wire joint



SC wire defect at 50th turn and 37th layer

项目名称: MuCool 超导磁体工程
操作人员: 李能仁
日期: 2009-6-24

线圈编号: 参考线圈: 7.3826.2

日期	时间 (hh:mm)	温度 T(C°)	层号	参考线圈: 7.3826.2			被测线圈			
				电压 (V)	电流 (mA)	电阻 (Ω)	电压 (V)	电流 (mA)	电阻 (Ω)	电阻 (Ω) @ T _{ref}
2010-9-7	10:39	28	21	1.152	156.8	7.3469	22.96	65.05	752.9593	354.6704
	16:25	28	22	1.154	156.8	7.3597	22.97	64.95	352.6567	354.2571
2010-9-9	17:25	28	23	1.147	155.6	7.2715	22.97	64.9	352.9291	354.4620
	8:20	28	24	1.140	155.6	7.3265	22.96	65	352.2008	352.9355
2010-9-10	18:00	28	25	1.155	155.0	7.4103	22.98	67.85	352.3562	353.0514
	17:30	28	26	1.141	155.0	7.3613	22.99	64.8	352.2800	355.8106
2010-9-14	17:26	28	27	1.352	183.3	7.2249	23.13	44.88	352.7703	355.8234
2010-9-15	11:25	28	28	1.372	185.1	7.2132	23.14	44.84	352.0711	353.9963
	16:40	28	29	1.367	184.9	7.2932	23.11	44.73	352.6155	352.9845
2010-9-16	10:44	28	30	1.366	185.8	7.3520	23.11	44.92	352.4129	356.5540
	18:50	28	31	1.366	186.0	7.3441	23.11	44.915	352.4129	357.1096
2010-9-17	11:27	28	32	1.340	185.51	7.2717	23.09	45.125	351.1234	358.9785
	20:30	24	33	1.390	184.4	7.2668	23.13	45.33	350.2581	358.3843
2010-9-18	11:30	23	34	1.334	184.6	7.2269	23.10	45.31	349.8422	350.8411
	12:30	23	35	1.347	185.0	7.2811	23.10	45.24	350.6101	357.7281
2010-9-19	17:00	23	26	1.346	184.6	7.2914	23.13	45.15	352.2924	358.7001
	12:00	23	27	1.342	184.9	7.2580	23.10	45.28	350.1590	358.9170
2010-9-20	6:40	23	28	1.340	184.6	7.2589	23.10	45.24	350.6101	359.3115
	15:25	23	29	1.340	184.6	7.2589	23.10	45.24	350.6101	359.3115
2010-9-24	16:23	23	30	1.340	184.6	7.2589	23.10	45.24	350.6101	359.3115
	18:15	23	31	1.340	184.6	7.2589	23.10	45.24	350.6101	359.3115

制表: 徐凤刚
打印日期: 2009-6-24

Coil winding log




MICE CC Cryostat Design Review

- The review was held from Sept. 13 to 14, 2010 at SINAP
- Review Committee was chaired by Prof. Alan Bross and report coming soon
- Review charges and areas:
 - **Validity of overall cryostat design**
 - **Does the 3 cryo-cooler design provide sufficiently low heat load to the cold mass to allow stable operation?**
 - **Are the final assembly procedures defined?**
 - **How will the cold-mass reference position be transferred to external survey markers?**
 - **Does the mechanical design allow for repairs?**
 - **Cooling circuit update**
 - **Instrumentation/diagnostic sensors (temperature and LHe level)**
 - The design for quench protection system (concerns)
 - HIT test system and cold-mass cover plate welding




The Cryostat Design Update

- An updated cryostat design was presented by SINAP MICE team
- The updated design significantly improves to the performance
 - **Three cryo-coolers as base**
 - **More robust and temperature margin**
 - **Easier for assembly**
 - **Easier access for future repair and adjustment**
 - **A direct method to reference cold mass position to outside survey fiducial**
 - **Improved cooling circuit**




Major Changes in Cryostat

Old





New




All proposed changes have been supported and confirmed by relevant FEA simulations

Cooling Circuit Updates




LHe supply line for cold down

Power Leads and Cooling




Previous design



Updated design



Assembly and Interface

- Many interface issues
- Preliminary progresses
- Assembly procedures
- Supporting structures




RF Coupler Region

- **Issue:** extremely tight space in RF coupler region for MLI and difficult for assembly
- **Proposed solutions:**
 - Reduce RF coupler from 4 1/16 to 3 1/8: ~ 0.5 cm more space
 - Make RFCC module slight longer and keep the RF coupler dimensions




Modification of RF Couplers

- **Proposed solutions:**
 - Reduce RF coupler from 4 1/16 to 3 1/8: ~ 0.5 cm more space




3 1/8" Coupler



4 1/16" Coupler

Update from HIT

- ICST test system: system disassembled
 - Transfer line contamination
 - New transfer line ordered
 - System ready by end Nov. 2010
- Cold-mass cover plate welding
 - Test sample made
 - Welding fixture in progress (with help from LBNL)



Near Term Plan and Schedule

- Finish the 1st coil winding by end of November 2010
- Finish ICST test system by end of November 2010
- Cold-mass cover plate welding
- Continue updating the CC cryostat design
 - More FEA simulations required on the cryostat vessel
 - Cooling circuit need to be further reviewed by experts or simulations
 - Air-plug
 - Quench protection also need to be reviewed
 - Interface with RF cavities and RFCC vacuum vessel
 - Technical discussions between SINAP MICE team and Qi Huan Corp. (received permission from HIT)
- A final design review on the CC cryostat design is required to happen soon before submitting MICE TB for approval
 - Can we combine two reviews?
- 3D, 2D drawings and fabrication of the cryostat




Updated CC Schedule


Task Description	CY 2010	CY 2011	CY 2012
MuCool Coupling Coil			
Cold mass fabrication and assembly	████████████████████		
Cryostat fabrication and final assembly	████████████████████		
Magnet testing and factory acceptance		████████	
MICE Coupling Coil #1			
Cold mass fabrication and assembly	████████████████████		
Cryostat fabrication and final assembly		████████████████████	
Magnet testing and factory acceptance			████████
MICE Coupling Coil #2			
Cold mass fabrication and assembly	████████████████████		
Cryostat fabrication and final assembly		████████████████████	
Magnet testing and factory acceptance			████████



Progress after the Review



Vacuum port: ID is changed from 40mm to 100mm.



Angle changes of gussets in order to avoid interference with RF cavity vacuum vessel

Welding with cut-away redundancy instead of flange connection

Inside supports to reduce local deformation and peak stress of CC vacuum vessel resulting from the upper 4 cold mass supports

