Status of TE² Electron Gun


M. Droba, O. Meusel, K. Schulte-Urlichs
IAP (GUF), GSI
ARIES WP16 internal discussion
20.04.2021


Status of E-Gun


Adaption to Solenoid and Design Upgrades of TE²-Gun


Modifications of:

- cooling connections and flange edges
 - ground electrode
 - grid electrode
 - modulating grid
 - anode
- Insulating shield between gun and solenoid











Design Upgrade of TE²-Gun

Former electrode design (with optimized grid)



Upgraded electrode design



E-Gun Parameters:

 $U_a = 30 \text{ kV}$

 $U_c=0 \text{ kV}$

 $U_g=0 \text{ kV}$

I_{ex}=8.4 A

 $B_z = 0.6T$

E-Gun Parameters:

 $U_a = 30 \text{ kV}$

 $U_c=0 \text{ kV}$


 $U_{g}=0 \text{ kV}$

 $I_{ex} = 10.7 \text{ A}$


B,=0.6 T

Design Upgrade of TE²-Gun

Variable cathode-anode-distance



Upgraded electrode design



E-Gun Parameters:


 $U_a=30 \text{ kV}$ $U_c=0 \text{ kV}$


U_g=0 kV

I_{ex}=10.7 A


design provides also flexibilty in adjusting cathode-grid-distance

Concept of Electron Source Test Bench






HV-Terminal for TE² Operation









Status of Terminal and Test Bench

Status of:

- terminal (cooling, cables, insulation sockets)
 - under construction
- experiment carrier
 - under construction
- adjustment unit for solenoid
 - in design process, material already delivered
- TE² parts
 - Vinidur and copper parts are under construction at IAP workshop
 - cathode and grid ordered, delivery delayed (KW 24)
- Controls (IT infrastructure, software)
 - T. Dönges, BSc Cand.








Numerical Studies of TE²-Gun

Thermionic Model




E-Gun Parameter:

U_a=30 kV T=2000 -2800 K


U_c=0 kV

 $U_g=0 \text{ kV}$ B_z=0.6 T tungsten

Cathode Operation Range



Operating Temperature



has to be determined experimentally

benchmark of simulations

Schedule

Task	Status	Schedule
Assembling of HV-terminal	under construction	Q1 - Q2 2021
Construction of test stand	under construction	Q1 - Q2 2021
Installation of e-gun solenoid and integration of TE ²	Solenoid delivered by GSI/FAIR TE ² parts are being manufactured Experimental carrier under construction support solenoid is being designed, material already delivered	Q2 2021
Extraction of low intensity electron beams	control system under development Numerical beam dynamics studies started	Q2 – Q3 2021
Extraction of high intensity electron beams with modulation	Beam dump delivered by Goethe- University	Q3 - Q4 2021