

# Construction and Testing of a Digital Hadron Calorimeter Prototype

For TIPP 2011

Kurt Francis

ANL\_HEP


# Particle Flow Algorithms

**The goal:** a detector that achieves  $30\%/\sqrt{E}$  jet energy resolution  
 Favored method is to use particle flow algorithms that measure charged particles with tracker and measure neutral particles with calorimeter

**Requires:**

Excellent tracker and high B – field  
 And a dense calorimeter also inside coil with high granularity to distinguish individual particle showers in jets and assign to charged or neutral parent

**Argonne’s solution:** a digital hadron calorimeter (DHCAL) using RPC chambers and 1 cm x 1 cm readout pads with single bit readout hit counting sufficient



Particles in jets	Fraction of energy	Measured with	Resolution [ $\sigma^2$ ]
Charged	65 %	Tracker	Negligible
Photons	25 %	ECAL with $15\%/\sqrt{E}$	$0.07^2 E_{jet}$
Neutral Hadrons	10 %	ECAL + HCAL with $50\%/\sqrt{E}$	$0.16^2 E_{jet}$
Confusion		Required for $30\%/\sqrt{E}$	$\leq 0.24^2 E_{jet}$

}  $18\%/\sqrt{E}$

# 1 m<sup>3</sup> – Digital Hadron Calorimeter Physics Prototype

## Description

Readout of 1 x 1 cm<sup>2</sup> pads with one threshold (1-bit) → **Digital Calorimeter**  
Layers inserted into the existing CALICE Analog (scintillator) HCAL and TCMT structures  
38 layers in DHCAL and 14 in tail catcher (TCMT), each ~ 1 x 1 m<sup>2</sup>  
Each layer with 3 RPCs, each 32 x 96 cm<sup>2</sup>  
~480,000 readout channels

## Purpose

Validate DHCAL concept  
Gain experience running large RPC systems  
Measure hadronic showers in great detail  
Validate hadronic shower models (Geant4)

## Status

Started construction in 2008  
Completed in January 2011  
Test beam runs started in Oct. 2010 at Fermilab  
More test beam runs through rest of year  
Analysis on-going



# Collaboration and Responsibilities

Task	Institutes
Project coordination	Argonne
RPC construction	Argonne
Cassette structure	Argonne
Mechanical structure	DESY
Overall electronic design	Argonne
ASIC design and testing	FNAL, Argonne
Front-end and Pad board design & testing	Argonne
Data concentrator design & testing	Argonne
Data collector design & testing	Boston, Argonne
Timing and trigger module design and testing	FNAL, Argonne
DAQ Software	Argonne, CALICE
High Voltage system	Iowa
Low voltage system	Argonne
Gas mixing and distribution	Iowa
Cables	Argonne, Iowa
Data analysis	Argonne, FNAL, IHEP, Iowa, McGill, Northwestern, UTA

DHCAL Personnel	Heads
Engineers/Technicians	23
Students/Postdocs	7
Physicists	10
<b>Total</b>	<b>40</b>



# RPC Construction

## RPC design

2 – glass RPCs (**chosen for construction**)

1 – glass RPCs (developed at Argonne)

Gas gap size 1.1mm

Total RPC thickness < 3.4mm

Dead area ~5% (frame, spacer)



## RPC concept

High voltage across gas (Freon+Iso-butane+SF<sub>6</sub>)

Ionization is amplified by avalanche effect

Signal detected at pad boards



## Chambers needed

~114 for DHCAL + 42 for TCMT + spares  
at the end, produced ~ **205** RPC's

## Assembly steps

Spraying of glass plates with resistive paint

Cutting of frame pieces

Gluing frame

Gluing glass plates onto frame

Mounting of HV connection, etc.





# Spraying of the glass sheets

## Challenge

Produce a uniform layer with  $R_{\square} = 1 - 5 \text{ M}\Omega$   
value affects pad multiplicity  
value only critical for thin plate, thick plate can be lower/higher

## New paint (artist paint) identified


Reasonably cheap  
Non toxic  
2 component mixture (BLACK and GREEN)  
Needs to be sprayed (built a spraying booth)




## Production

### Has been a struggle

Poor uniformity in a single plate  
Mean value not well controlled from plate to plate  
Low yield: ~ 60% pass quality cut  
Slow – barely match RPC assembly speed



$\text{M}\Omega/\square$




**at the end, it worked out**

# RPC Assembly


## Cutting frames

Dedicated (adjustable) cutting fixture  
Cut length to .2mm precision  
Drill holes  
Tooling designed at ANL



## Assembly

Dedicated gluing fixture  
Frame/gap glued to ~0.1mm precision  
Very time consuming process:  
~1 RPC/day/tech, 3 RPC produced/day



## Production



205 final RPC completed  
only ~10 not usable  
(due to glass broken or quality issues)



# Quality Assurance

1 mil = 25  $\mu\text{m}$

RPC 001





## Pressure tests

- Test with 0.3 inch of water pressure
- Pass if pressure drop < 0.02 inch in 30 seconds
- Chambers not passing 1<sup>st</sup> test are repaired
- All repaired chambers passed 2<sup>nd</sup> test

## Gap size measurement

- Thickness of all chambers measured along the edges (since glass is very uniform  $\rightarrow$  measure of gap size)
- Gap sizes at edges within 0.1 mm (central region uniform due to fishing lines)
- Corners typically thicker (up to 0.3 – 0.4 mm) (only affects very small region)
- > Only ~5 RPC's have low efficiency regions at corner(s) or along side(s), due to larger gap at those places, all replaced from prototype stack

RPC 012



## HV tests

- Tests up to 7.0 kV before placing readout board on top (operating voltage is 6.3 kV)





# Cosmic Ray Test Stand

Up to 9 RPCs tested at once

Testing of early FE board versions

First batch of chambers

Chamber characterization using  
cosmics and noise

Noise measurements



High voltage scans from 5.8 to 6.8 kV

Triggered, trigger-less operation






# Cosmic Ray Test Stand (cont.)


Triggered Data: Standard tests



Trigger-less Mode  
Analyze Cosmic Rays  
**Angle of Incidence Dependence!**



# Readout system overview



# The DCAL Chip

## Developed by

FNAL and Argonne

## Input

64 channels

High gain (GEMs, micromegas...) with minimum threshold  $\sim 5$  fC

Low gain (RPCs) with minimum threshold  $\sim 30$  fC

## Threshold

Set by 8 – bit DAC (up to  $\sim 600$  fC)

Common to 64 channels

## Readout

Triggerless (noise measurements)

Triggered (cosmic, test beam)

## Versions

DCAL I: initial round (analog circuitry not optimized)





DCAL II: some minor problems (used in vertical slice test)

DCAL III: no identified problems (final production: used in current test beam)


## Production of DCAL III

11 wafers, 10,300 chips, fabricated, packaged, tested


DHICAL Construction



# FrontEnd/DCON board + Pad board



- Build FE and pad boards separately to avoid blind and buried vias (cost and feasibility issue)
- Each board contains 1536 channels and 24 ASICs
- The data concentrator is implemented into the same board
- Glue the two boards together with conductive epoxy
- FE board need to pass computer test before gluing
  - Extensive tests (S-curves, noise rates...)
  - 3 – 6 hours/board
  - Accepted boards with less than 4/1536 dead channels



# Gluing fixture for Pad- and FE-boards

Goal: 1536 glue dots on contacts in less than 3 hours



## Fixture

Designed, built and commissioned

## Production

~25 minutes needed/board  
can glue > 10 boards/day

at the end: 300+ FE board fabricated/tested/glued



Controller



Solenoid  
valve

x axis  
motor and  
driver

y axis  
motor and  
driver


z slider

Glue Dispenser



## Back end electronics

1. Timing and Trigger Module (TTM)
2. Data Collector DCOL



## Power supply systems

1. Low voltage system
2. High voltage system



Gas System




# Cassette Assembly

## Assembly

- Cassette is compressed horizontally with a set of 4 (Badminton) strings
- Strings are tensioned to ~20 lbs each, very few broken strings
- ~45 minutes/cassette
- steel and copper plates

## Cassette Testing

- Cassettes were tested with CR before shipping to FTBF





**38+14 cassettes assembled**



## Transportation to FNAL and installation



# Installation into CALICE structure at FNAL




# Installation complete!








## Cabling up

**12 hours of hard work  
(350,000 readout channels  
for the DHCAL alone!)**




# The RPC DHCAL Testbeam Story






DHCAL Construction














# First beam: muons



One muon

Three muon


Four muon



A lot of muons


# Next: pions

60 GeV pions **measured** in DHCAL










Now, the real thing!

# And also positrons



# And occasionally, neutral hadron





# Summary

- The construction of the DHCAL prototype (+TCMT) is complete
- Test beam at Fermilab started last Oct.
- DHCAL prototype (+TCMT) works extremely well
- A lot of good data collected, analysis is on-going
- First look of the data is very encouraging!
- More test beam/more data is on the way
  - 5 to 6 more weeks in May/June
  
- Project led by Argonne
- Involves local Universities
- Many students involved in all phases: construction, operation and analysis



