


LHCf (+ATLAS ZDC) beam test in 2021 allocated for Week 37, 38 (14 days) (in v1.0)


H. Menjo, Nagoya Univ.



Motivations

- Precise pre-calibration of LHCf detectors before Run3
 - Evaluation of aging of the detectors after the last operation (4 or 5 years ago)
 - Precise energy scale calibration with $\sim 2\%$ precision under temperature control. (dominant systematic error on our measurements)
- Test of a upgraded readout system of silicon strip layers
 - It is newly developed for Run3 to improve the readout speed by x10.
- Joint calibration of LHCf and ATLAS-ZDC
 - New opportunities of joint operations in the Run3 period (pp at 2022 and pO, OO at 202?) to improve the energy resolution for hadronic showers from 40% (LHCf alone) to 20% (LHCf+ZDC)
 - First joint calibration of the two detectors.
- Parasitic beam test of RPD detector by the ATLAS-ZDC group

Setup at LHC 140 m from IP1



Beam requirements

- Particles and energies
 - protons: 150, 350 GeV
 - electrons: 100, 150, 200, (250)* GeV
 - muons

*) Highest energy with reasonable intensity

- Beam conditions
 - Parallel beams
 - Intensity of > 1000 per spill
 - beam spot size of ~1.5 cm radius
 - 2x2 cm² scintillator is used for triggers


Preliminary operation plan

| |
|---|
| Setup (3 days) |
| <ul style="list-style-type: none"> • Installation (1.5 day) • Beam tune and Commissioning (1.5 days) |
| Operation with Arm2 (3 days) |
| <ul style="list-style-type: none"> • Energy scan by electron beams (0.5 day) • Position scan by election beams (1 day) • Position scan by proton beams (1 day) • Muon data taking (0.5 day) |
| Switch to Arm1 (1.5 days) |
| <ul style="list-style-type: none"> • Switching the detector to Arm1 (0.5 day) • Commissioning (1 day) |
| Operation with Arm1 (3 days) |
| <ul style="list-style-type: none"> • Energy scan by electron beams (0.5 day) • Position scan by election beams (1 day) • Position scan by proton beams (1 day) • Muon data taking (0.5 day) |
| Contingency (additional tests) (3 days) |
| <ul style="list-style-type: none"> • Tests of new analog modules • PRD tests |
| Deinstallation (0.5 day) |

Infrastructure requests


Beam line

- Big movable table
 - Required movable range H: 80 cm V: 20 cm
 - Table size: **>1.8 m x 1.5 m**
- One electronics rack
 - locate near the table
- Dry air (gas) for avoiding dew condensation
 - Only very small flow
- Crane works
 - for installation (1st-day) and de-installation (last-day)
- Geometrical Survey to align the detector to the beam line



-
- Operation room
 - Space for pre-DAQ setup and test
 - ~ 5x5 m²
 - from 1-2 week before the beam time
-
- A chiller for temperature control
 - Can we rent it from someone ?

This plate size: 2 x 1 m²
 Bigger plate is require for this year operation .



Others

- Concerns about unclear COVID-19 situation in September.
 - All members come from Italy, Japan, and US.
 - Travel restriction (of the countries, institutes) to CERN in this moment.
 - Poor vaccination situation in Japan