### FD2-VD DAQ CDR: Slow Control overview and requirements

Xavier Pons CERN June 18, 2021



## Contents

- Introduction
- protoDUNE Single Phase Slow Control Layout
- Vertical Drift Detector Control System DDCS
- Vertical Drift Detector Safety System DDSS
- Requirements
- Vertical Drift Today: Coldbox, Facility Test
- Conclusion



## Introduction

- The Vertical Drift Slow Control SC is assured by two subsystems:
  - Detector Control System DDCS
  - Detector Safety System DDSS
- Communicating, exchanging data, controlled, operated by the Vertical Drift Slow Controls





### **Introduction. DDCS**

• The Detector Control System DDCS involves all the subsystems and elements (hardware and software) that integrate the detector allowing its correct operation and supervision.



CERN DUNE

### **Introduction. DDSS**

• The Detector Safety System DDSS assures the safety of the detectors, including all subsystems and elements (hardware and software) that integrate the detector, allowing the operation in safe conditions





### protoDUNE Single Phase Slow Control Layout





#### protoDUNE Single Phase Slow Control. HV integration Example

The data is transmitted to Real-Time controller, connected and integrated to the SCADA DCS program by means of the OPC UA driver for HV control, operation and monitor.





#### **Vertical Drift DUNE Detector Control System Layout. DDCS**





#### Vertical Drift DUNE Detector Safety System Layout. DDSS



- Highly reliable and available, as well simple and robust ۲
- A cost-effective solution for experiment safety
- Operated permanently and independently of the DDCS state
- Able to take the immediate action to protect the equipment
- Scalable, that it may evolve with the experiments during their assembly,
- Maintainable over the lifetime of the experiments
- Connectable to other detector, subdetector or any other equipment of the

The core of the DDSS is the redundant PLC, e.g. SIEMENS S7-400H.

The two S7-400 CPUS synchronized with optical fiber, run the same code. comparing their states, in case of problem in one CPU, the redundant takes over

The two S7-400 CPUS are mounted in different locations (e.g. one underground the other in the surface)



e.g. Underground 2

## **Slow Control requirement. Connectivity**

- The essential point of the Slow Controls is the connectivity
- The openness to a comprehensive range of drivers or protocols
- Vertical Drift DDCS gives priority to the OPC UA





#### **Slow Control Requirement. Scalability**

From M. Verzocchi, Bottom Detector



Total: 256 positive (16 ISEG modules with 16-channels each), 320 negative (20 ISEG modules with 16-channels) each

This requires four MPOD crates each with 4 positive and 5 negative ISEG modules

Each WIEC requires one channel of a WIENER PL506 (6 channels each)

Need 17 WIENER crates to provide power to the 100 WIECs (1.8-2.5 kW per crate)

Total amount of WIENER channels =

678 channels

X 37 OPC items /channel =

25086 items

#	Server	Node Id	Display Name	Value	Datatype	Source Timestamp	Server Timestamp	Status
1	MPOD	NS2IStringIMPOD CE RACK4	FailureMaxCurrent	false	Boolean	16:58:06.702	16:58:07.659	Good
2	MPOD	NS2IStringIMPOD CE RACK4	FailureMaxPower	false	Boolean	16:58:06.702	16:58:07.659	Good
3	MPOD	NS2IStringIMPOD CE RACK4	FailureMaxSenseVoltage	false	Boolean	16:58:06.702	16:58:07.659	Good
4	MPOD	NS2IString MPOD_CE_RACK4	FailureMax Temperature	false	Boolean	16:58:06.702	16:58:07.659	Good
5	MPOD	NS2IStringIMPOD CE RACK4	FailureMaxTermina/Voltage	false	Boolean	16:58:06.702	16:58:07.659	Good
6	MPOD	NS2IStringIMPOD CE RACK4	FailureMinSenseVoltage	false	Boolean	16:58:06.702	16:58:07.659	Good
7	MPOD	NS2IString MPOD_CE_RACK4	FailureTimeout	false	Boolean	16:58:06.702	16:58:07.659	Good
8	MPOD	NS2IStringIMPOD CE RACK4	Inhibit	false	Boolean	16:58:06.702	16:58:07.659	Good
9	MPOD	NS2IStringIMPOD CE RACK4	On	false	Boolean	16:58:06.702	16:58:07.659	Good
10	MPOD	NS2IStringIMPOD CE RACK4	RampDown	false	Boolean	16:58:06.702	16:58:07.659	Good
11	MPOD	NS2IStringIMPOD CE RACK4	RampUp	false	Boolean	16:58:06.702	16:58:07.659	Good
12	MPOD	NS2IStringIMPOD CE RACK4	Inhibit	1	Int32	16:58:05.001	16:58:07.659	Good
13	MPOD	NS2IStringIMPOD CE RACK4	MaxCurrent	1	Int32	16:58:05.001	16:58:07.659	Good
14	MPOD	NS2IStringIMPOD CE RACK4	MaxPower	0	Int32	16:58:05.001	16:58:07.659	Good
15	MPOD	NS2IStringIMPOD CE RACK4	MaxSenseVoltage	0	Int32	16:58:05.001	16:58:07.659	Good
16	MPOD	NS2IStringIMPOD CE RACK4	MaxTemperature	0	Int32	16:58:05.001	16:58:07.659	Good
17	MPOD	NS2IString MPOD_CE_RACK4	Max TerminalVoltage	0	Int32	16:58:05.001	16:58:07.659	Good
18	MPOD	NS2IStringIMPOD CE RACK4	MinSenseVoltage	0	Int32	16:58:05.001	16:58:07.659	Good
19	MPOD	NS2IString MPOD_CE_RACK4	Timeout	0	Int32	16:58:05.001	16:58:07.659	Good
20	MPOD	NS2IStringIMPOD CE RACK4	ClearEvents	false	Boolean	16:36:39.894	16:58:07.659	Good
21	MPOD	NS2IString MPOD_CE_RACK4	Current	0.001	Float	16:58:04.901	16:58:07.659	Good
22	MPOD	NS2IStringIMPOD CE RACK4	GroupNumber	0	Int32	16:58:04.901	16:58:07.659	Good
23	MPOD	NS2IStringIMPOD CE RACK4	MeasurementCurrent	3.85976e-011	Float	16:59:03.834	16:59:03.834	Good
24	MPOD	NS2IStringIMPOD CE RACK4	MeasurementSenseVoltage	0.0187143	Float	16:59:03.734	16:59:03.734	Good
25	MPOD	NS2IStringIMPOD CE RACK4	MeasurementTemperature	33	Float	16:58:06.702	16:58:07.659	Good
26	MPOD	NS2 String MPOD_CE_RACK4	MeasurementTerminalVoltage	0.0187143	Float	16:59:03.834	16:59:03.834	Good
27	MPOD	NS2IStringIMPOD CE RACK4	Name	UO	String	16:36:45.491	16:58:07.659	Good
28	MPOD	NS2[String]MPOD_CE_RACK4	OnOff	false	Boolean	16:36:39.894	16:58:07.659	Good
29	MPOD	NS2 String MPOD_CE_RACK4	SupervisionMaxCurrent	0.001	Float	16:58:05.001	16:58:07.659	Good
30	MPOD	NS2IStringIMPOD CE RACK4	SupervisionMaxPower	-1.#QNAN	Float	16:58:05.001	16:58:07.659	Good
31	MPOD	NS2IString MPOD_CE_RACK4	SupervisionMaxSenseVoltage	-1.#QNAN	Float	16:58:05.001	16:58:07.659	Good
32	MPOD	NS2 String MPOD_CE_RACK4	SupervisionMaxTerminalVoltage	100	Float	16:58:05.001	16:58:07.659	Good
33	MPOD	NS2[String]MPOD_CE_RACK4	SupervisionMinSenseVoltage	-1.#QNAN	Float	16:58:05.001	16:58:07.659	Good
34	MPOD	NS2 String MPOD_CE_RACK4	TripTimeMaxCurrent	500	Float	16:58:05.001	16:58:07.659	Good
35	MPOD	NS2 String MPOD_CE_RACK4	Voltage	0	Float	16:58:04.901	16:58:07.659	Good
36	MPOD	NS2 String MPOD_CE_RACK4	VoltageFallRate	-30	Float	16:58:04.901	16:58:07.659	Good
37	MPOD	NS2 String MPOD_CE_RACK4	VoltageRiseRate	-30	Float	16:58:04.901	16:58:07.659	Good

The Slow Controls has to provide the tools to facilitate and simplify the configuration, operation and archiving of such amount data/channels



### **Supervisory or Scada Software Requirements**

- Homogeneity. Ideally the SC provides a homogeneous environment into which all its parts can be integrated
- Scalability
  - To connect to different subsystem and devices
  - Capacity to handle huge amounts of data.
- Openness.
  - Possibility of parallel developers
  - Comprehensive range of drivers and Connectivity
  - Priority to the OPC UA
- Data Archiving & Data retrieving
- User Interface. Data reporting, trending...
  - Multi-user system. User interface
  - Access Control. User rights
  - Web User Interface, Mobile User Interface (only monitoring)
- Redundancy (Passive or Active), suitable.

### **Vertical Drift Today. Coldbox**



First VD Coldbox layout including rack arrangement a port assignment

- The VD coldbox is being installed using the Dual Phase protoDUNE infrastructure including the isolation detector ground.
- 5 racks will be installed close the coldbox for allocating the detector and slow control equipment.
- The SC will be based in the WINCC OA SCADA and using the facilities already in place for the Dual Phase Detector.
- Discussions are ongoing to define the specifications of the VD Slow control (DDCS and DDSS), the subsystems and the instrumentation



- The cryogenics SC already well defined and
- The instrumentation is already listed and the ports are assigned



### **Vertical Drift Today. Neutrino Test Lab**

- Due to the high requests, a Slow Control project is being prepared for neutrino test facilities at CERN, mainly at Building 182
- The aim of this project is to support the validation of the different tests that are ongoing:
  - Vertical Drift 50 liters test
  - 300 kV High Voltage Feedthrough test



First NU Test Lab panel for CERN 50 Liters test



300 kV feedthrough test setup



# **VD SC CDR Summary**

- We have a conceptual design for the Vertical Drift Slow Controls.
- This design follows the majority of the detectors as well the industrial control system standards
- The main requirements are understood but they will be completed first in the Coldbox and later in protoDUNE
- The team is not yet in place, meanwhile the project is driven by the CERN team in the interim



### Backup



16 June 18, 2021 X. Pons | FD2-VD Slow Controls

## **OPC** (Open Platform Communications)

#### **OPC** Data Access

See more on: https://opcfoundation.org/

- OPC Data Access is a group of client-server **standards** that provides specifications for communicating **real-time** data.
- Is based on Microsoft Windows technology using the COM/DCOM (Distributed Component Object Model) for the exchange of data between software components.

#### **OPC** Unified Architecture

- OPC UA was designed to enhance and surpass the capabilities of the OPC Classic specifications
  - Functional Equivalence
  - Platform Independence
  - Security
  - Extensible





6/17/2021

• Data storage



