

Chimneys: From Double Phase to Vertical Drift



To synchronization DAQ grand master White Rabbit switch network for clock syncronization


40 Gbit/s data


optical link to DAQ

Electronics Readout Scheme for Upper Drift Volume

Allows an access to Top Front-End electronics at any time

- Insures the **transition** between **cold** and **warm** parts
- Houses a thermal exchanger to **limit** the **heat injection** in the cryostat and to insure an **optimal running** of FE boards
- Is an isolated and independent volume filled with nitrogen at atmospheric pressure
- Houses 50 FE boards (3200 channels) (10 boards for DP)
- **105 chimneys** to be produced (240 for DP)






- For DP, need for 240 chimneys
- => reduction of cost production mandatory
- Work lead by Rodolphe Marie at IJCLab in connection with Dario Autiero and Franco Sergiampietri
- \Rightarrow Move to CF flanges to LF ones
- ⇒ Modification of guiding system => reduction of the numbers of components and weldings
- ⇒ Design with simplified machining
- ⇒ Cost of **prototype** ~12 k€: probably ½ of this amount for a mass production




2,35 meter


DP Prototype

- Partially produced in the industry
- Finalized at IJCLab workshop
- First Tests driven by A.Gallas in April 2021 in a cryostat with Liquid Nitrogen using Accelerator Pole facilities and support
















Tests Status

- Sealing not correct: one welding (done in the industry) at the top which cannot be easily fixed
- \Rightarrow remaining leak (~10⁻⁴ mbar l⁻¹ s⁻¹)
- \Rightarrow few 10⁻² mbar obtained (reminder at CERN (10⁻³ mbar))
- Not critical for cold tests
- Welding not present for ColdBox chimneys (no cooling circuit)
- To be taken into account for VD design




- Test in a cryostat filled with liquid Nitrogen
- Introduction of **blades**:
 - at warm temperature **OK**
 - at **cold** temperature **OK**
- Electrical continuity tests at cold for bottom part: OK
- Temperature profiles (tube, blades) with/without a simulated FE board heat dissipation
 - 6 measurement positions for 2 blades and on the tube
 - 1 measurement every minute






- 9h35 : Nitrogen flushing
- 10h : blade removal and tests of all slots
- 10h05 : cooling : Nitrogen injection in thermalisation circuit
- 10h20-11h10: heating with 2x5W (change of slope in cooling)
- 12h00-14h: tries to adjust temperature in the bottom part





- Effect of blade removal and introduction
- No increase due to heating start: just a change of slope in cooling (see previous slide)




Coldbox chimney

- Design similar to DP prototype, **just length adaptation**
- Suppression of heat exchanger
- 5 chimneys under production in the industry
 - Welding for the 5 chimneys ended today
 - Cleaning and leak tests next week
 - Delivery expected in 10 days
- Cost: 9 k€ per chimney







Chimneys for Vertical Drift

- Penetration diameter from 250 to 480 mm
- Able to house up to **50 FE boards** instead of 10
- **105 chimneys** to be produced


Positioning of 50 connectors on Cold flange is possible with

associated guiding system

PCB design to be done

Heat dissipation to be simulated

CAD file sent to I&I team to check potential problems with chimney height and handling



Conclusion

- ☐ DP Prototype
 - Cold tests in Liquid Nitrogen
 - Handling of blades without problem
 - 88 K reached in the bottom part. Stable within 1 K
 - Electrical continuity OK
 - Useful lessons for VD design
- □ Coldbox
 - Production in progress, almost ended (cleaning and leak tests to be performed next week
 - ⇒ Available at IJCLab in few weeks
 - ⇒ At CERN before the end of June if needed
- ☐ First drawings for VD version
 - Solution for housing 50 boards has been found
 - Heat simulation to be performed in order to design the heat exchanger
 - **Electronic engineer** identified for PCB design
 - Interactions with I&I team for possible height and handling issues