


The STAR Forward Upgrade Status

Xu Sun for the STAR Collaboration University of Illinois at Chicago



The STAR Forward Upgrade



STAR forward upgrade: $2.5 < \eta < 4$

- faces blue RHIC beam
- rapidity coverage the same as EIC hadron Arm

Combines:

Forward Colorimeter System (FCS) Electromagnetic Calorimeter Hadronic Calorimeter

Forward Tracking System (FTS) Forward Silicon Tracker (FST) small-strip Thin Gap Chambers (sTGC)

Observables:

- inclusive and di-jets
- hadrons in jets
- Lambda Polarization
- correlations mid-forward & forward-forward rapidity


Requirements from Physics:

- good e/h separation
- photon, π^0 identification

	Detector	pp and pA	AA
n	ECal	$\sim 10 \% / \sqrt{E}$	$\sim 20 \% /\sqrt{E}$
	HCal	$\sim 50 \% / \sqrt{E} + 10 \%$	—
Xu Sı	Tracking	Charge separation photon suppression	$\delta p_T / p_T \sim 20 - 30\%$ for $0.2 < p_T < 2GeV/c$

Forward Silicon Tracker





STAR forward upgrade: $2.5 < \eta < 4$


- faces blue RHIC beam
- rapidity coverage the same as EIC hadron Arm

3 Silicon disks: at 152, 165, and 179 cm from IP Built on successful experience with STAR IST

- locate inside STAR TPC cone
- Single-sided double-metal mini-strip sensors
 - Granularity: fine in ϕ and coarse in R
 - Si from Hamamatsu
- Frontend chips: APV25
- Material budget: ~1% per disk
- Reuse
 - IST DAQ system
 - IST cooling system

FST Module Design





Each module splits into two regions

- Inner-radius region: 5<R<16.5 cm
 - 1 Kapton flexible hybrid
 - 1 Si sensor: $128 \times 4 (\phi \times R)$ strips
 - 4 APV chips
- Outer-radius region: 16.5<R<28 cm
 - 1 Kapton flexible hybrid
 - 2 Si sensors: $128 \times 4 \ (\phi \times R)$ strips
 - 4 APV chips

Mechanical structure is made of

- PEEK (main structure, tube holder)
- Stainless steel (cooling tube)
- Aluminum (heat sinks)


Module assembly is done at two sites

- TiDC (NCKU): gluing inner/outer hybrids and mechanical structures together
- FNAL (UIC): mount/wire-bond APVs and Silicon sensors on hybrids

material budget: ~1% X₀ per disk


FST Module Design








FST Module Assembly at FNAL



- Module assembly at FNAL from January 2021 to June 2021.
- 48 modules assembled: 43 good + 5 problematic.
- All the modules arrived at BNL on June 11, 2021.

FST Module Performance Test at UIC



- Performance of FST modules are evaluated with cosmic ray:
 - All channels can be read out
 - Efficiency higher than 90%


FST pre-Installation and Test at BNL



- FST modules installed into the support structure in the clean room (April July 2021).
- Survey was done after each half plane completed (mid-plane has surveyed both sides).
- Readout and cooling test in the clean room for all 36 installed modules.

FST Installation at BNL






• FST Installation completed on 08/13/2021 and partition closed on 08/31/2021.


Xu Sun—WWND 2022

FST Cooling System











FST Operation








- Each FST disk is readout by 2 ARC & 6 ARM boards, reused IST system
- Operation HV: 140V for inner sensor and 160 for outer sensors
- FST is commissioned and currently taking data at STAR run 22

small-Strip Thin Gap Chamber



STAR forward upgrade: $2.5 < \eta < 4$


- faces blue RHIC beam
- rapidity coverage the same as EIC hadron Arm

4 sTGC disks: at 307, 325, 343 and 361 cm from IP

- locate inside STAR Magnet pole tip opening
 inhomogeneous magnetic field
- 4 quadrants double sided sTGC => 1 layer
 - diagonal strips to break ambiguities in the sTGC
- Position resolution: $\sim 100 \mu m$
- Material budget: ~0.5% per layer,
- Readout: based on VMM-chips
 => following ATLAS design


sTGC Design






- Provides tracking and position resolution less than 100 µm, at high luminosity and background
- Anode (HV): 50 µm gold-plated tungsten wires held at a potential of ~2900 V
 - TPC 20 μ m wires
- Working gas: n-Pentane+CO₂ = 45:55% by volume
- Cathode(Ground): graphite-epoxy mixture with a typical surface resistivity of 100 to 200 kΩ sprayed on G-10
- Readout: Small copper strips, perpendicular to anode wires, behind the cathode

sTGC Assembly at SDU






Efficiency > 97%




- Four planes, each consisting of four 55cm*55cm pentagonal modules
 - Double-sided sTGC with diagonal strips
 - Position resolution $< 100 \ \mu m$
 - performed cosmic ray test at SDU
- Material budget $\sim 0.5\%$ X₀ per layer
- 19 pentagon modules are produced and arrived at BNL on 08/06/2021.


sTGC Electronics Design at USTC













- FEBs are designed based on VMM chips. 4 VMM chips/ board, 212 channels.
- 96 Front-End Boards => 24 FEBs for each layer.
- 16 Read Out Driver Module => one for every 6 FEBs.
- ROD modules are designed based on Standard VME 6U Crate (with DC power supply).


Xu Sun—WWND 2022


sTGC Installation at BNL











sTGC Gas and Safety System at BNL




Gas Cabinet



Gas Distribution Panel



Gas Purity Analyzer




- sTGCs use a mixture of CO₂ and n-pentane
 - n-pentane isomer formula C5H12
 - Extreme care needed for the highly flammable n-pentane!
 - Flash point –49 °C; explosive limits 1.5 7.8%
 - Boiling point of 36.1 °C further complicates things
- Has operated extremely well through major power failures and big storms

sTGC Operation




sTGC HV Slow Control

		el			
Voltage W Board Power must be DN HV Board Power		STGC Clear Trips	Temperature [C]		
Full	HV Channel On Ramp Up/Down HV Channel Off Interlock		Board 0		
StandBy 0 Volts	Other Internal Trip	Calibrate Currents	Board 1		
and the second se	(expert only)		Board 2		
Cable Voltage (V) Current		Cable Voltage [V] Current [µA] Cable	Voltage [V] Current [µA]		
1 3000 30.8	810 3 3000 36.083	9 0 -0.130 11	3000 29.660		
2 3000 40.5	508 4 3000 35.890	10 3000 32.226 12	3000 47.510		
5 3000 51.4	448 7 3000 31.933	13 2999 47.549 15	2999 34.929		
6 3000 42.1	159 8 2999 40.019	14 2999 40.594 16	2999 40.133		
Plane 3 on or	(expert only)				
Cable Voltage [V] Current	t [μΛ] Cable Voitage [V] Current [μΛ]	Cable Voltage [V] Current [µA] Cable	Voltage [V] Current [µA]		
17 2999 32.2	289 19 3000 39.120	25 2999 32.938 27	2999 47.451		
18 2999 44.8	847 20 3000 46.343	26 2999 43.660 28	2999 46.279		
21 3000 50.1	129 23 3000 29.166	29 2999 54.997 31	3000 36.428		
22 2999 51.1	150 24 3000 47.390	30 2999 51.648 32	3000 48.012		
Write data to file? NO YES Writing!					








- Operation HV: 1500 V for standby and 3000 V for data taking
- Safety and gas mixing is automated through interlock logic
- Refill pentane, every three weeks by experts
- CO₂ change every two months by experts
 - Backed up by reserve tank online—no run out
- sTGC is commissioned and currently taking data at STAR run22


02/28/2022

Simulated Performance of the Forward Tracker



- Charge mis-ID rate less than 6% (8%) for $p_T < 5$ GeV/c and 500 (200) μm vertex resolution
- p_T resolution better than 35% for $p_T < 5$ GeV/c for both beam energies

Forward Calorimeter System



Entire FCS (ECal + HCal + electronics) was installed during 2020

- Commissioned during Run 21
- Extensive running with Au+Au at $\sqrt{s_{NN}} = 7.7 \text{ GeV}$
- Brief runs with O+O and d+Au at $\sqrt{s_{NN}} = 200 \text{ GeV}$

Location: 7 m from the IP on the "FMS platform" Readout: SiPMs

- Used in Trigger
- Split in 2 movable halves inside and outside of ring
- Slightly projective

ECal:

- reuse PHENIX PbSC calorimeter
 - 1496 channels: 5.52 x 5.52 x 33 cm³
 - 66 sampling cells with 1.5 mm Pb/4 mm Sc
 - 36 wavelength shifting fibers per cell
 - 18 X₀; 0.85 λ
- replaced PMTs with SiPM readout

HCal:


- Fe/Sc (20mm/3 mm) sandwich.
 - 520 readout channels: 10 x 10 x 84 cm³
 ~ 4.5 λ
- Uses same SiPM readout as ECal
- in close collaboration with EIC R&D

Preshower:

Use EPD => Splitter prototype tested and final ones currently built

02/28/2022

Forward Calorimeter System



Entire FCS (ECal + HCal + electronics) was installed during 2020

- Commissioned during Run 21
- Extensive running with Au+Au at $\sqrt{s_{NN}} = 7.7 \text{ GeV}$
- Brief runs with O+O and d+Au at $\sqrt{s_{NN}} = 200 \text{ GeV}_{Xu \text{ Sun}}$

Location: 7 m from the IP on the "FMS platform" Readout: SiPMs

- Used in Trigger
- Split in 2 movable halves inside and outside of ring
- Slightly projective

ECal:

- reuse PHENIX PbSC calorimeter
 - 1496 channels: 5.52 x 5.52 x 33 cm³
 - 66 sampling cells with 1.5 mm Pb/4 mm Sc
 - 36 wavelength shifting fibers per cell
 - 18 X₀; 0.85 λ
- replaced PMTs with SiPM readout

HCal:

- Fe/Sc (20mm/3 mm) sandwich.
 - 520 readout channels: 10 x 10 x 84 cm³
 ~ 4.5 λ
- Uses same SiPM readout as ECal
- in close collaboration with EIC R&D

Preshower:

Use EPD => Splitter prototype tested and final ones currently built


Forward Colorimeter System




Members of UC EIC Consortia Assembling FCS in Autumn 2020 at BNL

Forward Calorimeter System (FCS)

- ECal 1496 channels ~ 8 tons
- HCal 520 channels ~ 30 tons.
- SiPM Readout Bias ~ 67 V
- New digitizers + Trigger FPGA = DEP boards








Large group of STAR collaborators actively engaged in all aspects of the project: ACU, BNL, UCLA, UCR, Indiana University CEEM, UKU, OSU, Rutgers U., Temple U., Texas A&M U., Valparaiso U.


FCS Assembly

















FCS Readout and Commissioning, Run 21




- During Run21:
 - Exercised the on-line machinery, monitoring systems, and slow controls
 - Off-line and Monte Carlo machinery also in place
 - Trigger system was commissioned
- Was ready to go on Run 22 Day-1 (except for some gain tweaks)






+-Col North <-> South



FCS Performance





π^0 reconstructed by Di-photon from ECal



• FCS is commissioned and currently taking data at STAR run22

MIP peak from Hcal (Matched with Ecal MIP)






ECal MIP candidate matching HCal MIP candidate shows peak around dY=0,Vertically aligned

Summary




- Despite of COVID, all the Forward upgrade subsystems were installed on time
- All forward detectors were commissioned on time and taking data
- Many Thanks to those who are all involved to make this happen!





Dedicated manpower with large expertise for each subsystem



and the STAR collaboration, which stands enthusiastically behind the upgrade