

Kickers and dumps

Tuesday 25 January 2011 08:55 (15 minutes)

Planned major hardware interventions include the completion of the staged dilution kicker system in point 6 (installation of 2 last tanks and associated generators), replacement of the extraction protection elements TCDQ (for performance reasons) and possibly the replacement of 2 injection kickers. The reliability overhaul program for the extraction kicker generators will be completed, and numerous improvements of electronics and controls of the various systems be carried out, followed by a thorough test and re-qualification program.

Presenter: MERTENS, Volker (CERN)

Session Classification: Session 03 Shutdown 2012 (Part II)