



Recent activities at Tsinghua X-band High Power Test stand (TPoT-X)

Jiaru Shi

Tsinghua University, China



CLIC Project meeting, CERN, 2021.10.05

Background

- Accelerator Lab. In Tsinghua Univ., Beijing
- RF Structure (linac tubes) manufacturing since 1970s. >100 tubes/year
- Host of two beam lines
 - TTX (Tsinghua Thomson X-ray source), electron
 - CPHS (Compact Pulsed Hadron Sources) Proton
- X-band high-gradient activity started with collaboration with CLIC project. ~2009
- Production of HG structures
- Test stand at X and S-band




Tsinghua High Power Test-Stand





VIGAS: 350-MeV-linac based Inverse Compton Source

- Very Compact ICS Gamma-ray Source
- Total length < 12.5m: S-band injector and X-band linac at 80MV/m
- **Five-year (2021-2025) project**, beam-line under construction
- Beam available by the end of 2023



Background

- X-band High-power Test Stand started operation since 2018



System diagram of TPoT-X

Signal Source and SSA


11404 MHz~11444 MHz
1.2 kW/5 us/100 Hz

CPI VKX-8311B Klystron:

50 MW, 1.5 us RF pulse
52.6 MW achieved!

ScandiNova solid state modulator

Current Rep. Freq: 40 Hz




TPoT-X RF System w/ Power splitter



Courtesy of I. Syratchev and A. Grudiev

Left arm:

- No pulse compressor
- to test the standing wave structures




X-band RF gun



The power distribution ratio of the two branches can be changed by adjusting the position of the piston

Right arm:

- equipped with a pulse compressor
- **traveling wave structures**, high power, short pulse



X-band 72 cell structure

Parameters and functions of TPot-X



- TPot-X serves as an X-band high-power test stands
- Parameters:
 - Frequency: 11.424 GHz
 - Output of klystron: 50 MW, 1.5 us RF pulse
- Functions:
 - Test of high gradient structure
 - T24_THU#1, Single cell choke mode structures, single cell structure...
 - Structure conditioning
 - Accelerating structure for VIGAS, deflecting and accelerating structure for SXFEL...
 - Test of RF component
 - Pulse compressor, power splitter
 - Cathode imaging experiment with an X-band field emission gun

Recent activities at TPoT-X



- Single cell structure (finished 2021 Jan.)
- X-band deflecting structure (finished 2021 Mar.)
- X-band constant-impedance structure (finished 2021 July)
- X-band constant-gradient structure (finished 2021 Sept.)

Single cell structure

- Same design on 11.7GHz and 11.424GHz
- 11.7 version tested on AWA 400MW @ short pulse <10ns
- 11.424 version tested at TPoT



Single cell structure TW-A3.05T2.90 full history




Small amount of pulses


E^{50}

Single cell structure TW-A3.05T2.90

- Results of 30 ns and 100 ns are presented here.
- In 30-ns cases, breakdown is more likely to happen at the end of the pulse.
- In 100-ns cases, breakdown is more likely to happen at the middle of the pulse.



Breakdown pulse form with 30 ns input






Breakdown pulse form with 100 ns input

Recent activities at TPoT-X

- Single cell structure (finished 2021 Jan.)
- X-band deflecting structure (finished 2021 Mar.)
- X-band constant-impedance structure (finished 2021 July)
- X-band constant-gradient structure (2021 Sept.)


X band deflecting structure

- 1-m travelling wave deflecting structure for SXFEL.
- Developed at SINAP.
- **Milestone: First collaborated structure tested**



X band deflecting structure Full history

- The breakdown rate of 150 ns, 35 MW (nominal) was less than $1e-4$






Total # pulse : $1e7$

Recent activities at TPoT-X

- Single cell structure (finished 2021 Jan.)
- X-band deflecting structure (finished 2021 Mar.)
- X-band constant-impedance structure (finished 2021 July)
- X-band constant-gradient structure (2021 Sept.)




X-band Constant Impedance structure

- X-band Constant Impedance 72-cell travelling structure (XC72)
- Designed, fabricated and tested at Tsinghua.
- First prototype structure for VIGAS





X-band linac

- The structure is high-power tested with the pulse compressor on.





X-band linac full history

- The structure has been conditioned with 17 million pulses and tested with 2 million pulses.
- The target (80MV/m) was almost reached.



X-band linac conditioning history

- The breakdown rate versus accelerating gradient is close to the 30-power law
- The breakdown distribution is obtained from the input, transmit and reflect waveform






Recent activities at TPoT-X

- Single cell structure (finished 2021 Jan.)
- X-band deflecting structure (finished 2021 Mar.)
- X-band constant-impedance structure (finished 2021 July)
- X-band constant-gradient structure (2021 Sept.)



Constant gradient structure

- 1-m travelling wave constant gradient structure for SXFEL. Developed at SINAP.




Constant gradient structure full history


- Still conditioning. ~ 23.5 million pulsed. The result (150ns, 46MW, ~ 60 MV/m)
- It may be inferred from the breakdown distribution that the structure is not full conditioned




Timeline




● 2020.09 Power splitter



● 2020.12 Field emission gun




● 2021.01 Single cell structure



● 2021.09 Accelerating structure



● 2021.07 Accelerating structure




● 2021.05 Deflecting structure

Future plans—Test plans

Structures	Date
X-band deflecting structure. SINAP	May, 2021
XC72-Constant Impedance (VIGAS prototype)	July, 2021
X-constant gradient accl. SINAP	Sep, 2021, running
X-band RF gun	Running, since Jan 2021
Distributed-coupling structure	Oct, 2021
2-stage pulse compressor	Nov, 2021
T24-Half	Jan, 2022
XT72-constant gradient for 80MV/m (VIGAS prototype)	Mar, 2022

Two-stage pulse compressor

- Design peak power gain: 16
- Expected output power > **300 MW**
- The fabrication of RF components is finished
- Tuning and high-power test will be performed during Oct. and Nov.



Calculated pulse form



Correction cavities



1st and 2nd stage storage cavity

Summary

- VIGAS: compact 350MeV e-linac with X-band structures at 80MV/m.
 - Two more CPI 50MW klystrons by the end of 2022.
 - TPoT-X is very important experience for building the X-band beam line.
- Parameters of TPOT-X
 - 50MW, 1.5us, 40Hz from CPI VKX-8311B
 - Two arms w/ and w/o pulse compressor
 - ~200MW @100-200ns after pulse compressor, stable, for structure conditioning
 - >300MW @ 30ns-FWHM, also available for experimental structures,
- Run mode
 - 10h*(5-6)days / NOT for 24*7
 - 100~200h (~2e7 pulse) / month
 - 1-2month / structure
- Future plans
 - **Two** XT72's (630mm accelerating structure at 80MV/m) will be tested at TPoT in 2022.
 - Other time slots are open to different structures

Acknowledgements

- Many thanks to: Walter Wuensch, Igor Syrathev, Alexej Grudiev, Nuria Catalan Lasheras, Gerard Mcmonagle, Gerardo D'Auria, Toshiyasu Higo, Zhao Zhentang, Gu Qiang, Fang Wencheng, Wu Xiaowei ... for their contribution and help

Announcement

- <https://indico.cern.ch/event/1080222/>

International Workshop on Breakdown Science and High Gradient Technology (HG2022)

May 16 – 19, 2022
Europe/Paris timezone

Enter your search term



- We look forward to meeting again soon.

Thank you!