### **ISOLDE Operations, YETS** and plans for 2022

J. Vollaire on behalf of technical and operation teams

Slides from: K. Chrysalidis, R. Heinke, E. Siesling and S. Stegemann









- Technical feedbacks since the last ISCC (mid-June)
- Summary of target production & Fast Tape Station
- RILIS highlights
- Coming YETS (Year End Technical Stop) and plans for 2022




### Technical Highlights (problems & feedbacks)

- Excellent performances and availability of different systems (new Frontends)
- Technical problems could be addressed promptly thanks to the availability and commitments of experts:
  - Problem with the fan and temperature sensors for the HRS FE Turbo pumps
  - BTY line (proton beam line) vacuum leak
  - GPS FE: FC door opening, target clamping piston, extraction electrode movement
  - Interference between a shielding door (target storage shelves) and robot gripper
- Target exchanges can be further optimized (duration and resources):
  - Need to patrol all access sectors and have the target area in "Beam Mode" to move the robots (prevent access to the HV room for target setup)
  - Modifications proposed for the coming YETS
- Preventive maintenance will account for failures observed during the run
- Consolidation of interfaces with the ISOLDE robots (shielding doors for shelves and rail conveyor system



## Technical Highlights (problems & feedbacks)










- Technical feedbacks since the last ISCC (mid-June)
- Summary of target production & Fast Tape Station
- RILIS highlights
- Coming YETS (Year End Technical Stop) and plans for 2022



## **Target production operation 2021**



199192


Slide from S. Stegemann



### <u>199192</u>

### Feedbacks target production & operation

- Pre-making UC<sub>2</sub>C charges worked overall well!
  - Possibility to better distribute production workload
- Prolonged outgassing in some cases (and other older targets)
  - Issue since outgassing & carburization pump stands not available
  - Working on re-installation and readiness for 2022
- Calibrated leak clogging
  - Observed occasionally (at offline fortunately)
  - Developing improved leak installation








## **Target material production**

- Production went well despite personnel shortage
- Some more complex materials (eg CaO, Y<sub>2</sub>O<sub>3</sub>) require dedicated setups, space and time
- Bottleneck: production
  material development
- Eg, glove box required to load O<sub>2</sub>-sensitive materials, as well as for nano-target development



#### (Decarbonation setup that allows transport in inert atmosphere to glove box)





92<sup>nd</sup> ISOLDE Collaboration Committee meeting


199192

### Fast Tape Station (installed during LS2)

- New fast tape station (ISCC June) works very well!
- Equipped with:
  - In-beam detector
  - $4\pi \beta$ -detector
  - γ-detector
- Transport time ~100 ms!
- DAQ with online visualization proved to be very useful

#### But:

- Missing α-detector
  - Limiting for heavy systems
- Tape station has a free slot for such a detector
- Working on installation



#### Special thanks to Razvan Lica

#### Slide from S. Stegemann

199192








- Technical feedbacks since the last ISCC (mid-June)
- Summary of target production & Fast Tape Station
- RILIS highlights
- Coming YETS (Year End Technical Stop) and plans for 2022



## **RILIS operation 2021**









## LIST TISD October 2021

- Scheduled yield / contamination checks
  for multiple requested beams: Sn, In, TI, Ba, Yb, Ac
- Not successful due to failed connector coupling
  - Remotely identified via vector network analyzer device
  - Confirmed by visual inspection
  - Coupling modification ongoing, tbc in YETS







Slide from R. Heinke

199192





- Technical feedbacks since the last ISCC (mid-June)
- Summary of target production & Fast Tape Station
- RILIS highlights
- Coming YETS (Year End Technical Stop) and plans for 2022



## YETS 21/22 for the target area/separator zones and HV room

- Minimum required interventions for maintenance and repair:
  - Target transport (required before start of shutdown activities)
  - Frontend maintenance (extraction electrode exchange, greasing of movable parts, cleaning...)
  - Minimum vacuum intervention (pump maintenance needed every 2 years)
  - Ventilation system maintenance (two weeks with limited access possibilities)
  - Tests and maintenance of handling systems (robots & rail conveyor systems)
  - Consolidations (gas exhaust line, oil recovery) and maintenance in the HV room
  - Maintenance activities in the separator zones (laser windows exchange...)
  - Repair improvements following 2021 operational feedbacks



### 199192

#### YETS 21/'22 : key dates for the target area / low energy lines

- Saturday 8<sup>th</sup> of January: Target transport (required for shutdown activities)
- Shutdown activities (with accesses) until the Friday 28<sup>th</sup> of January
- 27<sup>th</sup> of January, DSO tests (re-validation of access and personnel protection safety systems)
- Ventilation maintenance from the 31/01 to the 14/02 (no accesses but hardware commissioning and stable beam possible)
- Water cooling back as of the 04/02: start of stable beam commissioning (no accesses to Faraday cages, HV room, separator zones)
- From 14/02 to 18/02 activities outside the Faraday cages (ventilation back)
- Installation of the SEMGRID target on GPS on the 17/02
- Monday 21th Feb: First protons to ISOLDE (BTY line commissioning)
- Commissioning with beam (protons) until March 14<sup>th</sup>: Start first Low E Physics



16

199192

#### YETS 21/'22 schedule: REX/HIE ISOLDE Key-Dates:

#### Cryo driven planning:

Cryo continuing over the annual Christmas break is unfortunately not possible: A study was carried out by Cryo, SRF, CV and EL and results presented at the IEFC meeting (26<sup>th</sup> March) and ISCC (16<sup>th</sup> June).

A full warm-up and cooldown cycle with the complications of a time consuming SRF reconditioning, and beam recommissioning will need to be carried out again this shutdown '21/'22.

#### Key-dates and planning drivers:


- End of protons to ISOLDE / End of HIE physics: 15<sup>th</sup> Nov
- Warm-up of the HIE SC linac starts on the 15<sup>th</sup> Nov and the following weeks
- Stop of all cooling water and lock-out power supplies as of the 10<sup>th</sup> Dec
- Cryo primary water back 26<sup>th</sup> Jan, all other as of 4<sup>th</sup> Feb -> Unlocking power supplies and start of Hardware Test period
- Cryo maintenance until 21<sup>st</sup> Feb followed by recommissioning of the plant.
  Cooldown of the Cryo Modules 24<sup>th</sup> March 27<sup>th</sup> April (possibly 1wk earlier)
- Cryo Modules 1-4 recommissioning and RF reconditioning at cold (4.5K) until 25<sup>th</sup> May
- Start of machine check-out and (stable) beam commissioning as of 25<sup>th</sup> May
- HIE ISOLDE (RIB) Physics start as of 20<sup>th</sup> July

	Task Name	Duration +	Start	Finish +	5 0	N	Half 1, 2022 Half 2, 2022 D J F M A M J J A S O N D
57	4 ISOLDE water stop 2021-2022		Fri 10/12/21	Fri 04/02/22			ISOLDE water stop 2021-2022
236	4 Shutdown 2021/2022	178 days	Mon 15/11/21	Wed 20/07/22		F	Shutdown 2021/2022
37	REX / HIE Vacuum	120 days	Mon 15/11/21	Fri 29/04/22		Г	REX / HIE Vacuum
44	Warm-up Procedure CMs	20 days	Mon 15/11/21	Fri 10/12/21			
54	Cryogenics maintenance	30 days	Mon 10/01/22	Fri 18/02/22			Cryogenics maintenance
57	Cryoplant commissioning	23 days	Mon 21/02/22	Wed 23/03/22			Cryoplant commissioning
61	Ready for Cooldown	0 days	Wed 23/03/22	Wed 23/03/22			Ready for Cooldown
62	Cooldown all CMs	4 wks	Thu 24/03/22	Wed 20/04/22			Cooldown all CMs
63	Cryo tests and tuning	5 days	Thu 21/04/22	Wed 27/04/22			Cryo tests and tuning
64	End of Cooldown	0 days	Wed 27/04/22	Wed 27/04/22			End of Cooldown
65	Recommissioning CM 1-4	70 days	Thu 17/02/22	Wed 25/05/22			Recommissioning CM 1-4
81	Survey activities	127 days	Mon 15/11/21	Tue 10/05/22			Survey activities
92	REX Low Energy	91 days	Fri 10/12/21	Fri 15/04/22			REX Low Energy
18	REX RF systems	126.5 days	Mon 29/11/21	Tue 24/05/22		I I	REX RF systems
30	BI activities	60 days	Mon 10/01/22	Fri 01/04/22			BI activities
33	EPC activities	5 days	Mon 07/02/22	Fri 11/02/22			[] EPC activities
35	# REX/HIE Check out and beam commissioning	118 days	Fri 04/02/22	Wed 20/07/22			REX/HIE Check out an
36	Hardware tests period	67 days	Mon 07/02/22	Tue 10/05/22			Hardware tests period
37	HEBT Check out start (without beam) (elements outside tunnel)	0 days	Fri 04/02/22	Fri 04/02/22			HEBT Check out start (without beam) (elements)
38	REXEBIS available for beam commissioning	0 days	Fri 15/04/22	Fri 15/04/22			REXEBIS available for beam commission
39	REXTRAP available for beam commissioning	0 days	Fri 15/04/22	Fri 15/04/22			REXTRAP available for beam commis
40	REX RF available for beam commissioning	0 days	Mon 25/04/22	Mon 25/04/22			REX RF available for beam commiss
41	Recommissioning CM1-4 finished	0 days	Wed 25/05/22	Wed 25/05/22			Recommissioning CM1-4 finish
42	Connect the CM vacuum valves (Beam Permit signed)	0 days	Wed 25/05/22	Wed 25/05/22			Connect the CM vacuum valves
43	End CM 1-4 recommissioning	0 days	Wed 25/05/22	Wed 25/05/22			End CM 1-4 recommissioning
44	REX/HIE Machine Check out and beam commissioning	40 days	Thu 26/05/22	Wed 20/07/22			REX/HIE Machine Chec
10	Course LUE Discusion	O dave	Wad 20/07/22	Wed 20/07/22			A Start HIF Physics



#### YETS 21/'22 schedule: REX/HIE ISOLDE activities:







Slide from E. Siesling



#### THANK YOU FOR YOUR ATTENTION





92<sup>nd</sup> ISOLDE Collaboration Committee meeting

## Target material development





Date: 2021-07-09

Operational Procedure

#### Production of nano-<u>LaOH</u> + multiwalled carbon nanotube powder pellets for ISOLDE target production


- Preparation of La(OH)<sub>3</sub>+MWCNT pills for nano-LaC<sub>x</sub> targets
- Glove box enclosure
  - Powder weighing and transfer
  - Pill pressing
- Planetary ball mill
  - La(OH)<sub>3</sub> particle size reduction
- Reactor setup
  - Wet dispersion mixing of La(OH)<sub>3</sub> and MWCNTs

Slide from <u>S. Stegemann</u>









- Procedure proved to be feasible
- > Waiting for final safety approval
  - Important step toward nano-UCx production

# Development and characterization equipment

Planetary ball mill – Powder particle size reduction



Laser diffraction particle size analyzer



Gas sorption – Pore size distribution





Carburization pumpstand

Target development, target sintering studies,...

Gas pycnometry - Apparent density determination

