



RFD Dressed Crab Cavities

Status, Issues and Delivery Dates

Leonardo Ristori – Fermilab

L2 Manager – RFD Dressed Crab Cavities Fabrication

11th HL-LHC Collaboration Meeting – 19th October 2021





U.S. RFD Team

US-HiLumi-doc-1055

Institutions in alphabetical order :


- Argonne National Laboratory (Brazing and Cavity Processing):
 - Mike Kelly, Tom Reid, Bill Toter
- Brookhaven National Laboratory (Coordination, Interfaces and MIPs):
 - Silvia Verdu Andres
- Fermilab (RF/Mech Design, Procurements, Cold Tests):
 - Paolo Berrutti, Manuele Narduzzi, Alex Melnichuk, Damon Bice
- Jefferson Lab (HOM Dampers Fabrication):
 - Naeem Huque
- Old Dominion University (General Oversight and RF measurements):
 - Jean Delayen, Subashini De Silva
- SLAC National Accelerator Laboratory (RF Design, Coordination):
 - Alessandro Ratti, Zenghai Li

	RFD Dressed Cavities Roles and Responsibilities	US-HiLumi-doc-1055 Date: 9/28/18 Page 1 of 5
		
US HL-LHC Accelerator Upgrade Project		
RFD Dressed Cavities Roles and Responsibilities		
Prepared by: L. Ristori, US HL-LHC AUP Crab Cavity L2 Manager, FNAL A. Ratti, SLAC Team Lead		
Accepted by: M. Kelly, ANL Team Lead Q. Wu, BNL Team Lead E. Daly, Jefferson Lab Team Lead J. Delayen, Old Dominion University Team Lead A. Ratti, SLAC Team Lead		
Reviewed by: P. Berrutti, US HL-LHC AUP Crab Cavity deputy L2 Manager, FNAL L. Ristori, US HL-LHC AUP 302.3 L2 Manager, FNAL R. Carcagno, US HL-LHC AUP Deputy Project Manager, FNAL		
Approved by: Giorgio Apollinari, US HL-LHC AUP Project Manager, FNAL		


*Roles & Responsibilities
Response to CD-1/3a recommendation*




Scope and Deliverables



Bare RFD Cavity



Dressed RFD Cavity
(front wall removed to show internal components)




RF Ancillaries


- **Project Scope includes 2 Prototypes + 2 Pre-Series + 10 Series**
- Bare Cavities: Intermediate Qualification at FNAL at 2K
- Integration: Bare Cavity + Magnetic Shields + Helium Tank
- Dressed Cavities: Final Qualification at FNAL at 2K + RF Ancillaries
- Transport to TRIUMF for acceptance by CERN:
 - 10 qualified dressed cavities (mix of pre-series + series)
 - Warm/Cold tests at TRIUMF → formal acceptance by CERN → hand-off

AUP Prototype #1 - Timeline


- 9/2020: Cavity received from Zanon
- 10/2020: RF inspection complete
- 12/2020: Metrology and optical inspections complete
- 1/2021: Bulk BCP and heat treatment
- 2/2021: Light BCP
- 3/2021: Flange issues and repairs
- 4/2021: HPR, assembly
- 4/21/21: Successful VTS test, achieved **4.2MV** (4.1MV requirement)



CMM Measurements at FNAL




RF Bead Pull at FNAL



Rotational BCP at ANL




VTS Preparations



Second Sound Instrumentation

Prototype #1 – Status and Plans


- “Somewhat” successful test exceeding acceptance requirements only marginally.
- Still under vacuum since April, we were awaiting results of Proto #2.
- Now it can be released for rework and will be shipped to Zanon for bulk rotational chemistry.



- 2 Goals for Prototype #1:
 - Improve performance of cavity
 - Validate Zanon facility as we transition to production

Flange Issues and Repairs

- Successful maintenance allowed to achieve leak tight connections and maintain momentum towards VTS.
- 4 cycles of high-pressure rinsing, assembly, evacuation and leak checking were needed.
- Received input from CERN on details of gaskets, hardware and procedures employed.
- Received one complete hardware kit shipped from CERN.
- Looks like we succeeded!




After maintenance


Leaks in Clean Room

AUP Prototype #2 - Timeline

- 12/2020: Cavity received from Zanon
- 2/2021: RF Inspection complete
- 3/2021: Metrology and optical inspection complete
- 4/2021: Leak check successful
- 5/2021: Bulk BCP, Heat Treatment
- 6/2021: Light BCP, HPR, leak issues, unsuccessful VTS
- 7/2021: HPR, leaks issues
- 8/2021: HPR, leak tight, successful VTS, achieved 5.8MV (4.1MV requirement)



Prototype #2 Successful Test 8/25/21




LARP Cold Tests Summary 2017-2019

Test Date	Cavity #	Location	HHOM	VHOM	Max Voltage	Q at 4.1MV
2/12/2017	LARP RFD#1	JLab	<input type="checkbox"/>	<input type="checkbox"/>	4.04	1.60E+09
3/23/2017	LARP RFD#1	JLab	<input type="checkbox"/>	<input type="checkbox"/>	4.38	8.21E+09
6/2/2017	LARP RFD#2	JLab	<input type="checkbox"/>	<input type="checkbox"/>	5.75	1.13E+10
8/20/2017	LARP RFD#1	FNAL	<input type="checkbox"/>	<input type="checkbox"/>	4.70	1.10E+10
4/30/2018	LARP RFD#1	FNAL	<input type="checkbox"/>	<input type="checkbox"/>	3.54	N/A
5/8/2018	LARP RFD#2	JLab	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	4.77	1.22E+09
5/31/2018	LARP RFD#2	JLab	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	5.03	1.32E+09
6/13/2018	LARP RFD#1	FNAL	<input type="checkbox"/>	<input type="checkbox"/>	3.47	N/A
8/16/2018	LARP RFD#2	JLab	<input checked="" type="checkbox"/>	<input type="checkbox"/>	5.26	6.60E+08
10/9/2018	LARP RFD#2	JLab	<input checked="" type="checkbox"/>	<input type="checkbox"/>	4.18	1.08E+09
11/14/2018	LARP RFD#2	JLab	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	5.50	5.00E+09
11/28/2018	LARP RFD#2	JLab	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	5.50	7.35E+09
3/27/2019	LARP RFD#2	JLab	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	5.33	6.50E+09
5/2/2019	LARP RFD#1	FNAL	<input type="checkbox"/>	<input type="checkbox"/>	5.10	1.00E+10

- 2 available LARP prototypes (RFD#1, RFD#2) exceeded Voltage and Q_0 requirements
- All 14 tests (with and w/o dampers) exceeded nominal voltage of 3.4MV
- Highest Q_0 achieved at 4.1 MV with dampers = $7.3 \cdot 10^9$ (~2x requirement)
- (A): Solved issues with RF losses in dampers
- (B): Removed surface defect causing early quench

LARP + AUP Cold Test Summary



Zanon – Resuming Fabrication after PRR



CERN Approval of MIP

- Zanon is (FINALLY!) cutting metal as we speak thanks to the approval of MIP →

1. Fabrication drawings

- approval ETA ~1 month

2. Weld test plan / Welding book

- approval ETA ~2 weeks

3. Manufacturing Procedures

- next slide

Holding productive 3-way meetings (FNAL-Zanon-CERN) to facilitate convergence.

2069490 v.6 ● Released 🔒 Restricted access Procedure
Manufacturing Inspection Plan - MIP by AUP Created on 2021-09-08
Last Modified on 2021-09-08

Info

Description: This folder contains the MIP (Quality Control Plan for Zanon) proposed by Zanon for the manufacturing of the preseries Crab Cavities. External reference: Keywords:

MIP Submitted by Zanon

Zanon		Document Code	Rev.	Page
		Z20008.QCP.001	2	1 of 66

Client	Fermi National Accelerator Laboratory	N° ordine	647590
Customer		Order No.	
Progetto	US HL-LHC Accelerator Upgrade Project	Disegno	3326.11.000.000
Project		Drawing	
Componente	RFD Crab Cavities	N° serie	NRF0xx
Component		Serial No.	
Titolo	QUALITY CONTROL PLAN - Pre-series fabrication-		
Title			

LIST OF ABBREVIATIONS

- M HOLD POINT** - the workflow is stopped until the quality records will be reviewed and approved by FNAL representatives and NCR are resolved. A feedback from FNAL shall be provided within 2 working days from submission of the records.
- N NOTIFICATION POINT** - FNAL representatives are informed that a specific step has been completed and that the following step in the approved workflow will be performed. A Notification Point does not affect the workflow. FNAL representatives' approval is non-mandatory.
- W WITNESS POINT** - FNAL representatives intend to attend the step of the production. Zanon FNAL will notify the Customer at least 10 working days in advance of the activity will be performed.
- R REVIEW AND APPROVAL** - the quality records (QA and QC documents and NCR) will be shared with the Customer for inspection and approval.

3					
2	Added notes at steps 16.3 and 16.19	07/09/2021	<i>A. Visentin</i>	<i>A. Grassie</i>	<i>L. Lotti</i>
1	Updated (where indicated with bold line) following customer comments	19/07/2021	A. Visentin	A. Grassie	L. Lotti
0	Issue for use	20/04/2021	A. Visentin	A. Grassie	L. Lotti
Rev	Emissione	Date	Redatto	Verificato	Approvato
	Issue for	Date	Issued by	Reviewed by	Approved by



Status of Procedures – Fast Recent Progress

Snapshot from ~1 month ago, now only 2 procedures remain to be approved!

Description Procedure	Procedure N.	Revision	Status	
Niobium Sheets	PO 657756	NA	QC Approved	
Niobium & Nb55Ti (Rods/Plates/Disks)	PO 671157	NA	QC Approved	
Niobium Tubes	PO 671490	NA	QC Approved	
RFD Crab Cavity Drawing Package	3326.1.000.000	1	Update Ongoing (ZRI)	
Welding Book	3326.W.001	NA	New version available after WPQR approval	
- section 1: Welding Map	3326.W.001	NA	New version available after WPQR approval	
- section 2: WPS	3326.W.001	NA	New version available after WPQR approval	
- section 3: Test Coupon (WPQR)	3326.W.001	4	Update Ongoing (ZRI)	
- section 4: WOPQ	3326.W.001	3	New version available after WPQR approval	
MIP – Pre-series (QCP @ ZRI)	Z20008.QCP.001	2	Approved	
Cleaning & Chemical Etching	Z20008.BCP	0	Approved*	* administrative update ongoing
Identification, Marking, Traceability	Z20008.IMT	0	Approved*	* administrative update ongoing
Radiographic Examination (RT)	Z20008.RT	0	Approved*	* administrative update ongoing
Radiographic Test Extent	NA	NA	Update Ongoing (ZRI)	
Manufacturing Sequence	NA	NA	Update Ongoing (ZRI)	
Helium Leak (LT)	Z20008.LT	0	Approved*	* administrative update ongoing
Dimensional Control	Z20008.DIM	0	Check Ongoing (CERN)	
Visual Inspection	Z20008.VT	0	Approved*	* administrative update ongoing
Packing Procedure	Z20008.SH	0	Check Ongoing (CERN)	
Grinding Procedure	ZGEN.GR	0	Check Ongoing (CERN)	

Zanon – Risks in Resuming Fabrication

- As of today, KEY documents and procedures are still not approved by CERN.
- AUP projections show that due to delays this year, we have consumed all float with respect to “late” delivery dates agreed with CERN (see final slide).
- In the interest of schedule, factoring the approved MIP, and extremely advanced stage of drawings, AUP decided to give OK to Zanon to start fabrication of 2x Pre-Series cavities.
- Approval was limited to cutting Niobium sheets and performing deep-drawing of Niobium components.
- Any activity is contingent on the approval of applicable procedures.





Nb sheet cutting at Zanon



RF Ancillaries Fabrication – Jlab




H-HOM Fabrication





H-HOM Hook & Tee EBW





V-HOM Feedthrough Brazing



H-HOM Feedthrough Brazing



H-HOM Metrology



Transition Plan: Prototypes, Pre-Series, Series

- LARP prototypes (2017-2019):
 - Validation of cavity design in achieving key performance requirements (e.g. deflecting voltage, quality factor).
 - Validation of FNAL/ANL facilities and processes for surface chemical processing, heat-treatments and cold test.
- AUP prototypes (2020-2021):
 - First development of fabrication process at Zanon.
 - First development of QA documentation.
 - Practice with CERN system for Manuf. Records & NCRs.
 - Confirmation of FNAL/ANL facilities and processes.
- **NOW** Validate Zanon facilities for processing.
- AUP Pre-Series (2021-2022):
 - Convergence with CERN on fabrication and QA documentation (DWGs, MIP, welding book, NCRs,..).
 - Validate fabrication process, including processing, at Zanon.
- AUP Series (2022-2023):
 - Repeat process of pre-series, deliver cavities to FNAL ready for VTS.

Niobium & Raw Materials Procurement

- Virtually all material for pre-series is already at Zanon. One last procurement imminent, plus some pieces for certain weld qualifications.
- All (83) Niobium sheets for series have been received from China. Inspection at FNAL completed. Accepted by CERN. Now verifying tensile and RRR properties.
- One last order of material for series (Niobium Tubes) not yet placed with Ningxia as negotiations on payment terms continue. Supplier requested 100% payment before shipment. FNAL proposing maximum 95% payment at acceptance of material certs and inspection reports and remaining 5% after receiving.
- QA contractor hired to tackle increased QA activities (for raw materials, and rest of scope as well).





Niobium Sheets for Series at FNAL



Helium Tanks

- Prototype magnetic shields were procured from Ad-Vance (U.S.) and are at FNAL.
- Helium Tank fabrication + welding: “lowest cost technically acceptable” proposal received from Zanon (Ita). Only other bid was received from Roark (USA).
- Contract with Zanon is imminent. Will include jacketing operations for 2x prototypes at this moment, a change order will be issued to add quantities for series.
- To allow a seamless transition to series in spring 2022, a final release by CERN of all drawings and supporting documents is needed by end of 2021, early 2022 at the latest.



Delivery Dates

- Deliveries are starting to fall outside the delivery window which was agreed with CERN before Covid. Dates will need to be re-negotiated prior to AUP rebaseline in April 2022.
- Delays are driven (A) by the additional work necessary to fully comply with CERN requirements prior to launching pre-series (~10mo); (B) Covid inefficiencies and impacts at suppliers are also affecting our schedule, to a smaller extent.

Cavity Delivery Dates with Current Plan of 1 bare cavity and 1 dressed cavity failure

	Agreed Early Delivery Date	August 2021 Status Schedule	Agreed Late Delivery Dates
Cavities 01 & 02	Jun-22		Jun-23
Cavities 03 & 04	Sep-22	May-23	Sep-23
Cavities 05 & 06	Nov-22		Dec-23
Cavities 07 & 08	Jan-23		Feb-24
Cavities 09 & 10	Mar-23		May-24

Cavity Delivery Dates with no failures

	Agreed Early Delivery Date	Success Oriented August 2021 Status Schedule	Agreed Late Delivery Dates
Cavities 01 & 02	Jun-22		Jun-23
Cavities 03 & 04	Sep-22	May-23	Sep-23
Cavities 05 & 06	Nov-22	Oct-23	Dec-23
Cavities 07 & 08	Jan-23		Feb-24
Cavities 09 & 10	Mar-23		Apr-23