

# Elettra Sincrotrone Trieste



# Status of FERMI upgrade, RF system development & test

Nuaman Shafqat

on behalf of

S-Band RF Systems Team



Nuaman Shafqat, 16/05/2022





#### □ What is FERMI

#### □ FERMI Upgrade

- Beam energy upgrade
- Beam quality upgrade

#### □FERMI linac

#### High Gradient module

- RF design
- □ Fabrication & testing of short prototype
- □ Fabrication & testing of full HG module
- □ High power S-band waveguide components
  - □ In-vacuum phase shifter
  - □ Spherical pulse compressor

#### □Summary and conclusions







# THE FERMI FEL

The **FERMI** linac-based FEL at the Elettra Laboratory (Trieste, IT) is an international user facility for scientific investigations in material science.

The electron bunches are produced in a laser-driven photo-injector and accelerated, with a **3-GHz, normal conducting Linac**, to energies up to **1.5 GeV**,





The FERMI facility comprises two separate coherent radiation sources, **FEL-1** and **FEL-2**.

FEL-1 operates in the wavelength range between 100 and 20 nm via a single cascade harmonic generation, while the FEL-2 is designed to operate at shorter wavelengths (20-4 nm) via a double cascade mechanism.





# THE FERMI LINEAR ACCELERATOR

The FERMI Linac is a S-Band (3 GHz), 1.5 GeV normal conducting, linear accelerator.



- ➢ Power Sources: 45 MW peak power, 4.5 µs pulse width, Klystron
- Linac 1 & Linac 2: one klystron feeds two FTW accelerating structures
- Linac 3 & Linac 4: one klystron feed one BTW accelerating structure

In order to reach a beam energy of **2.0 GeV**, all the BTW structures will be replaced & all the CERN sections will be pushed to higher gradient operation





## THE FERMI FEL UPGRADE PLAN BEAM ENERGY UPGRADE

- To reduce pulse duration to the sub-10 fs range to resolve charge transfer processes, bond dynamics, vibrational dynamics
- □ To extend photon energy range to N (410 eV), O (543 eV) which translates to the extension of operating of FERMI to ~2 nm.





# FERMI LINAC UPGRADE PALN ACC. SECTIONS TO BE REPLACED

#### **CERN Sections**

- Developed as injector of LEP
  Injector Linac (LIL) in 1984
- One 45 MW klystron feeds two 4,5 m CERN sections.
- □ Accelerating gradient is **12,6 MV/m**.
- Three out of seven CERN sections would be replaced by HG structures

| Parameter            | S0A-S0B     | C1-C7       | S1-S7        |
|----------------------|-------------|-------------|--------------|
| Mode                 | TW2/3 $\pi$ | TW $2/3\pi$ | BTW3/4 $\pi$ |
| Frequency (MHz)      | 2998.01     | 2998.01     | 2998.01      |
| Total length (m)     | 3.2         | 4.5         | 6.15         |
| Filling time (µs)    | 0.903       | 1.5         | 0.757        |
| Attenuation (Np)     | 0.603       | 0.7         | 0.611        |
| Acc. gradient (MV/m) | 15.8        | 13.1        | 23.6         |
| Energy gain (MeV)    | 50          | 60          | 145          |

ISO 9001 OHSAS 1800

**BUREAU VERITAS** 



#### S0a and S0b Sections

- Came from the old Elettra injector.
- One 45 MW klystron feeds two 3,2
  m S sections.
- □ Accelerating gradient is **15,0 MV/m**.
- Both S0a and S0b would be replaced by HG structures

#### **Backward Travelling Wave Sections**

- Designed specifically for FERMI
- Each BTW section is fed by 45 MW klystron followed by SLED.
- Suffer from frequent breakdowns and are limited to 18,0 MV/m at 50 Hz
- All seven would be replaced by HG structures



) HG2022, 16-19 May 2022



# THE FERMI UPGRADE PROPOSAL

#### TO EXTEND THE RANGE TO SHORTHER WAVELENGTH UP TO 2 nm



HG2022, 16-19 May 2022

BUREAU VERITAS

Nuaman Shafqat, 16/05/2022



## **NEW ACCELERATING MODULE**

- The new accelerating module will be comprised of 3.0 m long, constant gradient type structures. Double rounding is introduced to reduce Ohmic losses and increase Q
- A customized version of dual-fed-electric coupled (EC) coupler is chosen for the new high gradient (HG) structures
  - □ Very low surface magnetic field
  - Easy to machine
  - Reduced cost of fabrication

| Structure RF Parameters |                           |       |  |
|-------------------------|---------------------------|-------|--|
| L                       | 2988.3 mm                 |       |  |
| N <sub>cell</sub>       | 84                        |       |  |
| а                       | $11.13 \rightarrow 8.8$   | mm    |  |
| R <sub>sh</sub>         | $72.07 \rightarrow 80.70$ | MΩ/m  |  |
| $Q_0$                   | 15850                     |       |  |
| Filling Time            | 644.8                     | ns    |  |
| Attenuation             | 0.383                     | Neper |  |
| ISO 9001                | 7                         |       |  |

BUREAU VERITAS

HG2022, 16-19 May 2022

| Coupler RF Parameters       |               |                |  |  |
|-----------------------------|---------------|----------------|--|--|
|                             | Input Coupler | Output Coupler |  |  |
| E <sub>surf</sub><br>[MV/m] | 78            | 82             |  |  |
| H <sub>surf</sub><br>[kA/m] | 69            | 71             |  |  |
| S <sub>c</sub><br>MW/mm²]   | 0,47          | 0,39           |  |  |
| k <sub>q</sub><br>[V/ms]    | 1956          | 1319           |  |  |





#### Nuaman Shafqat, 16/05/2022

C. Serpico, N. Shafqat, A. Grudiev, and R. Vescovo, "High gradient high reliability, and low wakefields accelerating structures for the FERMI FEL", Review of Scientific Instruments, vol. 88, p. 073303, 2017

hafqat, S. Di Mitri, C. Serpico, and S. Nicastro, "Design study of high gradient, low impedance accelerating structures for the FRRMI free electron laser upgrade", Nuclear Instruments and Methods in Physics Research A, vol. 867, pp. 78-87, 2017



Bandwidth

40.00

-50.00

60.00

# **RF ANALYSIS OF FULL HG** STRUCTURE (3.0 METER)



7500

-6000.0

10

8000 0



# **PSI PROTOTYPE FACTORY ACCEPTANCE TEST**

- □ To prove the reliability and the feasibility of the upgrade plan, a short prototype has been built in collaboration with Paul Scherrer Institute (PSI).
- □ The prototype is realized using the same structure technology as developed for SwissFEL
- The prototype is made by 7 regular cells & 2 EC-couplers.
- Cells & couplers are realized with ultra-high precision with tolerance of  $\pm/-4\mu m$ .
- Prototype is machined on tune.





#### Nuaman Shafqat, 16/05/2022

11



# FERMI CAVITY TEST FACILITY

FERMI linac stations hot spare, has been upgraded to act also as a complete S-Band RF Cavity Test Facility (CTF)







# FERMI CAVITY TEST FACILITY

FERMI linac stations hot spare, has been upgraded to act also as a complete S-Band RF Cavity Test Facility (CTF)







#### **COMPLETE CONDITIONING HISTORY**

| Acc. Gradient<br>(MV/m) | PWR @ Ptype<br>(MW) | Start Date | End Date   | # of Pulses<br>(Million) | BDR<br>(bpp)        |
|-------------------------|---------------------|------------|------------|--------------------------|---------------------|
| 30                      | 72                  | 01-06-2018 | 07-11-2018 | 225                      | $2.0 	imes 10^{-8}$ |
| 35                      | 98                  | 30-01-2019 | 21-05-2019 | 229                      | $7.3 	imes 10^{-8}$ |
| 39 <sup>*</sup>         | 122**               | 31-08-2019 | 19-12-2019 | 400                      | $7.9 	imes 10^{-8}$ |



\*Original target was 40MV/m acc. Gradient \*\* Maximum available power at prototype with full power from Klystron



During the **Spring Shutdown (April 2018)** the prototype was installed in FERMI Test Facility.





#### COMPLETE CONDITIONING HISTORY PLOT







#### COMPLETE CONDITIONING BREAKDOWN LOCATIONS





#### FIRST HG STRUCTURE LOW POWER MEASUREMENTS





During the Spring Shutdown (April 2022) the HG structure was installed in FERMI Test Facility.
 Preliminary power tests were performed and all diagnostic was properly setup.









MATLAB conditioning plot (Power curve)













BUREAU VERITAS Certification

#### **FIRST HG STRUCTURE C**ONDITIONING



Nuaman Shafqat, 16/05/2022





- Breakdown detection problem
- PXI is triggered by signal from Faraday cups installed at each end of structure
- Not a single breakdown is detected by PXI
- Detection system was benchmarked during the conditioning of short prototype and worked well
- At higher power levels "Reflected Power interlock" installed at the output of klystron is triggered times and again

Water Load

Water Load

Vacuum Pump

Vacuum Pump



Farady Cup #2



#### **IN-VACUUM PHASE SHIFTER**







|                    | Value   | Units  |
|--------------------|---------|--------|
| f <sub>0</sub>     | 2.99801 | GHz    |
| Bandwidth @ -30 dB | 15      | MHz    |
| VSWR               | <1.05   |        |
| Insertion loss     | 0.1     |        |
| Phase Range        | ±200    | Degree |
| Max Peak Power     | 45      | MW     |
| Max Average Power  | 10.125  | W      |

Nuaman Shafqat, 16/05/2022



### **IN-VACUUM PHASE SHIFTER**















Nuaman Shafqat, 16/05/2022

https://media.mcam.com/fileadmin/quadrant/documents/QEPP/Global/English/Product\_Data\_Sheets\_AEP/Ketron\_GF30\_PEEK\_PDS\_GLOB\_E\_19092016.pdf



# Sincrotrone

## **IN-VACUUM PHASE SHIFTER CONDITIONING...**



Elettra

Trieste

#### 3<sup>rd</sup> run

#### Vacuum issue

- Baking out of plastic
- Replacement of metal screws with plastic ones.
- □ Spacers were introduced between copper choke & the plastic to avoid virtual leak.





### IN-VACUUM PHASE SHIFTER POST CONDITIONING ANALYSIS







# **RF PULSE COMPRESSOR**











ISO 9001 OHSAS 18001 BUREAU VERITAS Certification 

|                      | arametere |      |
|----------------------|-----------|------|
| f <sub>0</sub>       | 2.99801   | GHz  |
| Nominal Temperature  | 35        | °C   |
| Mode                 | TM13      |      |
| Q0                   | ≈140000   |      |
| Coupling Coefficient | 7.2±0.1   |      |
| E @ 45 MW            | 28.16     | MV/m |
| H @ 45 MW            | 169.75    | kA/m |

**RF** Parameters





Nuaman Shafqat, 16/05/2022



## **RF PULSE COMPRESSOR LOW POWER MESUREMENTS**









#### **Conditioning of HG prototype**

• Successful conditioning of HG prototype at Cavity Test Facility of Elettra up to an accelerating gradient of 40MV/m with break down rate of  $7.9 \times 10^{-8}bpp$ .

#### Conditioning of 1<sup>st</sup> 3,0m HG structure

• First 3,0m HG structure is installed at Cavity Test Facility of Elettra and is under conditioning from **28 April 2022**.

#### S-Band In-Vacuum Phase Shifter

 Successful design, fabrication and high power testing of S-Band In-Vacuum Phase Shifter up to RF power of 50 MW with pulse width of 1000 ns

#### **S-Band Spherical Pulse Compressor**

• Low power measurement done after successful brazing of Spherical Pulse Compressor.





# NEXT STEPS AND TIME SCHEDULE

#### Full HG module timeline...

- By August 2022, 2<sup>nd</sup> HG structure would be fabricated and shipped to Elettra.
- During **Summer 2022 shutdown full HG Module** would be installed in FERMI tunnel in place of one accelerating section and deflecting cavity (K15) for operation with beam.

#### Layout of HG module in FERMI Tunnel



#### Spherical Pulse Compressor...

- In the **last week of May 2022**, Spherical pulse compressor would be installed at Elettra for tuning and low power measurements at the right temperature.
- During the shutdown of **Summer 2022** Spherical Pulse Compressor would be installed at Cavity Test Facility for conditioning and high power testing





#### ACKNOWLEDGEMENTS



Special thanks to ...

- □ Mauro Trovo, Luca Giannessi, Claudio Masciovecchio, Michele Svandrlik FERMI, Elettra
- □ Walter Wuensch, Alexej Grudiev CERN
- □ X-box Team, Ben Woolley, Joseph Tagg CERN
- □ Hans Braun, Alessandro Citterio, Markus Bopp, Paolo Craievich Paul Scherrer Institut (PSI)



# Thank you!









www.elettra.eu