LST Project Status



FACULTÉ DES SCIENCES



D. Della Volpe on behalf the LST collaboration 12th of January 2022 CTA Swiss Day

Credits:M. Nöthe



LST Collaboration









in the second second		Members	Scientist	Authors
gras sand	Bulgaria	3	3	3
	Brazil	3	2	2
and the second se	Croatia	13	13	13
and the second	Czech Rep.	15	15	9
	France	37	16	18
	Germany	34	27	27
	India	2	2	2
A Standard and and and and and and and and and an	Italy	55	46	36
	Japan	73	69	54
	Poland	2	2	2
Contraction of the second s	Spain	77	42	49
	Switzerland	13	12	12
	Total	327	249	227

D. della Volpe | CTA Swiss Day | 2022-01-12



The Swiss scientists' role in LST





UNIGE DPNC:

 System engineering with main focus on CDR follow-up

cta chreenay telescope srey	LST CRITICAL DESIGN R Declaration of CDR Pass	EVIEW	CTA-CER-L
	Declaration	of CDR Pass	
	for passing the CDR given is pleased to confirm that the		
СТАС) declares the LST Critic	al Design Review	as passed
	forward to the successful co 3 and the acceptance of LS		
	oking forward to the producceptance and integration in		
Eh	Tere		In
Federico Ferrin CTAO Managin		Masahiro Teshima LST Principle Invest	tigator



UNIGE DPNC/EPFL/ ETHZ

- Project coordination
- R&D activities on sensor, front-end electronics and digital readout


D. della Volpe | CTA Swiss Day | 2022-01-12


A tough Year

- COVID break-in
 - Need to react and re-adjust all activities
- A major incident: Mirror detachment
 - On March, a mirror in the middle of the dish, detached
 - The first analysis pointed to a single failure,
 - Later confirmed by a series of test performed by the optics group
 - Some identified non-conformity will be corrected
 - Silicon protection of the glue to be corrected
 - Change washer size for the safety bolt

And in the end









Volcano Eruption

- On 21st of September the volcano Cumbre Vieja erupted
- The longest eruption since last 700 years
 - Major damages to the island, thousand of house destroyed, road, infrastructure
 - Now people, can finally rebuild and recover
 - It will be a long process
- Significant ash fall-out
- In last days, high concentration of SO₂ in the air
 - Dangerous for people
 - With water can create acid H₂SO₄




















LST project status Overview

► CDR

- Progress in all area.
- An important Milestone was achieved with the visit by CTAO on site.
- The decision on last Software array trigger (SWAT) is shifting its closing see ACADA matters
- Commissioning
 - Many improvement but Volcano eruption imposed a substantial break
 - Finally restoring the telescope these days
 - ACADA release 1 integration in LST1 in preparation
- Operations
 - Quite smooth and regular until Volcano eruption
 - A good quantity of data recorded, most of which of very good quality
 - See analysis result delivered this year
- LST2-4 construction
 - Steady progress on the tenders managed by IAC and contributors from the different countries Some delay introduced by the bureaucracy related to permits and licences











LST CDR

- Major progress in all areas
- Activities agreed could be completed by Q2 2022
- A meeting in coming weeks with CTAO SE to agree on the formal steps for closure

Title

CDR is first step towards **CTAO** acceptance of LST

Most of the result of these activities, set the basis for IKC

- What is a product (Requirements)
- If it meets expectation (Verification, RAMS)
- How much will it cost to maintain it (RAMS, Maintenance)
- If it safe according to CE rules
- It will integrate correctly (Interfaces)




Title	% completed	01	2020	0.1		2021		022
Global Plan revision 2022	77.75 %	Q1 0	Q2 Q3	Q4	Q1 Q2	Q3 Q4	Q1 Q2	Q3
RAM Planning	60.63 %							~
Revision of LRU/LLRU list	100.00 %				LST-SE			
Definition of LRU/LLRU	100.00 %				LST-5			
FMEA Report	99.88 %						LST-SE	
Reliability Analysis	53.33 %					-		
Revision of current reliability analysis	75.00 %					LST-SE		
Collection of available reliability data per LRU	35.00 %						LST-SE	
Complete collection reliability data/estimations	50.00 %							-SE
Reliability report							LST-	SE
Maintenance analysis	23.22 %						, , , , , , , , , , , , , , , , , , ,	
Revision of the maintenance plan	50.00 %			_		LS	T-SE	
Collect and analyse existing commissioning data	80.00 %						LST-SE	
Perform maintenance Analysis	21.43 %							LST-SE
Maintenance analysis								LST-SE
Condition Monitoring	51.22 %						LST-SE	
Requirement and Verification	91.04 %							
Kick-off meeting	100.00 %		LST-SE; C). Schnurr; V. Mo	ontes			
Revision of CTA Level-B Requirement concerning LST	100.00 %		+	LST	SE			
Requirement Flow-down Link Level-B & Level C	100.00 %					LST-SE		
Revision of LST Level C/Specification	100.00 %			,		LST-SE		
Level C/D documentation ready	100.00 %					Ļ		
Revision of Level-B Verification procedures	70.00 %					LST-SE;	O. Schnurr; V. Montes	
Verification matrix ready						Ļ		
CE Certification	89.37 %							
Project breakdown in components	100.00 %	K.Tegel; L	ST-SE					
Documentation Evaluation	100.00 %		ST-SE; K.Tegel					
Define global plan	100.00 %	~ -	J					
Risk Register compilation	100.00 %		*		LST-SE; K.Tegel			
Hazards analysis	100.00 %				K.Tegel;	LST-SE		
Report on Hazard analysis	100.00 %				LST-S	E		
SIL Hazard Analysis	100.00 %							
Visit on site	100.00 %					- LST-SE; K.Teg	gel	
Evalution of Mitigation action	80.00 %					LST-SI	; K.Tegel	
Definition of timeline for implemetation						l	LST-SE	
Preparation of the Documentation (procedures & manual, final check of drawiings, etc)	75.00 %						LST-SE	
Ready for Final Review								
INFRA LST ICD Planning	59.06 %							
LST-INFRA External Identification Definition Document	59.06 %							
Klck-off Call	100.00 %	\diamond						
LST MECHANICAL INTERFACE (MEC) Identification	100.00 %			LS	T-SE; C. Montanari; N. V	Whyborn; O. Schnurr		
LST-INFRA MECHANICAL (MEC) ICD								<mark>. ۸</mark> ر
LST SUPPLIED SERVICES INTERFACE (SSi) Identification	100.00 %			LST-SE	; C. Montanari; N. Whyl	born; O. Schnurr		
LST SUPPLIED SERVICES INTERFACE (SSi) ICD								C.
INFRA ICD LST ready								₩ ↓

D. della Volpe | CTA Swiss Day | 2022-01-12



Requirements and verification









Requirements and verification

- An excellent and tremendous job done over the year by M. Heller and M. Will (now M. Stodulska will take over M. Heller)
 - More than 1000 of requirements and specification analysed
 - Flow-down of the requirement from Level-B up to Level-D
 - Delivered to CTA in the end of 2021, now under scrutiny
- A dedicated 2-days meeting will be organised by S. Stanghellini (CTAO) to go together through it and validate the work
- Next steps
 - Verification plans based on this revision of requirements
 - Discussions are already on-going with CTAO to define the format and template to be used
 - A big part of the verification methods have been already checked during last year's work





- **Requirements** define what an LST product is
- **Verification** checks that the design and realisation match.


Swiss Day 2022-01-12 9 D. UCHA VOIPC





RAM - Reliability, Availability & Maintenance

- This activity was behind schedule, suffering lacking of man power.
- Since the Hiring of M. Stodulska, on August, there was an impressive boost
 - Also another 0.5 FTE were provided by INFN/INAF with E. Giro, now part of the SE team.
- We are finalising the FMEA these days to be discussed with CTAO for its blessing and to close this deliverable.
- In parallel, reliability analysis is on going and its quite advanced.
- We are quite confident to complete this work before the end of Q2-2022







- detection of failures in the early stages of design;
- ➡optimization of the maintenance schedule;
- ➡identification of equipment priorities on failures;
- ⇒allocation of adequate spares.

Important for IKC Contributors Operation costs Spare parts Long term Support







Conformity with European health, safety, and environmental protection standards


Few procedures to be written but the overall analysis is considered complete

#	Title	%	Expected End	Q1 / 2020	
		completed		01 02 03	
0	CE Certification	89.37 %	23 Mar 2022		
1	Project breakdown in components	100.00 %	6 Feb 2020	🔶 К.Тес	
2	Documentation Evaluation	100.00 %	17 Apr 2020		
3	Definition of the documentation for each subsystem	100.00 %	3 Feb 2020		
4	Provide Existing Documentation	100.00 %	21 Feb 2020	🖵 ני	
5	Evaluation by CTAO	100.00 %	17 Apr 2020		
6	Define global plan	100.00 %	20 Apr 2020		
7	Risk Register compilation	100.00 %	25 Jan 2021		
14	Hazards analysis	100.00 %	24 Mar 2021		
15	Report on Hazard analysis	100.00 %	24 Mar 2021		
16	SIL Hazard Analysis	100.00 %	28 July 2021		
17	Visit on site	100.00 %	30 Aug 2021		
18	Evalution of Mitigation action	80.00 %	29 Oct 2021		
19	Preparation of documentation	85.00 %	3 Sep 2021		
20	Definition of the Mitigation action	75.00 %	29 Oct 2021		
21	Definition of timeline for implemetation		21 Jan 2022		
22	Preparation of the Documentation (procedures & manual, final check of drawiings, etc)	75.00 %	23 Mar 2022		
23	Ready for Final Review		23 Mar 2022		

The last missing milestone was the visit on-site of CTAO, which happened in September 2021, few days before volcano eruption.



Though this is a 'living' object and it is continuously revised, for CDR closing, the work done so far is considered finished.








Visit at ORM 1-8 Sep. 2021

- It was very successful and prolific
- A deep inspection of the LST1
 - CE compliance findings confirmed by K. Tegel
 - S. Stanghellini satisfied with the project status
 - Later S. Haid, CTAO Director of Administration
- Reaffirmed an optimal cooperation with CTAO














D. della Volpe | CTA Swiss Day | 2022-01-12 12





Visit at ORM 1-8 Sep. 2021

- In also identify possible improvements on
 - Foundation Crack
 - Implementation of Lightning **Protection system**
 - Cable routing in some places









D. della Volpe | CTA Swiss Day | 2022-01-12 13





ACADA - SWAT decision

- Spotted an incoherence between original Array trigger architecture (2017) and the Data model (2021) IST & NectarCam build their Event Builder (EVB) according to the specification and design given by CTA in 2017
 - **(SWAT-2)**
 - The R1 Data model, recently approved, instead is not compliant with that original design and requires a different trigger scheme. (SWAT-1)
- No consensus was found to decide between the 2 schemes
 - For LST both trigger schemes are fine
 - For ACADA both implementation were fine,
 - start discussion with all project to compose this discrepancy
 - It was not possible to achieve a shared view (Flashcam and SST objected)
- A formal process was started
 - A memorandum was prepared from all projects with preferred option and impaction term of time/money/performance
- CTAO decide to go for SWAT-1
 - EVB for NectarCam has to be changed
 - LST and NectarCam have the same EVB so we need to go together
 - The performance can be affected







LST will evaluated the SWAT-1 solution with a new EVB.

If performance not achievable, or LST performance not fully exploitable re-discussion shall happen









ACADA release 1 test in LST

- ACADA release 1 will be tested in LST in 2022
- Regular bi-weekly meeting between ACADA and LST developer team
 - It was agreed that SE will not follow this as being purely technical
 - Where decision is to be agreed, it will be discussed in the bi-weekly meeting between ACADA - LST SE
- The SWAT-1 decision impacts the timeline, but LST wants to test the final system (with new EVB) even if there could be performance issue.
- A detailed plan with deliverable and milestones is being produced in collaboration between ACADA and LST












LST-1 commissioning



- Data processed at dedicated on-site IT center contributed by U-Tokyo



https://pos.sissa.it/395/872

D. della Volpe | CTA Swiss Day | 2022-01-12 16




cta



Telescope Control Unit (TCU)

- TCU became our main operator interface to control LST
 - Still many minor issues
 - Better error detection, including subsystems' health checks
 - Better handling of edge cases, automatic error resolution (if possible) and reporting
- These are not pure TCU software related issue
 - Many software agents running providing information to TCU
 - Error handling specific to each subsystem
 - efficiency and stability





More harmonised approach among all evolved agents to reach the desired level of






Volcano

- On 21st September the volcano Cumbre Vieja erupted
- Even if ORM is more that 20 km away and at higher altitude respect to eruption sites, we are affected by volcano activity
- Significant ash fall-out
 - Slightly paramagnetic (Motors, magnetised part)
 - Not highly volatile, cover is effective
 - No major problem of clogging of filters for chiller, air conditioning.
 - Greasing of elevation chain and azimuth rails affected
 - It will be needed to remove it and re-greased them
- Daily cleaning by Casana to avoid accumulation
- Since November, high concentration of SO₂ in the air.
 - Dangerous for people
 - With water can create acid H₂SO₄






Volcano

- On 21st September the volcano Cumbre Vieja erupted
- Even if ORM is more that 20 km away and at higher altitude respect to eruption sites, we are affected by volcano activity
- Significant ash fall-out
 - Slightly paramagnetic (Motors, magnetised part)
 - Not highly volatile, cover is effective
 - No major problem of clogging of filters for chiller, air conditioning.
 - Greasing of elevation chain and azimuth rails affected
 - It will be needed to remove it and re-greased them
- Daily cleaning by Casana to avoid accumulation
- Since November, high concentration of SO₂ in the air.
 - Dangerous for people
 - With water can create acid H₂SO₄





SO2




D. della Volpe | CTA Swiss Day | 2022-01-12 18





LST-1 early physics results

https://pos.sissa.it/395/806



- Detection of Crab nebula, Crab pulsar and several known AGN up to z~0.5 (Mrk 421, Mrk 501, 1ES1959+650, 1ES0647+250, PG1553+113)
- First LST-1 ATel: BL Lac flare on July 11th 2021, <u>ATel #14783</u>
- Higher-level spectral analysis using Gammapy: gammapy.org










LST-1 and the MAGIC telescopes



Cross-calibration based on the observation of the same showers[‡] First joint stereoscopic observations ongoing (better shower reconstruction, but energy threshold driven by MAGIC's)

UNIVERSITÉ DE GENÈVE FACULTÉ DES SCIENCES *<i>‡Events coincidence done with a software timing based on timestamps*



https://pos.sissa.it/395/724

D. della Volpe | CTA Swiss Day | 2022-01-12 20








LST2-4 Construction

Excellent progress in Tenders and procurements











D. della volpe | CTA Swiss Day | 2022-01-12 21

LST2-4 Construction

					2022		2023
	Task Mana	Durat	Canal	Quarter	1st Quarter	3rd Quarter	1st Qu
1	Sign Contract for Short Project	0 days	01.08.19				
2	Basic project ready for submission	0 days	16.01.20				
3	All Permissions granted	0 days	14.02.22		▶ 14.02		
4	Sign civil work contract	0 days	08.04.22		A 08	.04	
5	Civil Works start	0 days	12.05.22		+	12.05	
-	LST2 construction starts	0 days	17.10.22				7.10
7	LST2 dish and structure united	0 days	03.07.23				
8	LST2 CSS installed	0 days	16.10.23				
9	LST2 mirrors installed	0 days	08.02.24				
10	LST2 camera installed	0 days	23.05.24				
11	LST2 construction completed	0 days	17.06.24				
12	LST2 ready for acceptance	0 days	13.10.25				
15	LST3 construction starts	0 days	14.11.22			P4	14.11
14	LST3 dish and structure united	0 days	16.10.23				
15	LST3 CSS installed	0 days	05.02.24				
16	LST3 mirrors installed	0 days	16.05.24				
17	LST3 camera installed	0 days	16.07.24				
18	LST3 construction completed	0 days	08.08.24				
19	LST3 ready for acceptance	0 days	04.12.25				
20	LST4 construction starts	0 days	12.12.22			M	12.12
21	LST4 dish and structure united	0 days	19.02.24				
22	LST4 CSS installed	0 days	27.05.24				
23	LST4 mirrors installed	0 days	05.09.24				
24	LST4 camera installed	0 days	31.10.24				
25	LST4 construction completed	0 days	25.11.24				


This schedule has contingency, but there are also uncertainties that can impact







- ➡ Administrative issues in La Palma
- → Pending authorisation by **Spanish ministry (MCINN)**



2025

3rd Quarter

1st Quarter

Permission+Civil W

3rd Quarte

2024

1st Quarter

3rd Quarter

Quarter

D. della Volpe | CTA Swiss Day | 2022-01-12 22





What's next?

- The project going well despite COVID and Volcano
 - Physics results are confirming the performance is very good!
- Missing manpower in SE team: filled by INAF/INFN and UNIGE!
- We have ahead a tough year
- Restarting activities after volcano stopped
 - Deep cleaning needed Worries for Motors
 - Re-greasing of exposed parts
- SWAT-1 solution now will be setting the timeline
 - New EVB will Impact
 - CDR activities
 - Data taking
 - ACADA release integration
- Start discussing with CTAO a plan towards Acceptance
 - → also a recommendation from STAC in this direction
- LST2-4 construction

Swiss contribution is in critical areas: SysEng, TCU, Analysis. It is well recognised in the collaboration





D. della Volpe | CTA Swiss Day | 2022-01-12 23







