ISOLDE Technical Report

J. Vollaire on behalf of technical and operation teams

Slides from: K. Chrysalidis, R. Heinke, E. Siesling and S. Stegemann









- Status of the facility since the last INTC (June)
- Summary of target production & Fast Tape Station
- RILIS highlights
- Coming Year End Technical Stop and plans for 2022









Technical Highlights (problems & feedbacks)

- Excellent performances and availability of systems (new Frontends)
- New irradiation station at GPS tested successfully yesterday
- Technical problems could be addressed promptly thanks to the availability and commitments of experts:
 - Problem with the cooling and sensor for the HRS FE Turbo pumps
 - BTY line (proton beam line) vacuum leak
 - GPS FE: FC door opening, target clamping piston, extraction electrode movement
- · Preventive maintenance will account for failures observed during the run










Some Technical Highlights

- Irradiation of target #635 (UCx) located after the online target (#627 tantalum)
- HV compatibility and radiation protection measurements
- Target #635 will be irradiated all week and used for the winter physics program



Remote visualization prior to human intervention **Preventive maintenance Repair** *











- Status of the facility since the last INTC (June)
- Summary of target production & Fast Tape Station
- RILIS highlights
- Coming Year End Technical Stop and plans for 2022










Target production operation 2021

Target production:



ISOLDE on-line operation

- All ISOLDE targets went online
- Additionally, 8 'old' targets have been recuperated
- UC₂C was produced from pre-made charges prepared in 2020 and stored
 - 10 carburized
 - 5 un-carburized











Feedbacks target production & operation

- Pre-making UC₂C charges worked overall well!
 - Possibility to better distribute production workload
- Prolonged outgassing in some cases (and other older targets)
 - Issue since outgassing & carburization pump stands not available
 - Working on re-installation and readiness for 2022
- For none actinide, some more complex materials (eg CaO, Y₂O₃) required dedicated setups, space and time

Pump stand in new lab





CaO production

(Decarbonation setup to transport in inert atmosphere to glove box)















glove box required to load O₂-sensitive materials nano-target development




Fast Tape Station (installed during LS2)

- New fast tape station works very well!
- Equipped with:
 - In-beam detector
 - 4π β-detector
 - γ-detector
- Transport time ~100 ms!
- DAQ with online visualization proved to be very useful

Next step:

- Missing α -detector
 - Limiting for heavy systems
- Tape station has a free slot for such a detector
- Working on installation



Electronics
(HV and preamp)

Final configuration (June 2021)

P2 position:
HPGe γ-ray

ISOLDE Fast Tapestation

Special thanks to Razvan Lica

Slide from S. Stegemann







detector



- Status of the facility since the last INTC (June)
- Summary of target production & Fast Tape Station
- RILIS highlights
- Coming Year End Technical Stop and plans for 2022







RILIS operation 2021



- No major pump-laser failures this year!


Elements: Ag, Mg, Cu, Ca, In, Au, Ac, Zn, Pb*, [

Sb, Dy, Sc, Be

- physics runs: 17

TISD runs*: 4

→ Overall <u>21 weeks out of 23 weeks of ISOLDE</u> operations



- New Pb laser ionization scheme
- Developed Jan 2021 (Master thesis R. Mancheva, Sofia university)
- First used on-line Sep 2021
- Efficiency enhancement by factor 10!



- TISD on Actindes extraction for LISA student projects
- Many actinide schemes tested on-line
- Np, Pu, Ac were seen!
 - Additionally molecular extraction tested

Slide from K. Chrysalidis







70548.67 cm⁻¹

867.292 nm

217.068 nm

11530.14 cm⁻¹

59819.7 cm

57598.6 cm⁻¹


46068.44 cm⁻¹


LIST TISD October 2021





- Scheduled yield / contamination checksfor multiple requested beams: Sn, In, Tl, Ba, Yb, Ac
- Not successful due to failed connector coupling
 - Remotely identified via vector network analyzer device
 - Confirmed by visual inspection
 - Coupling modification ongoing, tbc in YETS


Laser Ion Source and Trap (LIST)











Slide from R. Heinke









- Status of the facility since the last INTC (June)
- Summary of target production & Fast Tape Station
- RILIS highlights
- Coming Year End Technical Stop and plans for 2022









YETS 21/22 for the target area/separator zones and HV room

Minimum required interventions for maintenance and repair:

- Target transport (required before start of shutdown activities)
- Frontend maintenance (extraction electrode exchange, greasing of movable parts, cleaning...)
- Ventilation system maintenance (two weeks with limited access possibilities)
- Tests and maintenance of handling systems (robots & rail conveyor systems)
- · Consolidations (gas exhaust line, oil recovery) and maintenance in the HV room
- Maintenance activities in the separator zones (laser windows exchange...)
- Repair improvements following 2021 operational feedbacks







YETS 21/'22 schedule: REX/HIE ISOLDE activities



HEBT:

- Stripping foils to be installed during summer '22 and depending on required beams
- Optimization of the overall alignment of the HEBT elements done last year Experiments:
- MINIBALL reinstallation expected for the 2022 run

HIE SC LINAC:

- No CM transport, modifications or repair
- Warm-up as of 15th Nov
- Cooldown as of 24th March
- Alignment verification at cold (4.5K)
- REX/HIE commissioning with stable beam as of 25th May



EBIS:

- Very well performing new gun over '20/'21 but possible cathode exchange to guarantee lifetime
- Cleaning flow meters
- Possible exchange of cooling tubes
- Minor reshuffle equipment
- Clean the HV cage

TRAP:

- Mark timing cabling
 - Refurbishment local Ion source

HIE SC LINAC REX NC LINAC: REX RF:

- Cleaning filters and amplifiers
- Flow meters verification and cleaning

REX LINAC

- Possible replacement of the various RF structures' tuner motors (reliability)
- Installation Buncher solid state amplifier
- Peak power tests during recommissiong

Beam Instrumentation:

- Replacement Si detector RFQ DBox







Slide from E. Siesling

Miniball



YETS 21/'22: key dates (low E)

- Stop of protons on the 15/11 early morning followed by 3 weeks of "winter physics" with pre-irradiated targets (06/12)
- Shutdown activities until Friday 28th of January
- Ventilation maintenance from the 31/01 to the 14/02 (no accesses but hardware commissioning and stable beam possible)
- Water cooling back as of the 04/02: stable beam commissioning
- First protons to ISOLDE (BTY line commissioning)
- Commissioning with beam (protons) until March 14th:

Start first Low E Physics











SONDJFMAMJJASONI

Ready for Cooldown

Cryo tests and tuning

REX Low Energy

Bl activities

REX RF systems

Hardware tests period

HEBT Check out start (without beam) (element

REXEBIS available for beam commiss

REXTRAP available for beam commiss

♠ Recommissioning CM1-4 finishe

♠ Connect the CM vacuum valves

REX/HIE Machine Check

a Start HIE Physics

Recommissioning CM 1-

41 days Fri 10/12/21 Fri 04/02/22

178 days Mon 15/11/21 Wed 20/07/22

20 days Mon 15/11/21 Fri 10/12/21

70 days Thu 17/02/22 Wed 25/05/22

127 days Mon 15/11/21 Tue 10/05/22

126.5 days Mon 29/11/21 Tue 24/05/22

0 days Fri 15/04/22 Fri 15/04/22

0 days Wed 25/05/22 Wed 25/05/22

ning 40 days Thu 26/05/22 Wed 20/07/22

Mon 25/04/22 Mon 25/04/22

Wed 25/05/22 Wed 25/05/22

118 days Fri 04/02/22 Wed 20/07/22 67 days Mon 07/02/22 Tue 10/05/22

0 days Fri 15/04/22

Thu 24/03/22 Wed 20/04/22

Fri 15/04/22

Cryo driven planning:

Cryo continuing over the annual Christmas break is unfortunately not possible:

A study was carried out by Cryo, SRF, CV and EL and results presented at the IEFC meeting (26th March) and ISCC (16th June).

A full warm-up and cooldown cycle with the complications of a time consuming SRF reconditioning, and beam recommissioning will need to be carried out again this shutdown '21/'22.

Key-dates and planning drivers:

- End of protons to ISOLDE / End of HIE physics: 15th Nov
- Warm-up of the HIE SC linac starts on the 15th Nov and the following weeks
- Stop of all cooling water and lock-out power supplies as of the 10th Dec
- Cryo primary water back 26th Jan, all other as of 4th Feb -> Unlocking power supplies and start of Hardware Test period
- Cryo maintenance until 21st Feb followed by recommissioning of the plant.
 Cooldown of the Cryo Modules 24th March 27th April (possibly 1wk earlier)
- Cryo Modules 1-4 recommissioning and RF reconditioning at cold (4.5K) until 25th May
- Start of machine check-out and (stable) beam commissioning as of 25th May

HIE ISOLDE (RIB) Physics start as of 20th July













7 4 ISOLDE water stop 2021-2022 36 4 Shutdown 2021/2022

Warm-up Procedure CMs

Survey activities

REX Low Energy

EPC activities

4 REX/HIE Check out and beam comm

End CM 1-4 recommissioning

REXERIS available for beam commis-

HERT Check out start (without beam) (element

REXTRAP available for beam commissioning

REX/HIE Machine Check out and beam comm.



THANK YOU FOR YOUR ATTENTION







