Development of an H⁻ plasma generator for SPL


Matthias Kronberger, CERN BE/ABP-HSL

SPL collaboration meeting, 2010/11/25

Formation of H⁻ ions

SPL is foreseen to operate with an ion source producing up to 80mA of H⁻.

However, high brightness H⁻ beams are difficult to achieve and require a sophisticated ion source !



The Linac4 source

```
Linac4 source = copy of the DESY-HERA H<sup>-</sup> source:
```

➢Volume source

 \rightarrow no Cs required

Plasma heating by an rf discharge with external2MHz antenna


 \rightarrow minimum of downtime

rf coupling with the plasma improved by ferrites surrounding the rf antenna

co-extracted electrons removed from beam by magnetic spectrometer

►I_{H-} typically ≈ 40 mA measured at DESY (Linac4 requirement: 80mA)





nominal operation parameters: DESY, Linac4 & SPL

	DESY	Linac4	LP-SPL	HP-SPL
I _H -	40	80	80	40-80
ε _n [π mm·mrad]	0.25	0.25	0.25	0.25
q _{RF,peak} [kW]	30	100	100	100
f [Hz]	3	2	2	50
Pulse length [ms]	0.15	0.4	0.9	0.4 - 0.8
Duty factor [%]	0.045	0.08	0.18	2 – 4
q _{RF,avg} [W]	13.5	80	180	2k-4k
		6 x		
	150-300x			
	130-300X			

Linac4 source temperature distribution, $P_{avg} = 80W$

- → Linac4 magnet cage, magnets & ferrites reach limit of operation at P_{avg} = 80W
- → Further extrapolation shows failure of all source components at P_{avg} = 2kW

\rightarrow Development of a new plasma generator necessary

SPL Plasma Generator

In view of these results, it was aimed to develop a new plasma generator for SPL (sLHC 7.1).


Design strategy:

preserve excellent performance of DESY/Linac4 source

→ minimize changes in plasma region

- Adaptation to operation at high average power:
 - Use of high thermal conductivity materials (Mo, AIN, ...)
 - **Optimize design** for an efficient heat flow
 - Implementation of **cooling circuits** to remove incident heat load
 - Minimization of ohmic losses to protect ferromagnetic materials


Project start: 01. April 2008 Project end: 31. March 2011



Production of prototype finished 09/2010 (in line with project schedule!)


Efficient heat removal assured by four independent, fully integrated **cooling circuits**:

ignition region (0.5l/min)




Efficient heat removal assured by four independent, fully integrated **cooling circuits**:

- ignition region (0.5l/min)
- plasma chamber (3 l/min)




Efficient heat removal assured by four independent, fully integrated **cooling circuits**:

- ignition region (0.5l/min)
- plasma chamber (3 l/min)
- rf antenna (0.5 l/min)



Efficient heat removal assured by four independent, fully integrated **cooling circuits**:

- ignition region (0.5l/min)
- plasma chamber (3 l/min)
- rf antenna (0.5 l/min)
- extraction region (2l/min)




SPL Plasma Generator: Ceramic plasma chamber

Ceramic plasma chamber:

receives > 90% of the total heat load

→ efficient removal of heat required to avoid failure due to thermal stresses






Solution:

- Material changed from Al₂O₃ to AIN (high thermal conductivity!)
- Integrated spiral cooling channel assures optimum cooling during operation
- PEEK sleeve confines cooling channel on the outside and serves also as support for antenna & ferrites

SPL Plasma Generator: Cusp Configuration & Magnet Cage


The SPL plasma generator comprises a dodecapole magnetic cusp configuration for plasma confinement and minimization of wall losses




Wall losses & confinement improve with field strength in plasma region

→ use of offset Halbach elements instead of N-S magnets (+40% field at plasma chamber wall!)






Test stand outline




Test stand outline




First results

1st November 2010:

First plasma ...



First results: rf measurements



Plasma formation &

power coupling:

60

50

40

30

20

10

0

40000

0

10000

20000

P_{FWD} [W]

30000


Power coupling [%]

equivalent plasma resistance & inductance:


M. Kronberger, SPL collaboration meeting, 2010/11/25, CERN

 \rightarrow to be investigated ...

First results: optical emission measurements



First results: optical emission measurements



Summary and Outlook

Summary:

- SPL plasma generator prototype is well on schedule
- > Test stand and plasma generator commissioning completed at low rep rate
- 1st plasma created November 2010
- plasma resistance, inductance and rf power coupling studied for different forward rf power; coupling efficiency lower than in Linac4 !
- > optical emission from plasma allows direct comparison with Linac4 source performance

to be done:


- Verification of thermal model, test of cooling systems
- mitigate problems identified during commissioning and testing (antenna sparks, gas ignition, ...)
- optimize gas pulsing + pressure and power coupling
- Final goal: Operate plasma generator at 100 kW, 50 Hz and 1.2 ms pulse length!

Thank you for your attention !


Backup slides

- Project Start: 1 April 2008
- 31 March 2009: Report Finite element thermal study of the Linac 4 design source at the final duty factor – Completed
 - determination of thermally critically components in the Linac4 plasma generator
- ✓ 31 May 2009: Report List of required improvements for the design of the high duty factor plasma generator to function at a high duty factor Completed
 - development of a design strategy in order to arrive at a plasma generator for SPL
- ✓ 30 September 2009: Report *Design of a high duty factor plasma generator* **Completed**
 - 1st design of the SPL plasma generator prototype
- 30 September 2010: Demonstrator Construction of the plasma generator and sub-systems (e.g. 2Hz RF generator, hydrogen gas injection and pumping) – Completed
 - presentation of built plasma generator prototype & test stand
- 31 March 2011: Final Report Plasma generation and study of the thermal and vacuum conditions tbd

SPL Plasma Generator: Ignition & Extraction Region




Extraction region includes **filter magnets + plasma electrodes** for optimization of H⁻ production and extraction




- Electrode assembly: Optimized heat transport by brazing of conductors on insulators
 - filter magnets:
 - positioning by AIN support
 - minimization of ohmic heating by laser-welded 0.5mm Cu boxes





SPL Plasma Generator: Plasma chamber + antenna



Plasma chamber:

receives > 90% of the total heat load


→ efficient removal of heat required

Solution:

- Material = AIN (high thermal conductivity!)
- Efficient heat removal by spiral cooling channel
- PEEK sleeve confining cooling channel on the outside

Antenna:

- ➢ 5 ½ windings
- hollow-tube Cu for internal water cooling
- insulation by molded epoxy,
 Kapton foil and shrink tubes
- rf coupling with plasma enhanced by ferrites



rf system & matching network

