



5th SPL Meeting



Summary

Working Group 1

E. Ciapala




E. Montesinos


- **Klystrons:**
 - One klystron per two cavities
 - One klystron per cavity

- **IOTs:**
 - One IOT per cavity
 - Multiple IOTs combined per cavity


- **Solid State Amplifiers (SSA)**

- **Magnetron**





- **IOTs do NOT saturate** -> margin for LLRF already included !
- **No pulsed modulator needed** -> pulses via RF drive
- pulse excursions possible
- **Better efficiency** than klystron at operating point
- Less gain
- Lower peak power




- Quasi ‘off the shelf’ IOT products
- Typical DC voltage range 40 kV
- Pulses via RF drive
- Easiest for control, individual LLRF per cavity

- **8 x 184 + 4 x 62 = 1720 IOTs**
- Production capability of such an item would be of ~ 150 per year per supplier
- It would then required ~ **12 years production**, even with three suppliers -> 4 years full production !

Total power from IOT, $\eta_{RF\ dist.} = 91\%$		160 kW
Combiners	+8.7 dB	155 kW
Circulator	-0.1 dB	1'125 kW
Power to Cavity Input		1'100 kW

Total power from IOT, $\eta_{RF\ dist.} = 93\%$		160 kW
Combiners	+5.8 dB	160 kW
Circulator	-0.1 dB	615 kW
Power to Cavity Input		600 kW



- Mandatory principle for reliability, module with:
 - Individual circulator
 - Individual DC/DC converter
 - Long life DC capacitors
- Foreseen reliable power unit = 1 kW
 - (perhaps 2 kW within coming years ?)
- $1665 \times 184 + 833 \times 62 = 358'006$ single modules
- Lifetime > 20 years with less than 1% faulty module per year:
 - turnover of $\sim 3'500$ modules per year
- No HV needed (\searrow but high current !)
- Gain = 20 dB
- Single low level per cavity

\searrow Total surface needed: $\sim 11'000$ m²

Total power from SSA (x 1600), $\eta_{RF \text{ dist.}} = 85 \%$		820 W
Combiners	+31.3 dB	815 W
Power to Cavity Input		1'100 kW
Total power from SSA (x 800), $\eta_{RF \text{ dist.}} = 87 \%$		900 W
Combiners	+28.4 dB	870 W
Power to Cavity Input		600 kW



Based on very tentative data

HP-SPL 40 mA : 0.78 ms / 50 Hz (cav #246 : 1.1 MW max)	½ 3.4 MW Klystron	1.6 MW klystron	1.125 MW MB-IOT	2 x 600 kW MB IOTs	8 x 160 kW IOT	1665 x 820 W SSA
Total	546	499	459	550	803	1084
Risk to fail	Medium	Low	High	High	Low	Low

LLRF and Layout

Wolfgang Hofle

Outline

Motivation for LLRF simulation

RF layout


Update on the simulations (→ M. Hernandez Flano)

Recent results from tests with piezo compensation at CEA Saclay test stand

Proposal for full LLRF hardware for tests at CEA Saclay


Conclusions

Layout with 2 cavities per klystron



Simulation program developed for LLRF simulations, user interface for 1, 2 and 4 cavities per klystron, for an update [see presentation by M. Hernandez Flano](#)


Optimization along Linac (Q_{ext}), filling time to minimize (peak & installed) power ?




needs update

CEA cavity tested and characterized incl. piezo tuner

Frequency [MHz]	704.4
Epk/Eacc	3.36
Bpk/Eacc [mT/(MV/m)]	5.59
r/Q [Ω]	173
G [Ω]	161
Q ₀ @ 2K Rs=8 n Ω	2 10 ¹⁰
Optimal β	0.52
Geometrical β	0.47
Total length [mm]	832
Cavity stiffness [kN/mm]	2.25
Tuning sensitivity $\Delta f/\Delta l$ [kHz/mm]	295
K _L @ k _{ext} = 30 kN/mm [Hz/(MV/m) ²]	-3.9
Δf @ 12 MV/m, k _{ext} = 30kN/mm [Hz]	-560
K _L with fixed ends	-2.7
K _L with free ends	-20.3



Measurement set-up for cavity tuner characterization in pulsed mode



modified LHC hardware:
four channels analog down conversion to IF

$$f_{RF} = 704.4 \text{ MHz}$$

$$f_{LO} = (39/40) f_{RF} = 686.79 \text{ MHz}$$

$$f_{IF} = f_{RF} - f_{LO} = 17.61 \text{ MHz}$$


digital IQ demodulation with
sampling at $4 \times f_{IF} = 70.44 \text{ MHz}$

rate of (I,Q) samples: 17.61 MS/s


actual bandwidth lower and
depending on desired precision

**Next steps → evolution to full LLRF system
with RF feedback**

Field flatness with and without piezo compensation (open loop → no RF feedback) acquired with CERN system installed at CEA Saclay




**+/- 0.7 %
field flatness
In amplitude
achieved
by using
piezos !**




use of piezo minimizes additional RF power needed to further improve the field flatness to the design target of +/- 0.5 %

Field flatness for phase, with and without piezo compensation (open loop → no RF feedback)



no piezo

+/- 8 degrees flatness
In phase,
achieved
by only using
piezo ! Needs
RF feedback
to achieve
design goal
of +/- 0.5
degrees



piezo
excited

Conclusions

new parameters need to be taken into account (shorter pulses of low/high current SPL)

move towards considering the whole accelerator with the different beam β 's

parameter variations will have a large impact on required power overhead and performance


test stands indispensable for the development of the LLRF systems, plans exist to build a test stand at CERN for 704 MHz, currently collaboration with CEA Saclay

results with piezo tuner demonstrate its capabilities to keep cavity on tune during the beam passage, essential to minimize the power requirements

having a test stand at CERN would be very important to build up momentum at CERN in the area of LLRF developments

LLRF Simulations - Mathias Hernandez Flano


High Level Diagram for Dual Cavity + Control System






Vcav Magnitude and Phase for Dual Cavity Case ($K=-1$ and -0.5)

Cavity Voltage



Voltage magnitude and
phase of vector average

Cavity Voltage Phase







Vcav Magnitude and Phase for Dual Cavity Case (Without Piezo Feed-Forward)

$$K = -0.5 \text{ Hz} \left(\frac{\text{MV}}{\text{m}} \right)^2$$

3rd Turn Magnitude




Cavity Voltage Phase




$$K = -1 \text{ Hz} \left(\frac{\text{MV}}{\text{m}} \right)^2$$

3rd Turn Magnitude




Cavity Voltage Phase




Vcav Magnitude and Phase for Dual Cavity Case (With Piezo Feed-Forward)


Cavity 1 ($K=-1 \text{ Hz} \left(\frac{MV}{m}\right)^2$)




Cavity 2 ($K=-0.5 \text{ Hz} \left(\frac{MV}{m}\right)^2$)




Effects of Source Beam Current Variation




5% variation in I_b for 40mA case requires approximately 60kW of additional power.



Transit Time Factor Variation with Relativistic Beta (SPL $\beta=1$ cavities, open loop simulation)




- Weaker beam loading will result in a higher flat-top equilibrium and less phase detuning of the cavity for the same generator power.
- Beta value taken from beam energy at beginning of SPL $\beta=1$ section.





Critical components

- Technology:
 - High voltage
 - Long pulses
 - High average power
 - High repetition rate
- Footprint:
 - 18 sqm in SM18
 - 1.4 m between cavity to cavity at ESS
- Time
 - Less than 24 month until installation in the SM18 test stand
 - Production capacity => multiple vendors.
 - Orders for the ESS modulators needs to be placed in 2014
- Cost
- Legal issues => do it right from the beginning.



SMI8



RF power system space as much, if not more, a constraint than cavity length !

ESS Modulator

Power to beam:

- Pulse repetition rate: 20 Hz
- Pulse length: 2 ms
- Peak Power: 0.9 MW
- Klystron:
 - Pulse length: 2.5 ms
 - Peak power: 1.5 MW
- Modulator
 - Pulse length: 2.8 ms
 - Peak power: 2.2 MW
 - Average power: 123 kW

ESS proposed scheme

	50 Hz	20 Hz
$\tau_{40 \text{ mA}}$	2.70E-04	2.70E-04
P_{nominal}	1.06E+06	1.06E+06
P_{gen}	1.10E+06	1.10E+06
HV pulse length	1.12E-03	2.80E-03
RF pulse length	8.20E-04	2.50E-03
$P_{\text{ac, modulator}}$	123,200	123,200

flat top at nominal cavity field

	50 Hz	20 Hz
1 cav $>V_0$	0.46	2.14
1 cav $>0.95 \cdot V_0$	0.48	2.16
1 cav $>0.90 \cdot V_0$	0.51	2.19
2 cav	0.18	1.86
2 cav $>0.95 \cdot V_0$	0.24	1.92
2 cav $>0.90 \cdot V_0$	0.29	1.97
4 cav	-1.34	0.34
4 cav $>0.95 \cdot V_0$	-0.64	1.04
4 cav $>0.90 \cdot V_0$	-0.34	1.34

SPL requested scheme

	50 Hz	20 Hz
$\tau_{40 \text{ mA}}$	2.70E-04	2.70E-04
P_{nominal}	1.06E+06	1.06E+06
P_{gen}	1.10E+06	1.10E+06
HV pulse length	1.80E-03	4.50E-03
RF pulse length	1.50E-03	4.20E-03
$P_{\text{ac, modulator}}$	198,000	198,000

flat top at nominal cavity field

	50 Hz	20 Hz
1 cav $>V_0$	1.14	3.84
1 cav $>0.95 \cdot V_0$	1.16	3.86
1 cav $>0.90 \cdot V_0$	1.19	3.89
2 cav	0.86	3.56
2 cav $>0.95 \cdot V_0$	0.92	3.62
2 cav $>0.90 \cdot V_0$	0.97	3.67
4 cav	-0.66	2.04
4 cav $>0.95 \cdot V_0$	0.04	2.74
4 cav $>0.90 \cdot V_0$	0.34	3.04

SM 18 Modulator

- Repetition rate: 20 Hz and 50 Hz
- Pulse length: 4.5 ms and 1.8 ms
- Average power: 200 kW

Competitive dialog


- Invite companies to tender
 - Selection criteria for companies (experience, turnover, facilities, etc...)
 - 1 to 3 systems
 - Functional specification as a preliminary
 - Average power: 123 kW minimum, 180 kW maximum
 - Repetition rate: 20 Hz with 50 Hz as an option
 - Awarding criteria
 - Cost
 - Maintainability
 - Delivery times
- Select 3 companies to continue discussions with.
- After discussions, the final specification will be written.

- Tender for 1-3 systems – 2 Suppliers ?
- 50 Hz as option for SPL
- Specs in preparation – Aim to order in 2011, for delivery October 2012




- Scope of the Work Package / Prerequisites
- Description of the work
 - Interfaces with other activities (cryogenics, electricity, water distribution,..)
 - Modulator
 - Klystron
 - RF power distribution system
 - Interlocks & controls
 - Auxiliaries
 - Installation
- Budget

- A Linac4 test place is now being prepared in SM18 => compatible with SPL requirements
- New helium (2K) distribution line will (might) be installed end 2011
- Need 400 V distribution line for the 50Hz modulator
- Must take into account the L4 planning in SM18 (in bunker A)





Klystrons



Option1:


- 1 MW 704 MHz tube based on CPI specs
- Specs ready (except HV interface to modulator)
- The tube exists. No development costs
- Specs do NOT include LLRF requirements

Option2:

- 3 MW 704 MHz tube including LLRF specifications
- Allows for full SPL (ESS?) RF power system distribution validation (incl. LLRF)
- More expensive! ($\approx + 1.5 MCHF$)
- *Bigger modulator !? Feasible?*

Option3:

1.5 MW 704 MHz tube – compatible ESS – common order (off the shelf ??ESS)



Circulators and RF loads specs 80% ready

Option 1: 1 circulator and 2 RF loads


- Cheapest solution
- Impact on Qext& phase and power quality (crosstalk,...) will be studied (N. Schwerg)

Option 2: 2 circulators and 3 RF loads

- Allows for full SPL (ESS?) RF power system distribution validation
- More expensive (+ 1 circulator + 1 magic T + 2 RF loads + WG +..)



Overall Plan for SPL work



Key dates & constraints to be ready for cryomodule tests in January 2013:

- Linac4 PIMS CW RF tests must be finished by end 2010 at the latest
- Installation of L4 test place in SM18: January –March 2011
- L4 tests: April 2011 –November 2012
- installation: September -October 2012
- 704 MHz equipment tests: November –December 2012
- L4 tests in SM18

2 months overlap !!! Linac 4

RF Power

- 600 kW MB-IOT is a very interesting option to study:
- Solid State options to be pursued. (easy configurability for different powers)
- Studies on waveguide tuners not presented but under way

LLRF

- Two cavity model now being used, extend results to low beta section
- Saclay Piezo tuner gives good results, essential to minimize power and enable dual cavity operation
- Source intensity stability is important, feedback will incur power loss
- Tests on CEA cavity with all feedbacks is essential to validate the modelling
- Optimization of Q_{ext} along the linac ? (cavity batches ?)

SM18, Modulators, Klystron

- Ordering of SM18 modulator on track for October 2012
- Space constraints for modulators are a concern !
- Common klystron order to arrange 1.5 MW ?
- SM18 test place planning is tight, but feasible



Spare Slides



RF System Summary - points from 5th Meeting



- Power splitting: from one klystron to 2 cavities, (use fixed 3-stub tuners instead of vector modulators),
- IOTs or solid state (<350 kW) for low beta section (one per cavity)
- Planning and preparation of RF test place in progress (consolidation with other projects at CERN is done, assembly procedure for cavities to be clarified,
- Preparation of low-power tests in vertical cryostats started, diagnostics being prepared (T-mapping, second sound, etc),
- JEMA is working on a ESS/SPL type 60 Hz modulator prototype, to be tested in 2011 at SNS,
- CERN will do design effort on Modulators up to 2014/15,
- Scandinova has done a pre-study with ESS specs, ESS is preparing tendering for test stand modulators
- LLRF code with GUI for drive of 1 versus 2 (or more) cavities with one klystron and without vector modulators, models for cavities (w. Lorentz force detuning) taking beam current & Qex variations, test data from 704 MHz cavity tests at Saclay incorporated,
- LLRF 2-cavity model w/o vector modulator seems feasible with feed-forward and piezo tuning, results now to be checked by beam dynamics,